



Maine Turnpike Authority Schedule of Items

Bridge Rehabilitation Sabattus River, Mile 85.2

Item No.	Description	Quantity	UOM
202.12	Removing Existing Structural Concrete	80.00	CY
202.1221	Removing Existing Superstructure Concrete	1.00	LS
202.123	Removing Existing Structural Steel	1.00	LS
202.202	Removing Pavement Surface	1,041.00	SY
202.2021	Removing Pavement Surface - Temporary Deck Repairs	188.00	SY
202.207	Infilling Existing S.N.A.P.s	3,104.00	LF
203.20	Common Excavation	1,999.00	CY
203.25	Granular Borrow	938.00	CY
206.08	Structural Earth Excavation - Major Structures	515.00	CY
206.09	Structural Earth Excavation - Piers	141.00	CY
304.09	Aggregate Base Course - Crushed	203.00	CY
304.10	Aggregate Subbase Course - Gravel	209.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	73.00	TON
403.21	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	386.00	TON
403.211	Hot Mix Asphalt (shimming)	72.00	TON
403.213	Hot Mix Asphalt, 12.5mm Nominal Maximum Size, Base	63.00	TON
409.15	Bituminous Tack Coat, Applied	263.00	Gal
419.30	Sawing Bituminous Pavement	1,007.00	LF
501.231	Dynamic Loading Test	3.00	EA
501.38	Steel H-Beam Pile 42 lb/ft delivered	960.00	LF
501.381	Steel H-Beam Pile 42 lb/ft in-place	960.00	LF
501.40	Steel H-Beam Pile 53 lb/ft delivered	520.00	LF
501.401	Steel H-Beam Pile 53 lb/ft in-place	520.00	LF
501.90	Pile Tips	20.00	EA
501.91	Pile Splices	32.00	EA
501.92	Pile Driving Equipment Mobilization	1.00	LS
502.21	Structural Concrete, Abutments and Retaining Walls	120.00	CY
502.23	Structural Concrete Piers	55.00	CY
502.24	Structural Concrete Piers (Placed Underwater)	58.00	CY
502.25	Structural Concrete Superstructure Slab	1.00	LS
502.264	Structural Concrete Parapets	1.00	LS
503.12	Reinforcing Steel, Fabricated and Delivered	3,207.00	LB
503.13	Reinforcing Steel, Placing	3,207.00	LB
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	97,983.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	97,983.00	LB
504.70	Structural steel, fabricated and delivered	1.00	LS
504.71	Structural steel erection	1.00	LS



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
504.721	Jacking Existing Superstructures	1.00	LS
505.09	Stud Welded Shear Connectors	1.00	LS
506.9102	Zinc-Rich Coating System (Shop Applied)	1.00	LS
506.9103	Zinc-Rich Coating System (Field Applied)	1.00	LS
506.9104	Zinc-Rich Coating System (Existing Steel)	1.00	LS
507.091	Aluminum Bridge Railing, 1 Bar	1.00	LS
508.14	High Performance Waterproofing Membrane	1.00	LS
511.07N	Cofferdam Pier 1 Northbound	1.00	LS
511.07S	Cofferdam Pier 1 Southbound	1.00	LS
511.091	Temporary Earth Support Systems	1.00	LS
515.202	Clear Protective Coating for Concrete Surfaces	660.00	SY
518.6313	Abutment and Bridge Seat Repairs	125.00	SF
518.6314	Pier Repairs	100.00	SF
518.64	THOROC 10-60 Rapid Set Mortar (50 lb bag)	70.00	EA
523.521	Bearing Removal and Installation	30.00	EA
523.5401	Laminated Elastomeric Bearings, Fixed	12.00	EA
523.5402	Laminated Elastomeric Bearings, Expansion	24.00	EA
524.40	Protective Shield - Steel Girders	985.00	SY
526.304	Temporary Concrete Barrier Type I - Bridge	300.00	LF
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
526.401	Resetting Temporary Concrete Barrier Type I - Bridge	100.00	LF
527.341	Work Zone Crash Cushions - TL-3	2.00	UNIT
602.30	Flowable Concrete Fill	5.00	CY
603.159	12 inch Culvert Pipe Option III	36.00	LF
606.1723	Bridge Transition - Type III	6.00	EA
606.178	Guardrail Beam	225.00	LF
606.352	Reflectorized Beam Guardrail Delineator	238.00	EA
606.353	Delineator Post	4.00	EA
606.354	Remove and Reset Delineator Post	2.00	EA
606.3605	Guardrail - Remove, Modify and Reset, Single Rail	781.00	LF
606.3606	Guardrail - Remove, Modify and Reset, Double Rail	300.00	LF
606.3631	Guardrail - Remove and Dispose	225.00	LF
606.48	Single Galvanized Steel Post	9.00	EA
609.15	Sloped Curb Type 1	485.00	LF
609.191	Concrete Curb Type 2	72.00	LF
610.08	Plain Riprap	607.00	CY
610.18	Stone Ditch Protection	5.00	CY



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
610.181	Temporary Stone Check Dams	6.00	CY
613.319	Erosion Control Blanket	460.00	SY
615.07	Loam	131.00	CY
618.1411	Seeding Method Number 3, Plan Quantity	11.00	Unit
619.1201	Mulch, Plan Quantity	11.00	Unit
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	1,157.00	SY
627.681	Temporary 6 Inch Painted Pavement Marking Line - Yellow or White	13,000.00	LF
627.77	Removing Existing Pavement Marking	7,174.00	SF
627.812	Temporary Raised Pavement Markers	184.00	EA
629.05	Hand Labor, Straight Time	60.00	HR
631.10	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	40.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.171	Truck - small (including operator)	35.00	HR
631.36	Foreman	20.00	HR
645.109	Remove and Reset Sign	2.00	EA
652.30	Flashing Arrow	3.00	EA
652.312	Type III Barricades	8.00	EA
652.33	Drum	106.00	EA
652.35	Construction Signs	1,366.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	50.00	HR
652.41	Portable-Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	1.00	EA
656.50	Baled Hay, in place	25.00	EA
656.60	Temporary Berms	380.00	LF
656.62	Temporary Slope Drains	60.00	LF
656.632	30 inch Temporary Silt Fence	1,403.00	LF
656.64	Boom Supp Float Silt Fence	215.00	LF
659.10	Mobilization	1.00	LS