



Maine Turnpike Authority Schedule of Items

Bridge Replacement Exit 48 Underpass Mile 48.5

Item No.	Description	Quantity	UOM
201.11	Clearing	0.50	AC
202.071	Remove Asbestos Containing Materials, Electrical Conduit	1.00	LS
202.19	Removing Existing Bridge	1.00	LS
202.202	Removing Pavement Surface	17,290.00	SY
202.206	Removing Rumble Strips	1,150.00	LF
203.20	Common Excavation	16,634.00	CY
203.25	Granular Borrow	2,641.00	CY
203.4339	Geofoam Lightweight Fill	11,133.44	CY
203.4359	Leveling Sand	1,614.63	CY
203.44	Compressible Geofoam Inclusion	2,208.00	CF
206.10	Structural Earth Excavation - Piers	209.00	CY
304.09	Aggregate Base Course - Crushed	1,418.00	CY
304.10	Aggregate Subbase Course - Gravel	5,581.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	1,478.00	TON
403.210	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	2,442.00	TON
403.211	Hot Mix Asphalt, Shimming	25.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, Base	780.00	TON
409.15	Bituminous Tack Coat, Applied	1,025.00	Gal
419.30	Sawing Bituminous Pavement	2,623.00	LF
501.231	Dynamic Loading Test	3.00	EA
501.46	Steel H-Beam Piles, 73 lb/ft delivered	7,750.00	LF
501.461	Steel H-Beam Piles, 73 lb/ft in-place	7,495.00	LF
501.52	Steel H-Beam Piles, 102 lb/ft delivered	3,060.00	LF
501.521	Steel H-Beam Piles, 102 lb/ft in-place	2,970.00	LF
501.90	Pile Tips	60.00	EA
501.903	Pile Tips - Rock Injector	9.00	EA
501.91	Pile Splices	10.00	EA
501.92	Pile Driving Equipment Mobilization	1.00	LS
502.211	Structural Concrete, Abutments and Retaining Walls	175.00	CY
502.231	Structural Concrete Piers	164.00	CY
502.251	Structural Concrete Superstructure Slab (450 CY)	1.00	LS
502.264	Structural Concrete Parapets (100 CY)	1.00	LS
502.311	Structural Concrete Approach Slab (100 CY)	1.00	LS
502.452	Structural Concrete Distribution Slab (320 CY)	1.00	LS
503.12	Reinforcing Steel, Fabricated and Delivered	7,000.00	LB
503.13	Reinforcing Steel, Placing	7,000.00	LB
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	235,400.00	LB



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
503.15	Epoxy-Coated Reinforcing Steel, Placing	235,400.00	LB
503.171	Mechanical Splice	150.00	EA
504.703	Structural steel fabricated and delivered (632,300 LB)	1.00	LS
504.71	Structural steel erection (632,300 LB)	1.00	LS
505.09	Stud Welded Shear Connectors (4820 Studs)	1.00	LS
506.9102	Zinc-Rich Coating System (Shop Applied) (14 Locations)	1.00	LS
507.091	Aluminum Bridge Railing, 1 Bar (526 LF)	1.00	LS
508.14	High Performance Waterproofing Membrane (1550 SY)	1.00	LS
511.091	Temporary Earth Support Systems (1186 SF)	1.00	LS
513.09	Slope Protection - Portland Cement Concrete	450.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	830.00	SY
518.64	THOROC 10-60 Rapid Set Mortar (50 lb bag)	10.00	EA
520.221	Expansion Device - Compression Seal with Steel Edge Beams(104 LF)	2.00	EA
520.23	Compression Seal	148.00	LF
523.52	Bearing Installation	21.00	EA
523.5302	Steel Bearing, Expansion, Sliding Plate	14.00	EA
523.5401	Laminated Elastomeric Bearings, Fixed	7.00	EA
524.40	Protective Shielding - Steel Girders	1,800.00	SY
526.306	Temporary Concrete Barrier Type I - Supplied by Authority (3000 LF)	1.00	LS
526.3121	Permanent Concrete Barrier Type II	432.00	LF
527.341	Work Zone Crash Cushions - TL-3	5.00	UNIT
603.155	12 Inch Reinforced Concrete Pipe - Class III	188.00	LF
603.192	24 Inch Corrugated HDPE Pipe	150.00	LF
603.195	24 Inch Reinforced Concrete Pipe - Class III	112.00	LF
603.212	36 Inch Corrugated HDPE Pipe	120.00	LF
603.215	36 Inch Reinforced Concrete Pipe - Class III	24.00	LF
603.28	Concrete Collar for Reinforced Concrete Pipe	4.00	EA
604.07	Catch Basin Type A1	4.00	EA
604.244	Catch Basin Type F4	1.00	EA
606.1723	Bridge Transition Type III	4.00	EA
606.1724	Bridge Transition Type IIIA	2.00	EA
606.178	Guardrail Beam	400.00	LF
606.24	Guardrail Type 3d - Single Rail	237.50	LF
606.2401	Guardrail Type 3d - Double Rail	818.75	LF
606.278	Terminal End - Anchored End	5.00	EA
606.352	Reflectorized Beam Guardrail Delineator	115.00	EA
606.353	Delineator Post	6.00	EA



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
606.354	Remove and Reset Delineator Post	12.00	EA
606.3605	Guardrail - Remove, Modify and Reset, Single Rail	3,088.00	LF
606.3606	Guardrail - Remove, Modify and Reset, Double Rail	463.00	LF
606.3631	Guardrail - Remove and Dispose	401.00	LF
606.471	Single Offset Block - W-Beam	28.00	EA
606.48	Single Galvanized Steel Post	28.00	EA
606.80	Guardrail 350 Fleat Terminal	2.00	EA
606.81	Guardrail 350 Fleat Terminal - Remove and Reset	2.00	EA
609.15	Sloped Curb Type 1	1,175.00	LF
609.191	Concrete Curb Type 2	96.00	LF
609.31	Curb Type 3	640.00	LF
610.08	Plain Riprap	609.00	CY
610.18	Stone Ditch Protection	59.00	CY
610.181	Temporary Stone Check Dam	29.00	CY
610.28	Stream Bed Gravel	264.00	CY
613.319	Erosion Control Blanket	11,440.00	SY
615.07	Loam	1,614.00	CY
618.1411	Seeding Method Number 3, Plan Quantity	131.00	Unit
619.1201	Mulch, Plan Quantity	131.00	Unit
619.1202	Temporary Mulch (131 Units)	1.00	LS
620.58	Erosion Control Geotextile	1,921.00	SY
620.70	HDPE Geomembrane	7,739.94	SY
621.546	Deciduous Shrubs, 2'-3', Group A	472.00	EA
621.800	Establishment Period-Two Year	1.00	LS
621.89	Planting Sonotubes	472.00	EA
626.11	Precast Concrete Junction Box	13.00	EA
626.22	Non-Metallic Conduit	2,700.00	LF
626.32	24 Inch Foundation	3.00	EA
627.681	Temporary 6 Inch Painted Pavement Marking Line - Yellow or White	8,445.00	LF
627.73	Temporary 6 inch Pavement Marking Tape	3,450.00	LF
627.77	Removing Existing Pavement Marking	1,283.00	SF
629.05	Hand Labor, Straight Time	60.00	HR
631.10	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	40.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.171	Truck - small (including operator)	35.00	HR
631.32	Culvert Cleaners (including Operator)	10.00	HR



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
631.36	Foreman	20.00	HR
634.2081	Remove and Reset Light Standard	3.00	EA
634.2156	#6 AWG THHN Wire	2,200.00	LF
634.2157	#6 AWG THHN Ground Wire	1,100.00	LF
639.191	Field Office, Type B	1.00	EA
645.105	Remove and Stack Sign	11.00	EA
645.109	Remove and Reset Sign	9.00	EA
645.292	Regulatory, Warning, Confirmation and Route Marker Assembly Signs Type II	2.00	EA
652.30	Flashing Arrow	3.00	EA
652.312	Type III Barricades	5.00	EA
652.33	Drum	114.00	EA
652.34	Cone	20.00	EA
652.35	Construction Signs	2,039.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	50.00	HR
652.411	Portable-Changeable Message Sign	6.00	EA
652.45	Truck Mounted Attenuator	1.00	EA
656.50	Baled Hay, in place	25.00	EA
656.60	Temporary Berms	525.00	LF
656.62	Temporary Slope Drains	200.00	LF
656.632	30 inch Temporary Silt Fence	4,464.00	LF
659.10	Mobilization	1.00	LS
822.341	Ductile Iron Water Main	1.00	LS