



Maine Turnpike Authority Schedule of Items

Bridge Superstructure Replacement Chandler Mill Road Underpass MM 70.2

Item No.	Description	Quantity	UOM
202.101	Removing Existing Superstructure	1.00	LS
202.12	Removing Existing Structural Concrete	27.00	CY
202.202	Removing Pavement Surface	458.00	SY
203.20	Common Excavation	866.00	CY
203.43391	Expanded Polystyrene Fill (EPS) Geofoam Fill - Owner Supplied	146.00	CY
203.4359	Leveling Sand	80.00	CY
304.10	Aggregate Subbase Course - Gravel	999.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	159.00	TON
403.210	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	229.00	TON
403.213	Hot Mix Asphalt, 12.5mm Nominal Maximum Size, Base	93.00	TON
409.15	Bituminous Tack Coat, Applied	274.00	Gal
419.30	Sawing Bituminous Pavement	704.00	LF
502.21	Structural Concrete, Abutments and Retaining Walls	43.00	CY
502.25	Structural Concrete Superstructure Slab (140 CY)	1.00	LS
502.49	Structural Concrete Curbs and Sidewalks (21 CY)	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	60,000.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	60,000.00	LB
504.703	Structural steel, fabricated and delivered (99,500 LB)	1.00	LS
504.71	Structural steel erection (99,500 LB)	1.00	LS
505.09	Stud Welded Shear Connectors (2,484 EA.)	1.00	LS
506.9102	Zinc Rich Coating System (Shop Applied) (8 LOCATIONS)	1.00	LS
506.9103	Zinc Rich Coating System (Field Applied) (1 LOCATION)	1.00	LS
507.0821	Steel Bridge Rail, 3 Bar (454LF)	1.00	LS
508.141	High Performance Waterproofing Membrane (530 SY)	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	270.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	295.00	SY
518.6313	Abutment and Bridge Seat Repairs	28.00	SF
518.63132	Abutment Crack Repairs	100.00	LF
518.6314	Pier Repairs	457.00	SF
520.221	Expansion Device - Locking Compression Seal with Steel Edge Beams	2.00	EA
523.521	Bearing Installation	20.00	EA
523.5401	Laminated Elastomeric Bearings, Fixed	4.00	EA
523.5402	Laminated Elastomeric Bearings, Expansion	8.00	EA
523.5404	PTFE Elastomeric Bearings, Expansion	8.00	EA
524.40	Protective Shield - Steel Girders	800.00	SY
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (40LF)	1.00	LS



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
527.341	Work Zone Crash Cushions TL-3	2.00	EA
606.1728	W-Beam to 3-Bar Bridge Rail Transition	4.00	EA
606.178	Guardrail Beam	88.00	LF
606.23	Guardrail Type 3c - Single Rail	275.00	LF
606.353	Delineator Post	6.00	EA
606.354	Delineator Post - Remove and Reset	2.00	EA
606.3605	Guardrail - Remove, Modify and Reset, Single Rail	875.00	LF
606.3631	Guardrail - Remove and Dispose	88.00	LF
606.471	Single Offset Block - W-Beam	7.00	EA
606.48	Single Galvanized Steel Post	7.00	EA
606.80	Guardrail 350 FLEAT Terminal	4.00	EA
607.1631	Snow Fence	452.00	LF
607.17	Chain Link Fence - 6 Foot	340.00	LF
607.23	Chain Link Fence Gate	2.00	EA
607.32	Bracing Assembly Type I - Metal Posts	8.00	EA
607.33	Bracing Assembly Type II - Metal Posts	5.00	EA
609.11	Vertical Curb Type 1	79.00	LF
609.31	Curb Type 3	56.00	LF
610.18	Stone Ditch Protection	51.00	CY
610.181	Temporary Stone Check Dams	4.00	CY
613.319	Erosion Control Blanket	2,763.00	SY
615.07	Loam	360.00	CY
618.1411	Seeding Method Number 3, Plan Quantity	29.00	Unit
619.1201	Mulch, Plan Quantity	29.00	Unit
619.1202	Temporary Mulch	1.00	LS
619.1401	Erosion Control Mix	3.00	CY
620.58	Erosion Control Geotextile	180.00	SY
620.6012	HDPE Geomembrane	300.00	SY
627.712	4 Inch White or Yellow Pavement Marking Line	800.00	LF
629.05	Hand Labor, Straight Time	60.00	HR
631.10	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	40.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.171	Truck - small (including operator)	20.00	HR
631.32	Culvert Cleaner (including operators)	10.00	HR
631.36	Foreman	20.00	HR
645.109	Remove and Reset Sign	1.00	EA



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
652.30	Flashing Arrow	2.00	EA
652.312	Type III Barricades	12.00	EA
652.33	Drum	42.00	EA
652.34	Cone	20.00	EA
652.35	Construction Signs	1,301.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	50.00	HR
652.41	Portable Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	2.00	EA
656.50	Baled Hay, in place	20.00	EA
656.60	Temporary Berms	600.00	LF
656.62	Temporary Slope Drains	138.00	LF
656.632	30 inch Temporary Silt Fence	1,959.00	LF
659.10	Mobilization	1.00	LS