



# Maine Turnpike Authority Schedule of Items

Saint Lawrence & Atlantic RR Overpass Bridge Repairs Mile 74.5  
 Kittyhawk Avenue Underpass Bridge Repairs  
 Mile 75

Item No.	Description	Quantity	UOM
202.191	Removing Existing Drainage Troughs	1.00	LS
202.202	Removing Pavement Surface	1,120.00	SY
202.2021	Removing Pavement Surface - Bridge Deck	2,155.00	SY
202.206	Removing Rumble Strips	1,600.00	LF
203.25	Granular Borrow	80.00	CY
206.082	Structural Earth Excavation - Major Structures	60.00	CY
304.10	Aggregate Subbase Course - Gravel	40.00	CY
403.209	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (sidewlaks, drives, islands & incidentals)	30.00	TON
403.210	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	415.00	TON
403.211	Hot Mix Asphalt (shimming)	35.00	TON
409.15	Bituminous Tack Coat, Applied	140.00	Gal
419.30	Full Depth Bituminous Sawcut	1,210.00	LF
503.171	Corroded Reinforcing Steel - Repair Per Detail 1	40.00	EA
503.172	Corroded Reinforcing Steel - Repair Per Detail 2	340.00	EA
504.80	Replacement Bridge Drain	4.00	EA
506.9104	Zinc Rich Coating System (Field Painting)	1.00	LS
507.095	Aluminum Bridge Railing- Splice Modification	44.00	EA
508.14	High Performance Waterproofing Membrane	2,155.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	1,600.00	SY
518.391	Repairing Granite Curb Joint and Bedding Mortar	660.00	LF
518.6313	Abutment and Bridge Seat Repairs	60.00	SF
518.6314	Pier Repairs	125.00	SF
518.6315	Fascia and Fascia Overhang Repairs	995.00	SF
518.64	Temporary Bridge Repairs - Deck Patching (50 lb. Bag)	40.00	EA
518.80	Partial Depth Concrete Deck Repairs	1,760.00	SF
518.81	Full Depth Concrete Deck Repairs	145.00	SF
520.2211	Bridge Joint Modifications - Type I	4.00	EA
520.2212	Bridge Joint Modifications - Type II	2.00	EA
523.521	Bearing Removal and Installation	20.00	EA
523.522	Pier Bearing Modification	20.00	EA
523.5304	Steel Bearings, Rocker	20.00	EA
524.7211	Jacking Existing Superstructures	1.00	LS
524.40	Protective Shield - Steel Girders	115.00	SY
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
526.34	Permanent Concrete Transition Barrier	8.00	EA
527.341	Work Zone Crash Cushions - TL-3	2.00	UNIT



## Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
602.30	Flowable Concrete Fill	12.00	CY
606.1721	Bridge Transition - Type I	6.00	EA
606.178	Guardrail Beam	100.00	LF
606.3605	Guardrail - Remove, Modify and Reset, Single Rail	650.00	LF
606.3606	Guardrail - Remove, Modify and Reset, Double Rail	100.00	LF
606.3631	Guardrail - Remove and Dispose	80.00	LF
613.319	Erosion Control Blanket	1,320.00	SY
617.30	Composted Bark Mix	160.00	CY
618.1411	Seeding Method Number 3, Plan Quantity	17.00	UNIT
619.1201	Mulch, Plan Quantity	17.00	UNIT
619.1202	Temporary Mulch	1.00	LS
627.4072	Reflectorized Plastic, White or Yellow Pavement Marking	860.00	LF
627.68	Temporary 4 Inch Pavement Marking Line, Yellow or White	6,300.00	LF
627.681	Temporary 6 Inch Pavement Marking Line, Yellow or White	12,800.00	LF
627.712	4 Inch White or Yellow Pavement Marking Line	3,000.00	LF
627.77	Removing Pavement Markings	6,700.00	SF
627.812	Temporary Raised Pavement Markers	850.00	EA
629.05	Hand Labor, Straight Time	60.00	MH
631.10	Air Compressor (including operator)	30.00	HR
631.11	Air Tool (including operator)	60.00	HR
631.171	Truck-small (including operator)	15.00	HR
631.36	Foreman	30.00	HR
652.30	Flashing Arrow Board	3.00	EA
652.312	Type III Barricades	6.00	EA
652.33	Drum	315.00	EA
652.35	Construction Signs	2,500.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	170.00	MH
652.39	Portable Light Tower	2.00	EA
652.41	Portable-Changable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	1.00	EA
656.50	Baled Hay, in place	20.00	EA
656.532	30 inch Temporary Silt Fence	640.00	LF
659.10	Mobilization	1.00	LS