



Maine Turnpike Authority

Schedule of Items

BRIDGE REPLACEMENT MAXWELL ROAD UNDERPASS MILE 90.0

Item No.	Description	Quantity	UOM
201.11	Clearing	0.75	AC
202.19	Removing Existing Bridge	1.00	LS
202.202	Removing Pavement Surface	340.00	SY
203.2	Common Excavation	450.00	CY
203.24	Common Borrow	4,100.00	CY
203.25	Granular Borrow	610.00	CY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	630.00	CY
304.1	Aggregate Subbase Course - Gravel	1,100.00	CY
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	280.00	Ton
403.209	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	10.00	Ton
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size Base and Intermediate Base Course	240.00	Ton
409.15	Bituminous Tack Coat, Applied	120.00	Gal
501.231	Dynamic Loading Test	2.00	EA
501.54	Steel H-beam Piles 117 lb/ft, delivered	316.00	LF
501.541	Steel H-beam Piles 117 lb/ft, in place	316.00	LF
501.9	Pile Tips	8.00	EA
501.91	Pile Splices	8.00	EA
501.92	Pile Driving Equipment Mobilization	1.00	LS
502.219	Structural Concrete, Abutments and Retaining Walls	1.00	LS
502.239	Structural Concrete, Pier	1.00	LS
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges	1.00	LS
502.31	Structural Concrete, Approach Slab	1.00	LS
502.49	Structural Concrete Curbs and Sidewalks	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	95,400.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	95,400.00	LB
504.702	Structural steel, fabricated and delivered, welded	1.00	LS
504.71	Structural steel erection	1.00	LS
505.08	Shear Connectors	1.00	LS
506.9102	Zinc Rich Coating System (Shop Applied)	1.00	LS
507.0821	Steel Bridge Railing, 3 Bar	1.00	LS
508.14	High Performance Waterproofing Membrane	1.00	LS
508.15	Membrane Waterproofing	1.00	LS
511.091	Temporary Earth Support Systems	1.00	LS
512.081	French Drains	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.202	Clear Protective Coating for Concrete Surfaces	510.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
520.23	Asphaltic Plug Joint	56.00	LF
523.52	Bearing Installation	4.00	EA
523.5401	Laminated Elastomeric Bearings, Fixed	4.00	EA
524.4	Protective Shielding - Steel Girders	765.00	SY
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
527.341	Work Zone Crash Cushions - TL-3	2.00	Unit
603.152	12 inch HDPE Pipe Liner	320.00	LF
603.159	12 inch Culvert Pipe Option III	35.00	LF
603.28	Concrete Collar	1.00	EA
606.1728	W-Beam to 3-Bar Bridge Rail Transition	4.00	EA
606.231	Guardrail Type 3c -15 ft radius and less	25.00	LF
606.232	Guardrail Type 3c - over 15 ft radius	62.50	LF
606.233	Guardrail Type 3c - Single Rail, 7 Foot Posts	775.00	LF
606.265	Terminal End - Single Rail - Galvanized Steel	2.00	EA
606.356	Underdrain Delineator Post	8.00	EA
606.3561	Delineator Post - Remove and Reset	10.00	EA
606.3605	Guardrail - Remove, Modify, and Reset Single Rail	540.00	LF
606.47	Single Wood Post	1.00	EA
606.81	Tangent Guardrail Terminal - Energy Absorbing	2.00	EA
607.09	Woven Wire Fence - Metal Posts	380.00	LF
607.17	Chain Link Fence - 6 Foot	500.00	LF
607.23	Chain Link Fence Gate	2.00	EA
607.32	Bracing Assembly Type I - Metal Posts	12.00	EA
607.33	Bracing Assembly Type II - Metal Posts	10.00	EA
607.431	Snow Fence	200.00	LF
609.11	Vertical Curb Type 1	120.00	LF
610.08	Plan Riprap	150.00	CY
610.18	Stone Ditch Protection	110.00	CY
613.319	Erosion Control Blanket	4,450.00	SY
615.07	Loam	520.00	CY
618.141	Seeding Method Number 3	42.00	Unit
619.1201	Mulch, Plan Quantity	42.00	Unit
619.1202	Temporary Mulch	1.00	LS
619.1401	Erosion Control Mix	43.00	CY
620.58	Erosion Control Geotextile	550.00	SY
627.73	Temporary 6 Inch Pavement Marking Tape	1,450.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	840.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
629.05	Hand Labor, Straight Time	100.00	HR
631.1	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	40.00	HR
631.12	All Purpose Excavator (including operator)	50.00	HR
631.171	Truck - small (including operator)	30.00	HR
631.172	Truck - large (including operator)	40.00	HR
631.36	Foreman	50.00	HR
639.19	Field Office, Type B	1.00	EA
645.106	Demount Regulatory, Warning, Confirmation and Route Marker Assembly Sign	5.00	EA
645.108	Demount Pole	5.00	EA
645.116	Reinstall Regulatory, Warning, Confirmation and Route Marker Assembly Sign	1.00	EA
645.118	Reinstall Pole	1.00	EA
645.272	Regulatory, Warning, and Bridge Number Signs, Type I - Supplied by Authority	4.00	EA
652.3	Flashing Arrow	2.00	EA
652.312	Type III Barricades	6.00	EA
652.33	Drum	110.00	EA
652.34	Cone	20.00	EA
652.35	Construction Signs	1,300.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	300.00	HR
652.41	Portable Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	100.00	CD
656.5	Baled Hay, in place	20.00	EA
656.6	Temporary Berms	1,100.00	LF
656.62	Temporary Slope Drains	340.00	LF
656.632	30 inch Temporary Silt Fence	1,650.00	LF
659.1	Mobilization	1.00	LS