



Maine Turnpike Authority Schedule of Items

SACO TOLL PLAZA LANE ADDITION - (INTERCHANGE 36 SACO TOLL PLAZA) &
VARIABLE MESSAGE SIGN (VMS) RELOCATION
TO MAINLINE IN ARUNDEL (MM 28.3)

Item No.	Description	Quantity	UOM
202.1271	REMOVING EXISTING BITUMINOUS PAVEMENT	200.00	CY
202.203	PAVEMENT BUTT JOINTS	350.00	SY
203.2	COMMON EXCAVATION	4,905.00	CY
203.24	COMMON BORROW	90.00	CY
203.25	GRANULAR BORROW	15.00	CY
203.43	GEOFOAM LIGHTWEIGHT FILL	2,550.00	CY
203.45	LEVELING SAND	500.00	CY
206.082	STRUCTURAL EARTH EXCAVATION - MAJOR STRUCTURES	30.00	CY
304.09	AGGREGATE BASE COURSE - CRUSHED	450.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	1,800.00	CY
403.207	HOT MIX ASPHALT, 19.0 mm NOMINAL MAXIMUM SIZE	450.00	T
403.208	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE, SURFACE	300.00	T
403.209	HOT MIX ASPHALT, 9.5 mm NOMINAL MAXIMUM SIZE (ISLAND & INCIDENTALS)	70.00	T
403.21	HOT MIX ASPHALT, 9.5 mm	100.00	T
403.213	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE, BASE	400.00	T
409.15	BITUMINOUS TACK COAT, APPLIED	200.00	G
419.3	SAWING BITUMINOUS PAVEMENT	1,300.00	LF
502.111	STRUCTURAL CONCRETE FOOTING	10.00	CY
502.266	STRUCTURAL CONCRETE PLAZA SLAB ON GRADE	25.00	CY
502.56	CONCRETE FILL	10.00	CY
503.14	EPOXY - COATED REINFORCING STEEL, FABRICATED AND DELIVERED	1,350.00	LB
503.15	EPOXY - COATED REINFORCING STEEL, PLACING	1,350.00	LB
503.18	GLASS FIBER REINFORCED POLYMER (GFRP) REINFORCING BARS, FABRICATED AND DELIVERED	1,810.00	LB
503.19	GLASS FIBER REINFORCED POLYMER (GFRP) REINFORCING BARS, PLACING	1,810.00	LB
503.9	SYNTHETIC FIBER REINFORCEMENT	175.00	LB
506.3	SHOP COATING OF STRUCTURAL STEEL	1.00	LS
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	210.00	SY
515.23	EPOXY OVERLAY	12.00	SY
518.51	REPAIR OF UPWARD FACING SURFACES - BELOW REINFORCING STEEL, <200 mm	22.00	SF
526.306	TEMPORARY CONCRETE BARRIER, TYPE I - SUPPLIED BY AUTHORITY (1,810 LF)	1.00	LS
526.311	PERMANENT CONCRETE BARRIER TYPE I	70.00	LF
526.342	PERMANENT CONCRETE BARRIER TYPE I TRANSITION	2.00	EA
527.342	WORK ZONE CRASH CUSHIONS TL-2	1.00	EA
602.3	FLOWABLE CONCRETE FILL	15.00	CY
603.152	16 INCH HDPE PIPE	38.00	LF
603.175	18 INCH REINFORCED CONCRETE PIPE - CLASS III	23.00	LF



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
604.248	CATCH BASIN TYPE F6	1.00	EA
606.1724	BRIDGE TRANSITION - TYPE III (MODIFIED)	2.00	EA
606.24	GUARDRAIL TYPE 3D - SINGLE RAIL	1,850.00	LF
606.2401	GUARDRAIL TYPE 3D - DOUBLE RAIL	1,225.00	LF
606.2652	TERMINAL END - REMOVE AND STACK	3.00	EA
606.278	TERMINAL END - ANCHORED END	2.00	EA
606.279	TERMINAL END - ANCHORED END, THRIE BEAM	1.00	EA
606.352	REFLECTORIZED BEAM GUARDRAIL DELINEATOR	18.00	EA
606.353	DELINEATOR POST	9.00	EA
606.354	DELINEATOR POST - REMOVE AND RESET	6.00	EA
606.3605	GUARDRAIL - REMOVE, MODIFY AND RESET, SINGLE RAIL	112.50	LF
606.3631	GUARDRAIL - REMOVE AND DISPOSE	1,612.50	LF
606.48	SINGLE GALVANIZED STEEL POST	16.00	EA
606.65	GUARDRAIL THRIE BEAM - SINGLE RAIL	150.00	LF
606.701	ASYMMETRICAL THRIE BEAM TRANSITION	3.00	EA
606.8	GUARDRAIL 350 FLEAT TERMINAL	1.00	EA
609.11	VERTICAL CURB TYPE 1	430.00	LF
609.12	VERTICAL CURB TYPE 1 - CIRCULAR	20.00	LF
609.234	TERMINAL CURB TYPE 1 - 4 FT	2.00	EA
609.441	CURBING REMOVE AND STACK	100.00	LF
610.08	PLAIN RIPRAP	10.00	CY
610.18	STONE DITCH PROTECTION	10.00	CY
613.319	EROSION CONTROL BLANKET	4,350.00	SY
615.07	LOAM	510.00	CY
618.1401	SEEDING METHOD NUMBER 2, PLAN QUANTITY	10.00	UN
618.1411	SEEDING METHOD NUMBER 3, PLAN QUANTITY	34.00	UN
619.1201	MULCH, PLAN QUANTITY	44.00	UN
619.1202	TEMPORARY MULCH	34.00	UN
620.58	EROSION CONTROL GEOTEXTILE	40.00	SY
620.625	CELLULAR CONFINEMENT SYSTEM	300.00	SY
620.7	HDPE GEOMEMBRANE	2,900.00	SY
626.11	PRECAST CONCRETE JUNCTION BOX	1.00	EA
626.31	18 in FOUNDATION	8.00	EA
626.32	24 in FOUNDATION	1.00	EA
626.331	30-INCH DIA., GREATER THAN 8-FEET LONG, AND ALL 36-INCH AND 42-INCH DIA. FOUNDATIONS	13.00	CY
626.36	REMOVE OR MODIFY CONCRETE FOUNDATION	8.00	EA



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
626.38	GROUND MOUNTED CABINET FOUNDATION	1.00	EA
627.73	TEMPORARY 6 INCH PAVEMENT MARKING TAPE	4,900.00	LF
627.731	TEMPORARY 6 INCH BLACK PAVEMENT MARKING TAPE	2,900.00	LF
629.05	HAND LABOR, STRAIGHT TIME	28.00	HR
631.1	AIR COMPRESSOR (INCLUDING OPERATOR)	8.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.00	HR
631.13	BULLDOZER (INCLUDING OPERATOR)	20.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	40.00	HR
631.22	FRONT END LOADER (INCLUDING OPERATOR)	20.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	20.00	HR
631.36	FOREMAN	8.00	HR
631.5	JACKHAMMER (AIR TOOL INCLUDING OPERATOR)	8.00	HR
631.51	BUCKET TRUCK	8.00	HR
631.52	SCISSOR LIFT	8.00	HR
631.53	ELECTRICIAN	8.00	HR
631.54	ELECTRICIAN'S APPRENTICE	8.00	HR
634.25	SERVICE POLE COMPLETE WITH CABINET AND CONTROLS	1.00	EA
643.712	LANE USE SIGNAL	1.00	EA
645.105	REMOVE AND STACK SIGN	6.00	EA
645.109	REMOVE AND RESET SIGN	18.00	EA
645.123	REMOVAL, DISASSEMBLY AND RELOCATION OF VMS AND SUPPORTING STRUCTURE	1.00	LS
645.161	BREAKAWAY DEVICE SINGLE POLE	1.00	EA
645.289	STEEL H-BEAM POLES	1,150.00	LB
645.303	REMOVE AND RESET DELINEATOR	6.00	EA
645.403	INSTALLATION OF TYPE 1 SIGNS	13.00	EA
652.3	FLASHING ARROW	3.00	EA
652.312	TYPE III BARRICADES	3.00	EA
652.33	DRUM	150.00	EA
652.35	CONSTRUCTION SIGNS	1,529.50	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE - CHANGEABLE MESSAGE SIGN	2.00	EA
652.45	TRUCK MOUNTED ATTENUATOR	10.00	CD
655.012	INSTALLATION OF CASH LANE CONTROLLER CABINET	1.00	EA
655.02	DVAS MOUNT INSTALLATION	1.00	EA
655.04	INSTALLATION OF SENSOR LOOPS	1.00	LS
655.05	INSTALLATION OF AVI ANTENNAS	1.00	EA



Maine Turnpike Authority Schedule of Items

Item No.	Description	Quantity	UOM
655.07	TRAFFIC CONTROL PEDESTAL PREPARATION WORK	1.00	EA
655.11	#10 AWG WIRE	450.00	LF
655.12	#12 AWG WIRE	600.00	LF
655.13	#14 AWG WIRE	50.00	LF
655.14	4pr/24 (CATEGORY 5e) CABLE	1,700.00	LF
655.16	FIBER OPTIC CABLE - 6 FIBER	600.00	LF
655.17	IVIS HOMERUN LOOP CABLE (IMSA 50-2 #16)	400.00	LF
655.203	1 1/2" SCHEDULE 80 PVC CONDUIT	50.00	LF
655.2031	2" SCHEDULE 80 PVC CONDUIT	175.00	LF
655.204	3" SCHEDULE 80 PVC CONDUIT	10.00	LF
655.2071	2" GALVANIZED RIGID METAL CONDUIT	190.00	LF
655.2102	2" LIQUID TIGHT METALLIC FLEX CONDUIT	20.00	LF
655.223	TYPE D PULL BOX OUTDOOR CANOPY	4.00	EA
655.81	KEY SWITCH	2.00	EA
656.5	BALED HAY, IN PLACE	60.00	EA
656.6	TEMPORARY BERMS	600.00	LF
656.62	TEMPORARY SLOPE DRAINS	30.00	LF
656.632	30 INCH TEMPORARY SILT FENCE	1,750.00	LF
659.1	MOBILIZATION	1.00	LS
669.01	BOLLARD	4.00	EA
800.501	TOLL GANTRY INSTALLATION	1.00	LS