



Maine Turnpike Authority *Schedule of Items*

Pavement Rehabilitation & Clear Zone Improvements MM 54.5 to 64.4 Eagles Nest Road Bridge Repairs MM 60.8 Hunts Hill Road Bridge Repairs MM 61.6

Item No.	Description	Quantity	UOM
202.12	Removing Existing Structural Concrete	34.00	CY
202.127	Removing of Existing Bituminous Pavement (660SY)	1.00	LS
202.202	Removing Pavement Surface - Mainline	121,164.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	4,200.00	SF
202.205	Rumble Strips	155,510.00	EA
203.2	Common Excavation	775.00	CY
203.21	Rock Excavation	50.00	CY
203.241	Common Borrow, Truck Measure	450.00	CY
203.25	Granular Borrow	136.00	CY
205.51	Widening of Existing Shoulder	265.00	LF
205.53	Widening of Existing Shoulder Pavement	350.00	LF
304.1	Aggregate Subbase Coarse - Gravel	150.00	CY
403.208	Hot Mix Asphalt, 12.5mm- RAP	7,150.00	Ton
403.2081	Hot Mix Asphalt, 12.5mm (Polymer Modified)- RAP	30,190.00	Ton
403.2084	Hot Mix Asphalt, 12.5mm Nominal Maximum Size(sidewalks,drives,islands & incidentals	261.00	Ton
403.212	Hot Mix Asphalt, 4.75mm Nominal Maximum Size	7,227.00	Ton
403.213	Hot Mix Asphalt, 12.5mm	88.00	Ton
407.08	Berm Dropoff Correction-Grindings	3,100.00	Ton
407.081	Berm Correction	35,195.00	LF
409.15	Bituminous Tack Coat - Applied	26,119.00	GAL
409.151	Bituminous Tack Coat - Applied, Bridge	59.00	GAL
419.3	Sawing Bituminous Pavement	2,415.00	LF
419.301	Sawing and Sealing Bituminous Pavement	320.00	LF
424.323	Asphalt Rubber Fiber Crack Filler-Applied	22,000.00	Pound
427.09	Pavement Crack Repair	30,460.00	LF
429.341	Grid/Fabric Composite Pavement Interlayer	43,000.00	SF
459.06	Bituminous Concrete Waterway - Type I	3.00	EA
459.061	Bituminous Concrete Waterway - Type II	9.00	EA
502.21	Structural Concrete, Abutments & Retaining Walls	38.00	CY
502.26	Structural Concrete Super. Slab on St Br (2CY)	1.00	LS
503.14	Epoxy -coated Reinforcing Steel, Fab & Delivered	6,400.00	LB
503.15	Epoxy -coated Reinforcing Steel, Placing	6,400.00	LB
506.99	Clean and Paint Existing Bearings	20.00	EA
507.095	Aluminum Bridge Railing - Splice Modification	56.00	EA
508.141	High Performance Waterproofing Membrane (Hunts Hill Rd)(660 SY)	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	710.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
515.202	Clear Protective Coating for Concrete Surfaces	620.00	SY
518.39	Granite Curb Joint Mortar and Bedding Mortar Repair	615.00	LF
518.4	Epoxy Injected Crack Repairs	205.00	LF
518.43	Parapet Joint Repair	260.00	LF
518.51	Repair of Upward Facing Concrete Surfaces - Below Reinforcing Steel <8 Inches	360.00	SF
518.511	Full Depth Concrete Repair	60.00	SF
518.6	Repair of Vertical Surfaces < 8 inches	245.00	SF
518.7	Repair of Overhead Surfaces < 8 Inches	95.00	SF
520.2211	Expansion Device Modifications(47.5 FT)	2.00	EA
520.231	Expansion Device - Asphaltic Plug for Crack Control	95.00	LF
520.232	Expansion Device - Asphaltic Plug Joint	145.00	LF
523.5211	Bearing Rehabilitation, Rocker Bearings	20.00	EA
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority(660 LF)	1.00	LS
527.303	Energy Absorbing System (CAT) – Remove and Reset	1.00	EA
527.341	Work Zone Crash Cushions - TL-3	2.00	UNIT
603.155	12 inch Reinforced Concrete Pipe - Class III	78.00	LF
603.159	12 inch Culvert Pipe Option III	105.00	LF
603.179	18 inch Culvert Pipe Option III	105.00	LF
603.209	30 inch Culvert Pipe Option III	65.00	LF
603.229	42 inch Culvert Pipe Option III	20.00	LF
603.28	Concrete Collar	19.00	EA
604.184	Rebuild Catch Basin to Grade - Type II	32.00	EA
604.186	Rebuild Catch Basin to Grade - Type IV	8.00	EA
606.1723	Bridge Transition - Type III	6.00	EA
606.1724	Bridge Transition - Type III Modified	1.00	EA
606.178	Guardrail Beam	650.00	LF
606.24	Guardrail Type 3d Single Rail	200.00	LF
606.2401	Guardrail Type 3d Double Rail	450.00	LF
606.2652	Terminal End - Remove and Stack	31.00	EA
606.278	Terminal End - Anchored End	31.00	EA
606.279	Terminal End - Anchored End, Thrie Beam	1.00	EA
606.352	Reflectorized Beam Guardrail Delineator	1,500.00	EA
606.353	Delineator Post	120.00	EA
606.355	Delineator Post - Remove and Stack	120.00	EA
606.3605	Guardrail - Remove, Modify and Reset Type 3d Single Guardrail	25.00	LF
606.3606	Guardrail - Remove, Modify and Reset Type 3d Double Guardrail	545.00	LF
606.3621	Guardrail Adjust - Single Rail	29,850.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
606.3622	Guardrail Adjust - Double Rail	37,915.00	LF
606.3631	Guardrail - Remove and Dispose	130.00	LF
606.47	Single Wooden Post	10.00	EA
606.471	Single Offset Block - W Beam	90.00	EA
606.472	Single Offset Block - Thrie Beam	10.00	EA
606.48	Single Galvanized Steel Post	100.00	EA
606.63	Thrie Beam Rail Beam	50.00	LF
606.65	Guardrail Thrie Beam - Single Rail	25.00	LF
606.701	Asymmetrcial Thrie Beam Transition	5.00	EA
606.754	Widen Shoulder for Guardrail 350 Flared Terminal	2.00	EA
606.755	Modify Widen Shoulder for Guardrail 350 Flared Terminal	19.00	EA
606.8	Guardrail - 350 Flared Terminal	4.00	EA
606.82	Guardrail - Remove and Stack Existing Crash End	4.00	EA
606.83	Remove and Reset Existing Crash End	1.00	EA
607.431	Snow Fence	676.00	LF
609.13	Vertical Bridge Curb, Type 1	130.00	LF
609.191	Concrete Curb, Type 2	84.00	LF
610.08	Plain RipRap	75.00	CY
610.18	Stone Ditch Protection	160.00	CY
613.319	Erosion Control Blanket	975.00	SY
615.07	Loam	73.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	146.00	UNIT
619.1201	Mulch, Plan Quantity	176.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	460.00	SY
627.712	White or Yellow Pavement Marking Line	179,100.00	LF
627.713	Broken White Pavement Marking Line	89,550.00	LF
627.77	Removing Existing Pavement Markings	1,150.00	SF
627.78	Temporary Pavement Marking Line, Yellow or White	320,550.00	LF
627.812	Temporary Raised Pavement Markers	24,663.00	EA
627.94	Pavement Marking Tape	3,318.00	LF
627.941	Pavement Marking Tape, Dotted White Lane Line, 6-inch Width	906.00	LF
629.05	Hand Labor, Straight Time	240.00	HR
631.1	Air Compressor (including operator)	50.00	HR
631.11	Air Tool (including operator)	20.00	HR
631.12	All Purpose Excavator (including operator)	60.00	HR
631.172	Truck - Large (including operator)	60.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.36	Foreman	40.00	HR
645.109	Remove and Stack Sign	2.00	EA
652.3	Flashing Arrow	6.00	EA
652.331	Drums	1.00	LS
652.34	Cone	60.00	EA
652.35	Construction Signs	6,988.00	SF
652.351	Construction Signs - Supplied by Authority	250.00	SF
652.3611	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flagger	2,110.00	HR
652.3911	Maintenance of Traffic Control Devices (Eagles Nest)	1.00	LS
652.3912	Maintenance of Traffic Control Devices (Hunts Hill)	1.00	LS
652.3913	Maintenance of Traffic Control Devices (Bennett & Kittyhawk)	1.00	LS
652.411	Portable - Changeable Message Sign with Radar Unit	4.00	EA
652.45	Truck Mounted Attenuator	217.00	CD
656.5	Baled Hay, in place	220.00	EA
656.6	Temporary Berms	225.00	LF
656.62	Temporary Slope Drains	225.00	LF
656.632	30 inch Temporary Silt Fence	3,150.00	LF
659.1	Mobilization	1.00	LS