



Maine Turnpike Authority *Schedule of Items*

Bridge Repair, High Street Underpass, Mile 103.6

Superstructure Replacement, Winthrop Road Underpass, Mile 108.3

Item No.	Description	Quantity	UOM
202.1	Removing Existing Superstructure - Property of Contractor	1.00	LS
202.17	Removing Existing Structural Concrete	1.00	LS
202.202	Removing Pavement Surface	1,100.00	SY
203.2	Common Excavation	1,233.00	CY
203.25	Granular Borrow	105.00	CY
304.1	Aggregate Subbase Course - Gravel	1,295.00	CY
402.208	Hot Mix Asphalt, 12.5 mm Nominal Max. Size	200.00	TON
403.209	Hot Mix Asphalt, 9.5 mm Nominal Max. Size (Sidewalks, Drives, Islands and Incidentals)	10.00	TON
403.21	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	340.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Course)	415.00	TON
409.15	Bituminous Tack Coat - Applied	240.00	GAL
419.3	Sawing Bituminous Paving	150.00	LF
502.21	Structural Concrete, Abutments and Retaining Walls	42.00	CY
502.23	Structural Concrete Piers	28.00	CY
502.25	Structural Concrete Superstructure Slab	1.00	LS
502.58	Ultra High Performance Structural Concrete	1.00	LS
502.701	Bridge Drain Grate Modification	4.00	EA
503.12	Reinforcing Steel, Fabricated and Delivered	1,721.00	LB
503.13	Reinforcing Steel, Placing	1,721.00	LB
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	13,748.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	13,748.00	LB
504.702	Structural Steel Fabricated and Delivered, Welded	1.00	LS
504.71	Structural Steel Erection	1.00	LS
505.08	Shear Connectors	1.00	LS
506.9102	Zinc-Rich Coating System (Shop Applied)	1.00	LS
507.0821	Steel Bridge Railing, 3 Bar	1.00	LS
508.14	High Performance Waterproofing Membrane	1.00	LS
508.15	Membrane Waterproofing	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	1,315.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	425.00	SY
518.1	Abutment Repairs	54.00	SF
518.2	Pier Repairs	302.00	SF
518.4	Epoxy Injection Crack Repair	6.00	LF
518.8	Partial Depth Concrete Deck Repair	600.00	SF
520.2211	Expansion Joint Modification	2.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
520.23	Asphaltic Plug Joint	66.00	LF
520.234	Expansion Device - Silicone Coated and Pre-compressed Seal	96.00	LF
523.52	Bearing Installation	25.00	EA
523.5402	Laminated Elastomeric Bearings, Expansion	10.00	EA
523.5404	PTFE Elastomeric Bearings, Expansion	15.00	EA
524.4	Protective Shielding - Steel Girders	960.00	SY
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
527.341	Work Zone Crash Cushions -TL-3	4.00	UNIT
534.7601	Precast Approach Slab	1.00	LS
535.302	Full Depth Precast Concrete Deck Panels	1.00	LS
603.179	18" Culvert Pipe Option III - HDPE Only	90.00	LF
606.1728	W-Beam to 3-Bar Bridge Rail Transition	4.00	EA
606.244	Guardrail Type 3d - Single Rail, 7 Foot Posts	937.50	LF
606.241	Guardrail Type 3d - 15' Radius and Less	12.50	LF
606.242	Guardrail Type 3d - Over 15' Radius	12.50	LF
606.259	Anchorage Assembly	1.00	EA
606.265	Terminal End - Single Rail - Galvanized Steel	1.00	EA
606.353	Reflectorized Flexible Guardrail Marker	3.00	EA
606.356	Underdrain Delineator Post	4.00	EA
606.8	Guardrail FLEAT 350 Terminal	1.00	EA
606.81	Tangent Guardrail Terminal - Energy Absorbing	1.00	EA
607.17	Chain Link Fence - 6 Foot	375.00	LF
607.23	Chain Link Fence Gate	2.00	EA
607.2326	Remove and Reset Pipe Entry Gate	1.00	EA
607.32	Bracing Assembly Type I - Metal Posts	12.00	EA
607.33	Bracing Assembly Type II - Metal Posts	8.00	EA
607.431	Snow Fence	224.00	LF
609.11	Vertical Curb Type I	148.00	LF
610.08	Plain Riprap	248.00	CY
610.18	Stone Ditch Protection	47.00	CY
613.319	Erosion Control Blanket	1,100.00	SY
615.07	Loam	275.00	CY
618.14	Seeding Method Number 2	9.50	UNIT
618.141	Seeding Method Number 3	13.00	UNIT
619.1201	Mulch - Plan Quantity	22.50	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	340.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
627.712	4 inch White or Yellow Pavement Marking Line	1,000.00	LF
629.05	Hand Labor, Straight Time	90.00	HR
631.12	All Purpose Excavator (Including Operator)	30.00	HR
631.171	Truck - Small (Including Operator)	30.00	HR
631.36	Foreman	30.00	HR
639.18	Field Office, Type A	1.00	EA
645.272	Regulatory, Warning and Bridge Number Signs, Type 1 - Supplied by Authority	2.00	EA
652.3	Flashing Arrow	4.00	EA
652.312	Type III Barricades	18.00	EA
652.33	Drum	180.00	EA
652.34	Cone	100.00	EA
652.35	Construction Signs	3,257.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flagger	100.00	HR
652.41	Portable Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	140.00	CD
656.5	Baled Hay, in place	15.00	EA
656.632	30 inch Temporary Silt Fence	2,050.00	LF
659.1	Mobilization	1.00	LS