



Maine Turnpike Authority *Schedule of Items*

Exit 47 Intersection Improvements: Pavement Rehabilitation & Clear Zone Improvements Mile 47

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface	28,600.00	SY
202.2026	Removing Pavement Surface - Drainage Paths	530.00	SF
202.203	Pavement Butt Joint	625.00	SY
203.2	Common Excavation	780.00	CY
203.24	Common Borrow	1,836.00	CY
304.1	Aggregate Subbase Course - Gravel	560.00	CY
304.14	Aggregate Base Course - Type A	190.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	350.00	TON
403.2081	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, (Polymer Modified) RAP	2,630.00	TON
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size (Shim)	150.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate)	2,280.00	TON
409.15	Bituminous Tack Coat, Applied	2,520.00	GAL
419.3	Sawing Bituminous Pavement	1,200.00	LF
470.08	Berm Dropoff Correction - Grindings	180.00	TON
520.23	Asphaltic Plug Joint	195.00	LF
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (1020')	1.00	LS
527.341	Work Zone Crash Cushion TL-2	3.00	EA
603.175	18 inch Reinforced Concrete Pipe Class III	8.00	LF
603.209	30 inch Culvert Pipe Option III	144.00	LF
603.28	Concrete Collar	1.00	EA
604.18	Adjusting Manhole or Catch Basin to Grade	4.00	EA
604.184	Rebuild Catch Basin to Grade - Type II	4.00	EA
606.13	31" W-Beam Guardrail - Mid-Way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	150.00	LF
606.131	31" W-Beam Guardrail - Mid-Way Splice (8' Steel Post, 8" Offset Blocks, Single Faced)	450.00	LF
606.1723	Bridge Transition Type III	1.00	EA
606.178	Guardrail Beam	200.00	LF
606.352	Reflectorized Beam Guardrail Delineator	230.00	EA
606.3531	Permanent Flexible Delineator Post	4.00	EA
606.355	Delineator Post - Remove and Stack	10.00	EA
606.356	Underdrain Delineator Post	3.00	EA
606.3621	Guardrail Adjust - Single Rail	3,200.00	LF
606.3622	Guardrail Adjust - Double Rail	2,050.00	LF
606.471	Single Offset Block-W-Beam	200.00	EA
606.791	Guardrail - Flared Terminal - 31" W-Beam Guardrail	1.00	EA
610.08	Plain Riprap	100.00	CY
610.181	Temporary Stone Check Dam	4.00	CY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
613.319	Erosion Control Blanket	1,900.00	SY
615.07	Loam	420.00	CY
618.14	Seeding Method Number 2	34.00	UNIT
619.1201	Mulch - Plan Quantity	34.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	240.00	SY
626.12	36" x 24" x 21" Quazite Junction Box	4.00	EA
626.21	Metallic Conduit	50.00	LF
626.22	Non-metallic Conduit	3,000.00	LF
626.223	Horizontal Directional Drilled Conduit	600.00	LF
626.332	30-inch Diameter, greater than 8-feet long, and all 36-inch and 42-inch Diameter Foundations	4.00	CY
626.35	Controller Cabinet Foundation	1.00	EA
627.712	White or Yellow Pavement Marking Line	19,650.00	LF
627.75	White or Yellow Pavement and Curb Marking	1,500.00	SF
627.77	Remove Existing Pavement Markings	1,900.00	SF
627.78	Temporary Pavement Marking Line, White or Yellow	8,150.00	LF
627.812	Temporary Raised Pavement Marker	1,100.00	EA
627.9411	Pavement Marking Tape - Dotted White or Yellow Lane Line - 6" Width	100.00	LF
629.05	Hand Labor, Straight Time	50.00	HR
631.1	Air Compressor (Including Operator)	40.00	HR
631.11	Air Tool (Including Operator)	40.00	HR
631.12	All Purpose Excavator (including operator)	50.00	HR
631.17	Truck - Large (Including Operator)	50.00	HR
631.32	Culvert Cleaner (Including operator)	8.00	HR
631.36	Foreman	50.00	HR
634.175	Replacement LED Fixture, Installed	1.00	EA
643.72	Temporary Traffic Signal	1.00	LS
643.8	Traffic Signal Modifications at Exit 47 and Rand Road	1.00	LS
643.83	Video Detection System Supply and Install	1.00	LS
645.1061	Relocate Existing Sign Assembly and Post	4.00	EA
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type II	72.00	SF
652.3	Flashing Arrow Board	1.00	EA
652.33	Drum	55.00	EA
652.34	Cone	55.00	EA
652.35	Construction Signs	3,200.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.38	Flaggers	240.00	HR
652.381	Traffic Officers	20.00	HR
652.41	Portable-Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	10.00	CD
655.16	Fiber Optic Cable	650.00	LF
655.165	Fiber Optic Splice Panel	2.00	EA
656.5	Baled Hay, in place	15.00	EA
656.6	Temporary Berms	1,100.00	LF
656.632	30" Temporary Silt Fence	1,150.00	LF
659.1	Mobilization	1.00	LS