



# Maine Turnpike Authority *Schedule of Items*

## Bridge Superstructure Replacement Small Road Underpass MM 95.1

Item No.	Description	Quantity	UOM
201.11	Clearing	0.80	AC
202.1	Removing Existing Superstructure	1.00	LS
202.12	Removing Existing Structural Concrete	42.00	CY
202.191	Removing Existing Drain Troughs	1.00	LS
202.202	Removing Pavement Surface	390.00	SY
203.2	Common Excavation	950.00	CY
203.24	Common Borrow	400.00	CY
203.43	Geofoam Lightweight Fill	125.00	CY
203.45	Leveling Sand	15.00	CY
206.082	Structural Earth Excavation - Major Structures	160.00	CY
304.1	Aggregate Subbase Course - Gravel	1,080.00	CY
403.21	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	270.00	Ton
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size, Base	220.00	Ton
409.15	Bituminous Tack Coat, Applied	105.00	Gal
502.219	Structural Concrete, Abutments and Retaining Walls	1.00	LS
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges	1.00	LS
502.49	Structural Concrete Curbs and Sidewalks	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	94,000.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	94,000.00	LB
504.702	Structural Steel, Fabricated and Delivered, Welded	1.00	LS
504.71	Structural Steel Erection	1.00	LS
505.08	Shear Connectors	1.00	LS
506.9102	Zinc Rich Coating System (Shop Applied)	1.00	LS
507.0821	Steel Bridge Railing, 3 Bar	1.00	LS
508.13	Sheet Waterproofing Membrane	1.00	LS
508.14	High Performance Waterproofing Membrane	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	350.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	430.00	SY
518.1	Abutment Repairs	20.00	SF
518.2	Pier Repairs	430.00	SF
518.3	Abutment Seat Refacing	8.00	CY
520.221	Expansion Devices - Locking Compression Seal with Steel Edge Beams	2.00	EA
523.521	Bearing Removal and Installation	20.00	EA
523.5401	Laminated Elastomeric Bearings, Fixed	4.00	EA
523.5402	Laminated Elastomeric Bearings, Expansion	16.00	EA
524.4	Protective Shielding - Steel Girders	1,210.00	SY



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
526.306	Temporary Concrete Barrier, Type I, Supplied by Authority	1.00	LS
527.34	Work Zone Crash Cushions	1.00	Unit
606.1728	W-Beam to 3-Bar Bridge Rail Transition	4.00	EA
606.244	Guardrail Type 3d - Single Rail, 7 Foot Posts	1,000.00	LF
606.3531	Delineator Post	8.00	EA
606.47	Single Wood Post	1.00	EA
606.78	Low Volume Guardrail End - Type 3	4.00	EA
607.17	Chain Link Fence - 6 Foot	210.00	LF
607.23	Chain Link Fence Gate	2.00	EA
607.32	Bracing Assembly Type I - Metal Posts	8.00	EA
607.33	Bracing Assembly Type II - Metal Posts	4.00	EA
607.431	Snow Fence	336.00	LF
609.11	Vertical Curb Type 1	80.00	LF
610.18	Stone Ditch Protection	53.00	CY
613.319	Erosion Control Blanket	1,600.00	SY
615.07	Loam	220.00	CY
618.141	Seeding Method Number 3	18.00	Unit
619.1201	Mulch, Plan Quantity	18.00	Unit
619.1202	Temporary Mulch	1.00	LS
619.1401	Erosion Control Mix	72.00	CY
620.58	Erosion Control Geotextile	170.00	SY
620.625	Cellular Confinement System	990.00	SY
620.7	HDPE Geomembrane	250.00	SY
629.05	Hand Labor, Straight Time	60.00	HR
631.1	Air Compressor (including operator)	20.00	HR
631.11	Air Tool (including operator)	40.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.171	Truck - small (including operator)	20.00	HR
631.36	Foreman	20.00	HR
645.109	Remove and Reset Sign	3.00	EA
652.3	Flashing Arrow	2.00	EA
652.312	Type III Barricades	10.00	EA
652.33	Drum	90.00	EA
652.34	Cone	20.00	EA
652.35	Construction Signs	1,500.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	150.00	HR



## Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.41	Portable Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	100.00	CD
656.5	Baled Hay, in place	20.00	EA
656.6	Temporary Berms	1,320.00	LF
656.62	Temporary Slope Drains	190.00	LF
656.632	30 inch Temporary Silt Fence	1,960.00	LF
659.1	Mobilization	1.00	LS