



Maine Turnpike Authority *Schedule of Items*

Southern Bridge Repairs - MM 10.6, 11.9 & 13.8 Southern Culvert Repairs - MM 15.2, 31.25 & 32.2

Item No.	Description	Quantity	UOM
202.17	Removing Existing Structural Concrete	1.00	LS
202.202	Removing Pavement Surface	1,420.00	SY
202.203	Pavement Butt Joints	220.00	SY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	25.00	CY
304.1	Aggregate Subbase Course - Gravel	20.00	CY
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	245.00	Ton
409.15	Bituminous Tack Coat, Applied	51.00	GA
502.219	Structural Concrete, Abutments and Retaining Walls	1.00	LS
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges	1.00	LS
502.701	Bridge Drain Grate Modification	3.00	EA
502.702	Replace Bridge Drain	1.00	EA
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	5,800.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	5,800.00	LB
504.8	Structural Steel Repair	1.00	LS
508.141	High Performance Waterproofing Membrane (Mountain Road)	1.00	LS
508.142	High Performance Waterproofing Membrane (N. Berwick Road)	1.00	LS
508.15	Membrane Waterproofing	1.00	LS
511.07	Cofferdam (Ogunquit River)	1.00	LS
511.071	Cofferdam (Second Thacher Brook)	1.00	LS
511.072	Cofferdam (Third Thacher Brook)	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	725.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	801.00	SY
518.1	Abutment Repairs	280.00	SF
518.17	Culvert Repairs	60.00	SF
518.171	Special Concrete Repair	1.00	LS
518.2	Pier Repairs	160.00	SF
518.391	Repairing Granite Curb Joint and Bedding Mortar	11.00	LF
518.4	Epoxy Injection Crack Repair	365.00	LF
518.43	Parapet Joint Repair	130.00	LF
518.48	Reseal Joints	400.00	LF
518.49	Repointing Wingwall Joints	95.00	LF
518.511	Full Depth Concrete Repair	30.00	SF
518.75	Fascia and Overhang Repairs	18.00	SF
518.8	Partial Depth Concrete Deck Repairs	375.00	SF
518.92	Slope Protection Repairs	45.00	SF
518.93	Parapet Repairs	200.00	SF
518.94	Curb Repairs	10.00	SF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
518.98	Reset Coping Blocks	4.00	EA
520.23	Asphaltic Plug Joint	87.00	LF
520.234	Expansion Device - Silicone Coated and Pre-Compressed Seal	15.00	LF
520.2401	Bridge Joint Modification - Type 1	1.00	LS
525.4	Repointing Coping Blocks	74.00	LF
526.34	Permanent Concrete Transition Barrier	4.00	EA
606.1721	Bridge Transition - Type I	4.00	EA
606.48	Single Galvanized Steel Post	16.00	EA
627.712	White or Yellow Pavement Marking Line	500.00	LF
629.05	Hand Labor, Straight Time	110.00	HR
631.1	Air Compressor (Including Operator)	100.00	HR
631.11	Air Tool (Including Operator)	110.00	HR
631.12	All Purpose Excavator (Including Operator)	60.00	HR
631.17	Truck - Small (Including Operator)	110.00	HR
631.36	Foreman	110.00	HR
639.18	Field Office, Type A	1.00	EA
652.3691	Maintenance of Traffic Control for Mountain Road Underpass	1.00	LS
652.3692	Maintenance of Traffic Control for Clay Hill Road Underpass	1.00	LS
652.3693	Maintenance of Traffic Control for N. Berwick Road Underpass	1.00	LS
652.3694	Maintenance of Traffic Control for Ogunquit River Culvert	1.00	LS
652.3695	Maintenance of Traffic Control for Second Thacher Brook Culvert	1.00	LS
652.3696	Maintenance of Traffic Control for Third Thacher Brook Culvert	1.00	LS
652.41	Portable-Changeable Message Sign	4.00	EA
656.751	Temporary Soil Erosion and Water Pollution Control (Mountain Road)	1.00	LS
656.752	Temporary Soil Erosion and Water Pollution Control (N. Berwick Road)	1.00	LS
656.753	Temporary Soil Erosion and Water Pollution Control (Ogunquit River)	1.00	LS
656.754	Temporary Soil Erosion and Water Pollution Control (Second Thacher Brook)	1.00	LS
656.755	Temporary Soil Erosion and Water Pollution Control (Third Thacher Brook)	1.00	LS
659.1	Mobilization	1.00	LS