



# Maine Turnpike Authority

## *Schedule of Items*

### Pavement Rehabilitation & Clear Zone Improvements MM 98.0 TO MM 102.17

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface - Mainline	119,250.00	Squar
202.2026	Removing Pavement Surface - Drainage Paths	3,552.00	Squar
202.205	Rumble Strips	35,750.00	Each
202.206	Removing Rumble Strips	950.00	Linea
203.2	Common Excavation	2,398.00	Cubic
203.25	Granular Borrow	1,184.00	Cubic
304.1	Aggregate Subbase Course - Gravel	498.00	Cubic
304.14	Aggregate Base Course - Type A	233.00	Cubic
403.207	Hot Mix Asphalt, 19.0mm Nominal Maximum Size RAP	547.00	Ton
403.208	Hot Mix Asphalt, 12.5mm Nominal Maximum Size RAP	345.00	Ton
403.2081	Hot Mix Asphalt, 12.5mm Nominal Maximum Size, (Polymer Modified) RAP	9,100.00	Ton
403.20811	Hot Mix Asphalt, 12.5mm Nominal Maximum Size, (Polymer Modified) RAP (70E-34)	500.00	Ton
403.2084	Hot Mix Asphalt, 12.5mm Nominal Maximum Size (sidewalks,drives,islands,and incidentals)	50.00	Ton
403.212	Hot Mix Asphalt, 4.75mm Nominal Maximum Size	4,000.00	Ton
407.08	Berm Dropoff Correction - Grindings	802.00	Ton
407.081	Berm Correction	3,200.00	Linea
409.15	Bituminous Tack Coat, Applied	9,397.00	Gallo
409.3	Saw Cutting Bituminous Pavement	571.00	Linea
424.323	Asphalt Rubber Mastic Crack Filler-Applied	11,500.00	Pound
429.341	Grid/Fabric Composite Pavement Interlayer	7,200.00	Squar
526.306	Temporary Concrete Barrier Type I - Supplied by Authority ( 590 LF)	1.00	Lump
527.301	Energy Absorbing System (CAT) - New	2.00	Each
527.341	Work Zone Crash Cushions - TL-3	1.00	Each
603.155	12 Inch Reinforced Concrete Pipe - Class III	36.00	Linea
603.199	24 Inch Culvert Pipe Option III	60.00	Linea
603.28	Concrete Collar	3.00	Each
604.184	Rebuild Catch Basin to Grade - Type II	15.00	Each
605.105	6 inch Underdrain Type C	65.00	Each
606.353	Delineator Post - New	5.00	Each
606.354	Delineator Post - Remove and Reset	8.00	Each
606.3605	Guardrail - Remove, Modify, and Replace - Single Rail	200.00	Linea
606.3606	Guardrail - Remove, Modify, and Replace - Double Rail	475.00	Linea
606.3621	Guardrail Adjust - Single Rail	500.00	Linea
606.3622	Guardrail Adjust - Double Rail	200.00	Linea
606.3631	Guardrail - Remove and Dispose	175.00	Linea
606.471	Single Offset Block - W- Beam	10.00	Each



# Maine Turnpike Authority

## *Schedule of Items*

Item No.	Description	Quantity	UOM
606.48	Single Galvanized Steel Post	5.00	Each
606.791	Guardrail 350 Flared Terminal - Remove and Reset	1.00	Each
610.08	Plain Riprap	82.00	Cubic
613.319	Erosion Control Blanket	543.00	Squar
615.07	Loam	38.00	Cubic
618.1401	Seeding Method #2, Plan	3.00	Unit
619.12	Mulch	3.00	Unit
619.1202	Temporary Mulch	1.00	Lump
620.58	Erosion Control Geotextile	400.00	Squar
627.712	White or Yellow Pavement Marking Line	74,540.00	Linea
627.713	Broken White Pavement Marking Line	35,750.00	Linea
627.77	Removing Existing Pavement Marking	4,750.00	Squar
627.78	Temporay Pavement Marking Line, White or Yellow	228,780.00	Linea
627.812	Temporary Raised Pavement Markers	9,990.00	Each
627.94	Pavement Marking Tape 6 inch	1,344.00	Linea
627.941	Pavement Marking Tape - Dotted White Lane Line 6 inch	111.00	Linea
629.05	Hand Labor, Straight Time	50.00	Hour
631.1	Air Compressor (Including Operator)	40.00	Hour
631.11	Air Tool (Including Operator)	40.00	Hour
631.12	All Purpose Excavator (including Operator)	50.00	Hour
631.172	Truck - Large (including Operator)	50.00	Hour
631.36	Foreman	50.00	Hour
645.109	Remove and Reset Sign	1.00	Each
652.3	Flashing Arrow Board	4.00	Each
652.312	Type III Baracades	2.00	Each
652.331	Drum	1.00	Lump
652.35	Construction Signs	4,205.00	Squar
652.361	Maintenance of Traffic Control Devices	1.00	Lump
652.41	Portable-Changeable Message Sign	2.00	Each
652.4	Truck Mounted Attenuator	60.00	Cal.
652.451	Automated Trailer Mounted Speed Limit Sign	2.00	Each
652.46	Temporary Portable Rumble Strips ( 1 Unit = 3 strips)	60.00	Unit
656.632	30 inch Temporary Silt Fence	700.00	Linea
659.103	Mobilization (Paving)	1.00	Lump