



Maine Turnpike Authority

Schedule of Items

Emergency Vehicle Ramps Blackstrap Road Underpass Mile 52.0

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface	940.00	SY
203.2	Common Excavation	5,090.00	CY
203.25	Granular Borrow	210.00	CY
304.1	Aggregate Subbase Course - Gravel	2,400.00	CY
304.14	Aggregate Base Course - Type A	600.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	160.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Surface)	480.00	TON
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size (Shim)	30.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate)	480.00	TON
409.15	Bituminous Tack Coat, Applied	310.00	GAL
419.3	Sawing Bituminous Pavement	1,260.00	LF
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (840')	1.00	LS
527.431	Work Zone Crash Cushion	1.00	EA
603.155	12 inch Reinforced Concrete Pipe Class III	4.00	LF
603.159	12 inch Culvert Pipe Option III	72.00	LF
603.179	18 inch Culvert Pipe Option III	38.00	LF
603.199	24 inch Culvert Pipe Option III	80.00	LF
603.219	36 inch Culvert Pipe Option III	72.00	LF
603.28	Concrete Collar	1.00	EA
606.1301	31" W-Beam Guardrail - Mid-Way Splice (Steel Post, 8" Offset Blocks, Single Faced)	250.00	LF
606.1305	31" W-Beam Guardrail - Mid-Way Splice Flared Terminal (31" Height)	1.00	EA
606.242	Guardrail Type 3d - Over 15 feet Radius	25.00	LF
606.278	Terminal End - Anchored End	1.00	EA
606.3561	Delineator Post - Remove and Reset	2.00	EA
606.369	Guardrail - Remove and Stack	385.00	LF
606.48	Single Galvanized Post	2.00	EA
607.17	Chain Link Fence - 6'	139.00	LF
607.2325	Pipe Entry Gate	3.00	EA
607.2326	Remove and Reset Pipe Entry Gate	1.00	EA
607.32	Bracing Assembly, Type I - Metal Post	4.00	EA
607.33	Bracing Assembly, Type II - Metal Post	2.00	EA
610.08	Plain Riprap	475.00	CY
610.18	Stone Ditch Protection	196.00	CY
610.181	Temporary Stone Check Dams	55.00	CY
613.319	Erosion Control Blanket	1,220.00	SY
615.07	Loam	630.00	CY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
618.14	Seeding Method Number 2	52.00	UNIT
619.1201	Mulch, Plan Quantity	52.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	2,570.00	SY
621.043	Evergreen Tr (6'-8') GP A	50.00	EA
626.13	18" x 12" x 18" Quazite Junction Box	9.00	EA
626.32	24 inch Diameter Foundation	4.00	EA
629.05	Hand Labor, Straight Time	10.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.171	Truck - small (including operator)	10.00	HR
631.36	Foreman	10.00	HR
634.2041	Luminaires	1.00	EA
634.208	Remove and Reset Light Standard	3.00	EA
634.21	Conventional Light Standard	1.00	EA
634.2156	#6 AWG THHN Wire	2,620.00	LF
634.2157	#6 AWG THHN Ground Wire	1,320.00	LF
645.1061	Relocate Existing Sign Assembly and Post	1.00	EA
652.3	Flashing Arrow	1.00	EA
652.33	Drum	87.00	EA
652.34	Cone	87.00	EA
652.35	Construction Signs	650.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	300.00	HR
652.45	Truck Mounted Attenuator	10.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	10.00	CD
655.2031	2" Schedule 80 PVC conduit	1,350.00	LF
655.204	3" Schedule 80 PVC conduit	280.00	LF
656.5	Baled Hay, in place	30.00	EA
656.632	30" Temporary Silt Fence	3,200.00	LF
659.1	Mobilization	1.00	LS