



Maine Turnpike Authority *Schedule of Items*

Bridge Repairs (MM 45.4, 58.3, 66.2)

Superstructure Replacement - Dutton Hill Road (Mile 59.9)

Item No.	Description	Quantity	UOM
202.1	Removing Existing Superstructure - Property of Contractor	1.00	LS
202.17	Removing Existing Structural Concrete (Dutton Hill Road)	1.00	LS
202.171	Removing Existing Structural Concrete (Weymouth Road)	1.00	LS
202.202	Removing Pavement Surface	3,425.00	SY
202.203	Pavement Butt Joints	190.00	SY
203.2	Common Excavation	2,880.00	CY
203.21	Rock Excavation	1,150.00	CY
203.24	Common Borrow	2,262.00	CY
203.25	Granular Borrow	190.00	CY
304.1	Aggregate Subbase Course - Gravel	2,500.00	CY
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	96.00	TON
403.209	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	12.00	TON
403.21	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size	1,070.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	750.00	TON
409.15	Bituminous Tack Coat - Applied	452.00	GAL
411.1	Untreated Aggregate Surface Course, Truck Measure	4.00	CY
419.3	Sawing Bituminous Pavement	1,940.00	LF
502.21	Structural Concrete, Abutments and Retaining Walls	81.00	CY
502.23	Structural Concrete Piers	15.00	CY
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges	1.00	LS
502.49	Structural Concrete Curbs and Sidewalks	1.00	LS
502.701	Bridge Drain Grate Modification	8.00	EA
502.7011	Bridge Drain Grate Modification (Running Hill Road)	1.00	EA
502.91	Sealing Deck Construction Joints	73.00	LF
503.12	Reinforcing Steel, Fabricated and Delivered	440.00	LB
503.13	Reinforcing Steel, Placing	440.00	LB
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	77,400.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	77,400.00	LB
504.7	Structural Steel Fabricated and Delivered (Dutton Hill Road)	1.00	LS
504.701	Structural Steel Fabricated and Delivered (Weymouth Road)	1.00	LS
504.71	Structural Steel Erection (Dutton Hill Road)	1.00	LS
504.711	Structural Steel Erection (Weymouth Road)	1.00	LS
505.08	Shear Connectors	1.00	LS
506.9102	Zinc Rich Coating System (Shop Applied)	1.00	LS
506.9103	Zinc Rich Coating System (Field Applied)	1.00	LS
507.0821	Steel Bridge Railing, 3 Bar	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
507.0928	Aluminum Bridge Rail - 3 Bar Post Remove and Reset	1.00	EA
507.095	Aluminum Bridge Railing - Splice Retrofit	3.00	EA
508.14	High Performance Waterproofing Membrane (Running Hill Road)	1.00	LS
508.141	High Performance Waterproofing Membrane (Blackstrap Road)	1.00	LS
508.142	High Performance Waterproofing Membrane (Dutton Hill Road)	1.00	LS
508.143	High Performance Waterproofing Membrane (Weymouth Road)	1.00	LS
508.15	Membrane Waterproofing (Dutton Hill Road)	1.00	LS
508.151	Membrane Waterproofing (Weymouth Road)	1.00	LS
509.201	Culvert Sliplining	67.00	LF
514.06	Curing Box for Concrete Cylinders	2.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	1,850.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	1,020.00	SY
518.1	Abutment Repairs	385.00	SF
518.2	Pier Repairs	970.00	SF
518.391	Repairing Granite Curb Joint and Bedding Mortar	292.00	LF
518.4	Epoxy Injection Crack Repair	88.00	LF
518.8	Partial Depth Concrete Deck Repairs	1,780.00	SF
520.2211	Expansion Joint Modification	2.00	EA
520.23	Asphaltic Plug Joint	151.00	LF
520.234	Expansion Device - Silicone Coated and Pre-compressed Seal	18.00	LF
520.2341	Bridge Joint Replacement - Silicone Coated and Pre-compressed Seal	63.00	LF
523.1201	Reset Steel Bearings	8.00	EA
523.52	Bearing Installation	45.00	EA
523.521	Bearing Removal	20.00	EA
523.5402	Laminated Elastomeric Bearings, Expansion	10.00	EA
523.54021	PTFE Elastomeric Bearings, Expansion	15.00	EA
524.4	Protective Shielding - Steel Girders	870.00	SY
524.7212	Jacking Existing Superstructure (Blackstrap Road)	1.00	LS
524.72121	Jacking Existing Superstructure (Weymouth Road)	1.00	LS
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority	1.00	LS
526.34	Permanent Concrete Transition Barrier	4.00	EA
527.341	Work Zone Crash Cushions - TL-3	6.00	UNIT
603.159	12 inch Culvert Pipe Option III	41.00	LF
603.179	18 inch Culvert Pipe Option III	190.00	LF
606.1721	Bridge Transition - Type I	4.00	EA
606.1728	W-Beam to 3-Bar Bridge Rail Transition	4.00	EA
606.241	Guardrail Type 3d - 15 ft. Radius and Less	50.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
606.242	Guardrail Type 3d - over 15 feet Radius	225.00	LF
606.244	Guardrail Type 3d - Single Rail, 7 foot Posts	2,312.50	LF
606.265	Terminal End - Single Rail - Galvanized Steel	3.00	EA
606.278	Terminal End - Anchored End	1.00	EA
606.353	Reflectorized Flexible Guardrail Marker	18.00	EA
606.78	Low Volume Guardrail End - Type 3	2.00	EA
606.79	Guardrail 350 Flared Terminal	6.00	EA
606.81	Tangent Guardrail Terminal – Energy Absorbing	1.00	EA
607.17	Chain Link Fence - 6 Foot	1,010.00	LF
607.23	Chain Link Fence Gate	5.00	EA
607.2325	Pipe Entry Gate	4.00	EA
607.32	Bracing Assembly Type I - Metal Posts	26.00	EA
607.33	Bracing Assembly Type II - Metal Posts	11.00	EA
607.431	Snow Fence	208.00	LF
609.11	Vertical Curb Type 1	250.00	LF
610.08	Plain Riprap	230.00	CY
610.18	Stone Ditch Protection	86.00	CY
613.319	Erosion Control Blanket	6,500.00	SY
615.07	Loam	1,140.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	96.00	UNIT
619.1201	Mulch - Plan Quantity	96.00	UNIT
619.1202	Temporary Mulch (Dutton Hill Road)	1.00	LS
619.12021	Temporary Mulch (Weymouth Road)	1.00	LS
620.58	Erosion Control Geotextile	430.00	SY
620.625	Cellular Confinement System	840.00	SY
627.712	White or Yellow Pavement Marking Line	5,760.00	LF
627.78	Temporary Pavement Marking Line, White or Yellow	25.00	LF
629.05	Hand Labor, Straight Time	184.00	HR
631.12	All Purpose Excavator (Including Operator)	100.00	HR
631.171	Truck - Small (Including Operator)	120.00	HR
631.36	Foreman	120.00	HR
639.18	Field Office, Type A	1.00	EA
643.72	Temporary Traffic Signal	1.00	LS
645.272	Regulatory, Warning and Bridge Number Signs, Type I - Supplied by the Authority	29.00	EA
652.3	Flashing Arrow	9.00	EA
652.312	Type III Barricades	4.00	EA
652.33	Drum	820.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.34	Cone	200.00	EA
652.35	Construction Signs	4,425.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	160.00	HR
652.41	Portable - Changeable Message Sign	12.00	EA
652.45	Truck Mounted Attenuator	60.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	8.00	UNIT
652.46	Temporary Portable Rumble Strip	550.00	CD
656.75	Temporary Soil Erosion and Water Pollution Control (Running Hill Road)	1.00	LS
656.751	Temporary Soil Erosion and Water Pollution Control (Blackstrap Road)	1.00	LS
656.5	Baled Hay, in place	30.00	EA
656.632	30 inch Temporary Silt Fence	4,510.00	LF
659.1	Mobilization	1.00	LS