



Maine Turnpike Authority *Schedule of Items*

Bridge Improvements - Stroudwater River Overpass Mile 46.7

Bridge Improvements -

Item No.	Description	Quantity	UOM
201.11	Clearing	1.50	AC
202.1	Removing Existing Superstructure Property of Contractor - Stroudwater	1.00	LS
202.11	Removing Existing Superstructure Property of Contractor - MCRR	1.00	LS
202.12	Removing Existing Structural Concrete	255.00	CY
202.13	Removing Existing Railings Retained by Authority	2,240.00	LF
202.15	Removing Existing Manhole or Catch Basin	6.00	EA
202.202	Removing Pavement Surface	5,650.00	SY
202.206	Removing Rumble Strips	1,230.00	LF
203.2	Common Excavation	28,650.00	CY
203.21	Rock Excavation	150.00	CY
203.24	Common Borrow	17,200.00	CY
203.25	Granular Borrow	9,800.00	CY
203.35	Crushed Stone 3/4 - inch	40.00	CY
203.45	Clay Borrow	95.00	CY
206.07	Structural Rock Excavation - Drainage & Minor Structures	20.00	CY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	850.00	CY
206.1	Structural Earth Excavation - Piers	1,440.00	CY
304.1	Aggregate Subbase Course - Gravel	4,750.00	CY
304.14	Aggregate Base Course - Type A	3,900.00	CY
403.207	Hot Mix Asphalt, 19 mm Nominal Maximum Size	8,550.00	Ton
403.2081	Hot Mix Asphalt, 12.5 mm (Polymer Modified) - RAP	2,920.00	Ton
403.212	Hot Mix Asphalt, 4.75 mm	270.00	Ton
403.213	Hot Mix Asphalt, 12.5 mm (base and intermediate course)	2,950.00	Ton
409.15	Bituminous Tack Coat, Applied	4,550.00	GAL
419.3	Sawing Bituminous Pavement	7,250.00	LF
470.08	Berm Dropoff Correction - Grindings	217.00	Ton
470.081	Berm Correction	200.00	LF
501.231	Dynamic Loading Test	16.00	EA
501.301	Steel Sheet Piling - MCRR	1.00	LS
501.42	Steel H-beam Piles 57 lb/ft, delivered	4,214.00	LF
501.421	Steel H-beam Piles 57 lb/ft, in place	4,214.00	LF
501.44	Steel H-beam Piles 63 lb/ft, delivered	2,968.00	LF
501.441	Steel H-beam Piles 63 lb/ft, in place	2,968.00	LF
501.54	Steel H-beam Piles 117 lb/ft, delivered	195.00	LF
501.541	Steel H-beam Piles 117 lb/ft, in place	195.00	LF
501.9	Pile Tips	136.00	EA
501.91	Pile Splices	49.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
501.92	Pile Driving Equipment Mobilization - Stroudwater	1.00	LS
501.921	Pile Driving Equipment Mobilization - MCRR	1.00	LS
502.219	Structural Concrete, Abutments and Retaining Walls - Stroudwater	1.00	LS
502.2191	Structural Concrete, Abutments and Retaining Walls - MCRR	1.00	LS
502.239	Structural Concrete Piers - Stroudwater	1.00	LS
502.2391	Structural Concrete Piers - MCRR	1.00	LS
502.249	Structural Concrete Piers (Placed Under Water)	640.00	CY
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges - Stroudwater	1.00	LS
502.261	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges - MCRR	1.00	LS
502.264	Structural Concrete Parapets - Stroudwater	1.00	LS
502.2641	Structural Concrete Parapets - MCRR	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	799,000.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	799,000.00	LB
503.17	Mechanical/Welded Splice	4,512.00	EA
504.702	Structural steel fabricated and delivered, welded - Stroudwater	1.00	LS
504.7021	Structural steel fabricated and delivered, welded - MCRR	1.00	LS
504.71	Structural steel erection - Stroudwater	1.00	LS
504.711	Structural steel erection - MCRR	1.00	LS
504.7111	Peening Cover Plate Welds	64.00	EA
505.08	Shear Connectors - Stroudwater	1.00	LS
505.081	Shear Connectors - MCRR	1.00	LS
506.9102	Zinc Rich Coating System (Shop Applied) - Stroudwater	1.00	LS
506.91021	Zinc Rich Coating System (Shop Applied) - MCRR	1.00	LS
506.9105	Field Touch-Up of Existing Steel - Stroudwater	1.00	LS
506.91051	Field Touch-Up of Existing Steel - MCRR	1.00	LS
507.091	Aluminum Bridge Railing, 1 Bar - Stroudwater	1.00	LS
507.0911	Aluminum Bridge Railing, 1 Bar - MCRR	1.00	LS
508.14	High Performance Waterproofing Membrane - Stroudwater	1.00	LS
508.141	High Performance Waterproofing Membrane - MCRR	1.00	LS
511.071	Cofferdam Pier 1 - NB - Stroudwater	1.00	LS
511.072	Cofferdam Pier 1 - SB - Stroudwater	1.00	LS
511.073	Cofferdam Pier 2 - NB - Stroudwater	1.00	LS
511.074	Cofferdam Pier 2 - SB - Stroudwater	1.00	LS
511.091	Temporary Earth Support Systems - Stroudwater	1.00	LS
511.0911	Temporary Earth Support Systems - MCRR	1.00	LS
514.06	Curing Box for Concrete Cylinders	2.00	EA
515.202	Clear Protective Coating for Concrete Surfaces	2,630.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
515.23	Anti-Graffiti Coating	3,230.00	SY
518.3	Abutment Seat Refacing	7.00	CY
518.4	Epoxy Injection Crack Repair	99.00	LF
518.51	Repair of Upward Facing Surfaces - below Reinforcing Steel < 8 inches	160.00	SF
518.6	Repair of Vertical Surfaces < 8 inches	250.00	SF
520.221	Expansion Device - Locking Compression Seal with Steel Edge Beams	6.00	EA
520.23	Asphaltic Plug Joint	116.00	LF
523.52	Bearing Installation	36.00	EA
523.5303	Steel Bearings, Fixed, Rocker	8.00	EA
523.5304	Steel Bearings, Expansion, Rocker	28.00	EA
523.56	Clean and Paint Bearing	49.00	EA
523.561	Clean, Paint, and Reset Bearing	23.00	EA
524.301	Temporary Structural Support - Jacking - Stroudwater	1.00	LS
524.3011	Temporary Structural Support - Jacking - MCRR	1.00	LS
524.302	Temporary Structural Support - Girders - Stroudwater	1.00	LS
524.303	Temporary Structural Support - Braces - Stroudwater	1.00	LS
524.3031	Temporary Structural Support - Braces - MCRR	1.00	LS
524.4	Protective Shielding - Steel Girders	5,900.00	SY
526.301	Temporary Concrete Barrier, Type I - Stroudwater	1.00	LS
526.3012	Temporary Concrete Barrier, Type I - MCRR	1.00	LS
526.3011	Temporary Concrete Barrier, Type I: To Remain - Stroudwater	1.00	LS
526.30111	Temporary Concrete Barrier, Type I: To Remain - MCRR	1.00	LS
526.304	Temporary Concrete Barrier, Anchored - Stroudwater	1.00	LS
526.3041	Temporary Concrete Barrier, Anchored - MCRR	1.00	LS
526.307	Concrete Barrier Type I - Stormwater Filter	40.00	LF
527.341	Work Zone Crash Cushion - TL3	4.00	UNIT
603.155	12 inch Reinforced Concrete Pipe - Class III	320.00	LF
603.165	15 inch Reinforced Concrete Pipe - Class III	65.00	LF
603.175	18 inch Reinforced Concrete Pipe - Class III	77.00	LF
603.28	Concrete Collar	4.00	EA
604.09	Catch Basin Type B1	7.00	EA
604.15	Manhole	1.00	EA
604.246	Catch Basin Type F5	1.00	EA
604.26	Catch Basin Type B5	5.00	EA
604.4	Secure Catch Basin Grate	14.00	EA
605.016	6 Inch PVC Underdrain	590.00	LF
605.018	8 Inch PVC Underdrain	240.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
605.09	6" Underdrain Type B	420.00	LF
605.11	12" Underdrain Type C	140.00	LF
606.1301	31" W-Beam Guardrail - Mid-Way Splice (7' Steel Post, 8" Offset Blocks, Single Faced)	4,137.50	LF
606.1305	31" W-Beam Guardrail - Mid-Way Splice Flared Terminal (31" Height)	3.00	EA
606.1351	Terminal End - Anchored End - 31" W-Beam Guardrail	3.00	EA
606.1723	Bridge Transition - Type III	8.00	EA
606.353	Reflectorized Flexible Guardrail Marker	4.00	EA
606.354	Remove and Reset Reflectorized Flexible Guardrail Marker	10.00	EA
606.3622	Guardrail Adjust - Double Rail	530.00	LF
607.09	Woven Wire Fence - Metal Posts	1,500.00	LF
607.17	Chain Link Fence - 6 foot	1,760.00	LF
607.32	Bracing Assembly Type I - Metal Posts	2.00	EA
607.33	Bracing Assembly Type II - Metal Posts	10.00	EA
609.15	Sloped Curb Type I	1,600.00	LF
610.08	Plain Riprap	1,639.00	CY
610.18	Stone Ditch Protection	327.00	CY
610.181	Temporary Stone Check Dam	60.00	CY
613.319	Erosion Control Blanket	14,700.00	SY
615.07	Loam	3,850.00	CY
618.14	Seeding Method Number 2	310.00	UNIT
618.143	Special Seeding	6.00	UNIT
619.1201	Mulch - Plan Quantity	320.00	UNIT
619.1202	Temporary Mulch - Stroudwater	1.00	LS
619.12021	Temporary Mulch - MCRR	1.00	LS
620.58	Erosion Control Geotextile	2,523.00	SY
627.712	White or Yellow Pavement Marking Line	41,700.00	LF
627.73	Temporary 6 Inch Pavement Marking Tape	3,300.00	LF
627.77	Removing Existing Pavement Marking	31,600.00	SF
627.78	Temporary Painted Pavement Marking Line, White or Yellow	61,300.00	LF
629.05	Hand Labor, Straight Time	40.00	HR
631.1	Air Compressor (Including Operator)	40.00	HR
631.11	Air Tool (Including Operator)	40.00	HR
631.12	All Purpose Excavator (Including Operator)	40.00	HR
631.172	Truck - Large (Including Operator)	40.00	HR
631.32	Culvert Cleaner (Including Operator)	40.00	HR
631.36	Foreman	40.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
645.272	Regulatory, Warning and Bridge Number Signs, Type 1 - Supplied By Authority	4.00	EA
645.501	Remove and Reset Mainline Sign No. 1	1.00	LS
645.502	Remove and Reset Mainline Sign No. 2	1.00	LS
645.503	Remove and Reset Mainline Sign No. 3	1.00	LS
645.504	Remove and Reset Mainline Sign No. 4	1.00	LS
645.505	Remove and Reset Mainline Sign No. 5	1.00	LS
645.506	Remove and Reset Mainline Sign No. 6	1.00	LS
645.507	Remove and Reset Mainline Sign No. 7	1.00	LS
645.508	Remove and Reset Mainline Sign No. 8	1.00	LS
645.509	Remove and Reset Mainline Sign No. 9	1.00	LS
645.51	Remove and Reset Mainline Sign No. 10	1.00	LS
645.511	Remove and Reset Mainline Sign No. 11	1.00	LS
645.512	Remove and Reset Mainline Sign No. 12	1.00	LS
645.513	Remove and Reset Mainline Sign No. 13	1.00	LS
645.514	Remove and Reset Mainline Sign No. 14	1.00	LS
645.515	Remove and Reset Mainline Sign No. 15	1.00	LS
652.3	Flashing Arrow	4.00	EA
652.312	Type III Barricades	2.00	EA
652.33	Drum	510.00	EA
652.34	Cone	510.00	EA
652.35	Construction Signs	2,250.00	SF
652.361	Maintenance of Traffic Control Devices - Stroudwater	1.00	LS
652.3611	Maintenance of Traffic Control Devices - MCRR	1.00	LS
652.41	Portable-Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	130.00	CD
652.451	Automated Trailer Mounted Speed Limit Sign	130.00	CD
656.5	Baled Hay, In Place	40.00	EA
656.6	Temporary Berms	1,000.00	LF
656.62	Temporary Slope Drains	200.00	LF
656.632	30 Inch Temporary Silt Fence	8,850.00	LF
656.64	Boom Supported Floating Silt Fence	500.00	LF
659.1	Mobilization	1.00	LS
673.01	Stormwater Filter Bed	170.00	CY