



Maine Turnpike Authority *Schedule of Items*

York Toll Plaza Mile 8.8

Item No.	Description	Quantity	UOM
201.11	Clearing	17.00	AC
202.15	Removing Existing Manhole or Catch Basin	22.00	EA
202.151	Abandoning Existing Manhole or Catch Basin	10.00	EA
202.16	Removing Existing Pipe	575.00	LF
202.161	Abandoning Existing Pipe	680.00	LF
202.202	Removing Pavement Surface	88,000.00	SY
202.205	Rumble Strips - Shoulder	35,500.00	LF
202.206	Removing Rumble Strips	6,100.00	LF
202.6	Abandon Monitoring Well	2.00	EA
203.2	Common Excavation	128,500.00	CY
203.21	Rock Excavation	47,300.00	CY
203.211	Presplitting Rock	400.00	LF
203.213	Drilling and Blasting of Solid Rock Subgrade	5,700.00	SY
203.245	Clay Borrow	55.00	CY
203.25	Granular Borrow	7,400.00	CY
203.35	Crushed Stone Fill 3/4-Inch	550.00	CY
205.51	Widening of Existing Shoulder, Plan Quantity	315.00	SY
206.07	Structural Rock Excavation - Drainage & Minor Structures	3,200.00	CY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	2,450.00	CY
206.092	Structural Rock Excavation - Major Structures	1,980.00	CY
304.1	Aggregate Subbase Course-Gravel	115,500.00	CY
304.14	Aggregate Base Course - Type A	26,170.00	CY
304.15	Aggregate Base Course - Type B	200.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	39,750.00	T
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	550.00	T
403.2081	Hot Mix Asphalt - 12.5 mm Nominal Maximum Size (Polymer Modified)	14,300.00	T
403.209	Hot Mix Asphalt 9.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	50.00	T
403.211	Hot Mix Asphalt (Shim)	11,500.00	T
403.213	Hot Mix Asphalt 12.5 mm Nominal Maximum Size (Binder)	14,240.00	T
409.15	Bituminous Tack Coat - Applied	17,675.00	G
419.3	Saw Cutting Bituminous Pavement	3,600.00	LF
502.231	Structural Concrete, Space Frame and Overhead Sign Structure Pedestals	155.00	CY
502.233	Structural Concrete, Canopy Column Foundations	55.00	CY
502.265	Structural Concrete, ORT Slabs	300.00	CY
502.266	Structural Concrete, Plaza Structural Slabs	470.00	CY
502.267	Structural Concrete, Toll Islands	290.00	CY



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
502.268	Structural Concrete, Utility Pits	60.00	CY
502.269	Structural Concrete, CCTV Pole Foundations	14.00	CY
502.28	Structural Concrete, Rigid Frame Structures [Tunnel]	170.00	CY
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	136,500.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	136,500.00	LB
503.18	Glass Fiber Reinforced Polymer (GFRP) Reinforcing Bars, Fabricated and Delivered	48,000.00	LB
503.19	Glass Fiber Reinforced Polymer (GFRP) Reinforcing Bars, Placing	48,000.00	LB
503.9	Synthetic Fiber Reinforcement	2,100.00	LB
504.8	Space Frame Canopies, Fabricated and Delivered	1.00	LS
504.81	Space Frame Canopies, Erection	1.00	LS
504.9	Space Frame Steel Support Posts and Anchorage Assemblies	1.00	LS
504.91	Mounting Bracket Assemblies	1.00	LS
506.15	Shop Coating of New Steel	1.00	LS
506.9103	Galvanizing	1.00	LS
508.14	High Performance Waterproofing Membrane	1,670.00	SY
508.15	Membrane Waterproofing	1.00	LS
511.091	Temporary Earth Support Systems	1.00	LS
515.2011	Pigmented Concrete Protective Coating - Tunnel Walls & Ceiling	1,330.00	SY
515.2012	Pigmented Concrete Protective Coating - Tunnel Floor	455.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	1,400.00	SY
515.23	Epoxy Overlay	250.00	SY
526.306	Temporary Concrete Barrier Type I - Supplied by the Authority	1.00	LS
526.351	Median Barrier Type I -Precast	7,000.00	LF
526.3511	Median Barrier Type IA - Precast	1,800.00	LF
526.3512	Median Barrier Type IB - Precast	870.00	LF
526.352	Median Barrier Type II - Precast	240.00	LF
526.3522	Median Barrier Type II - Cast in Place	140.00	LF
526.3531	Median Barrier Type IIIA - Precast	180.00	LF
526.3532	Median Barrier Type IIIB - Precast	180.00	LF
526.361	Median Barrier Transition Type I - Precast	4.00	EA
526.3611	Median Barrier Transition Type IA - Precast	2.00	EA
526.3612	Median Barrier Transition Type IB - Precast	2.00	EA
526.3613	Median Barrier Transition Type LP-A	8.00	EA
526.3614	Median Barrier Transition Type LP-B	10.00	EA
526.362	Median Barrier Transition Type II - Precast	16.00	EA
526.371	Median Barrier With Mounted Light Pole Type LP-A - Cast in Place	4.00	EA
526.372	Median Barrier With Mounted Light Pole Type LP-B - Cast in Place	5.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
527.306	Center Barrier Crash Attenuator	2.00	EA
527.341	Work Zone Crash Cushions - TL-3	5.00	UNIT
534.71	Precast Concrete Tunnel and Tunnel Staircase Structures	1.00	LS
603.155	12 Inch Reinforced Concrete Pipe - Class III	420.00	LF
603.159	12 Inch Culvert Pipe Option III	250.00	LF
603.165	15 Inch Reinforced Concrete Pipe - Class III	2,375.00	LF
603.169	15 Inch Culvert Pipe Option III	450.00	LF
603.175	18 Inch Reinforced Concrete Pipe - Class III	940.00	LF
603.179	18 Inch Culvert Pipe Option III	100.00	LF
603.199	24 Inch Culvert Pipe Option III	25.00	LF
603.205	30 Inch Reinforced Concrete Pipe - Class III	64.00	LF
603.215	36 Inch Reinforced Concrete Pipe - Class III	64.00	LF
603.2353	48 Inch Reinforced Concrete Pipe - Class V	200.00	LF
603.28	Concrete Collar for Reinforced Concrete Pipe	10.00	EA
603.9	12 Inch Ductile Iron Storm Drain	90.00	LF
604.09	Catch Basin Type B1	24.00	EA
604.0901	Catch Basin Type B1 with Flat Top	48.00	EA
604.152	48 Inch Manhole	7.00	EA
604.1542	72 Inch Outlet Control Structure	5.00	EA
604.1561	96 Inch Doghouse Manhole	1.00	EA
604.1581	Inlet Control Structure	1.00	EA
604.26	Catch Basin Type B5	13.00	EA
605.09	6 Inch Underdrain Type B	1,450.00	LF
605.105	8 Inch Underdrain Outlet	350.00	LF
605.11	12 Inch Underdrain Type C	1,700.00	LF
606.13	31" W-Beam Guardrail – Mid-way Splice	5,050.00	LF
606.1724	Bridge Transition - Type III Modified	2.00	EA
606.278	Terminal End - Anchored End	11.00	EA
606.279	Terminal End - Anchored End, Thrie Beam	2.00	EA
606.352	Reflectorized Beam Guardrail Delineator	9.00	EA
606.353	Reflectorized Flexible Guardrail Marker	32.00	EA
606.356	Underdrain Delineator Post	189.00	EA
606.3562	Delineator Post - Remove and Stack	119.00	EA
606.3605	Guardrail - Remove, Modify, and Reset, Single Rail	25.00	LF
606.361	Guardrail - Remove, Modify, and Reset Thrie Beam, Single Rail	175.00	LF
606.3611	Guardrail - Remove, Modify, and Reset Thrie Beam, Double Rail	700.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
606.3631	Guardrail - Remove and Stack or Dispose	10,050.00	LF
606.48	Single Galvanized Steel Post	20.00	EA
606.64	Gr - Thrie Beam - Dbl Rail	125.00	LF
606.65	Gr - Thrie Beam - Sgl Rail	550.00	LF
606.754	Widen Shoulder for Energy Absorbing End Terminal	12.00	EA
606.791	Guardrail – Flared Terminal – 31” W-Beam Guardrail (7’ Steel Posts, 8” Offset Blocks, Single Faced)	13.00	EA
607.093	Right of Way Fencing with Habitat Barrier Fence, Metal Posts	15,000.00	LF
607.2325	Pipe Entry Gate	1.00	EA
607.4	Chain Link Fence - 3' High	480.00	LF
607.41	Post Assembly for Sign or Chain Link Fence	67.00	EA
607.4211	Dumpster Enclosure	1.00	LS
608.08	Reinforced Concrete Sidewalk/Site Concrete Slabs	340.00	SY
608.26	Curb Ramp Detectable Warning Field	75.00	SF
609.11	Vertical Curb Type 1	1,700.00	LF
609.12	Vertical Curb Type 1 - Circular	350.00	LF
609.238	Terminal Curb Type 1 - 8'	8.00	EA
610.07	Stone Fill	420.00	CY
610.08	Plain Riprap	250.00	CY
610.181	Temporary Stone Check Dam	400.00	CY
610.182	Permanent Stone Check Dam	80.00	CY
613.319	Erosion Control Blanket	40,000.00	SY
615.07	Loam	14,050.00	CY
618.13	Seeding Method Number 1	850.00	UN
618.141	Seeding Method Number 3	200.00	UN
619.1201	Mulch	950.00	UN
619.1202	Temporary Mulch	1.00	LS
619.13	Bark Mulch	60.00	CY
620.56	Drainage Geotextile	350.00	SY
620.58	Erosion Control Geotextile	14,400.00	SY
621.037	Evergreen Tree (5'-6') Group GP A	8.00	EA
621.291	Large Deciduous Tree (4" Cal) GP A	1.00	EA
621.535	Deciduous Shrub (No. 3 Cont) GP A	25.00	EA
625.086	2" Copper Tubing	20.00	LF
625.145	8" Non-Metallic Pipe Sleeve	360.00	LF
625.16	2" Non-Metallic Pipe	780.00	LF
626.111	Barrier Junction Box	13.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
626.113	4'x4' Splice Box	12.00	EA
626.12	Quazite Junction Box (36x24)	81.00	EA
626.13	Primary Electric Manholes (CMP)	6.00	EA
626.22	Non-Metallic Conduit	22,755.00	LF
626.2214	4" Non-Metallic Conduit, Concrete Encased	6,500.00	LF
626.2215	5" Non-Metallic Conduit, Concrete Encased	6,500.00	LF
626.3321	36-inch Diameter Drilled Shaft	360.00	LF
626.3322	30-Inch Diameter Drilled Shaft - Rock Socket	80.00	LF
626.341	Light Standard Foundation	65.00	EA
627.18	12" Solid White Pavement Marking	10,200.00	LF
627.4072	Pref Pave Mark Tape Line, Groove Install	2,000.00	SF
627.681	Temporary 6 Inch Painted Pavement Marking Line -Yellow or White	140,000.00	LF
627.71	4" White Pavement Marking Line	1,100.00	LF
627.731	Temporary 6 Inch Black Pavement Marking Tape	2,000.00	LF
627.744	6" White or Yellow Painted Pavement Marking Line	50,700.00	LF
627.75	White or Yellow Pavement & Curb Marking	200.00	SF
627.77	Remove Existing Pavement Marking	3,400.00	SF
627.73	Temporary 6 Inch Pavement Marking Tape	3,200.00	LF
627.812	Temporary Raised Pavement Markers	530.00	EA
627.9011	Pavement Marking Symbol	9.00	EA
627.94	Pavement Marking Tape	2,750.00	LF
629.05	Hand Labor, Straight Time	20.00	HR
631.1	Air Compressor (Inc Operator)	20.00	HR
631.11	Air Tool (Inc Operator)	20.00	HR
631.115	Jackhammer (Inc Operator)	20.00	HR
631.12	All Purpose Excavator (Inc Operator)	20.00	HR
631.171	Truck - Small (Including Operator)	20.00	HR
631.18	Chain Saw Rental (Inc Operator)	20.00	HR
631.32	Culvert Cleaner (Inc Operator)	20.00	HR
631.36	Foreperson	25.00	HR
631.51	Bucket Truck	20.00	HR
631.52	Scissor Lift	20.00	HR
631.53	Electrician	20.00	HR
631.54	Electrician's Apprentice	20.00	HR
633.021	Propane Service Line	100.00	LF
634.16	Highway Lighting	1.00	LS
634.231	Conventional Light Standard with LED Fixture	77.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
634.232	Sign Light	14.00	EA
639.18	Field Office Type A	1.00	EA
639.19	Field Office Type B	1.00	EA
641.35	Aluminum Flag Pole	1.00	EA
643.63	Flashing Beacon - Solar Powered	4.00	EA
643.712	Lane Use Signal	9.00	EA
645.105	Remove and Stack Sign	13.00	EA
645.1051	Remove and Stack Ground Mount Guide Sign and Structure	4.00	EA
645.109	Remove and Reset Sign	3.00	EA
645.1092	Canopy Mounted Dynamic Message Sign	1.00	EA
645.121	Overhead Guide Sign 1 (Sta. 281+45)	1.00	LS
645.122	Overhead Guide Sign 2 (Sta.306+65)	1.00	LS
645.123	Overhead Guide Sign 3 (Sta.318+81)	1.00	LS
645.124	Overhead Guide Sign 4 (Sta.332+00)	1.00	LS
645.125	Overhead Guide Sign 5 (Sta.359+50)	1.00	LS
645.126	Overhead Guide Sign 6 (Sta.374+50)	1.00	LS
645.127	Overhead Guide Sign 7 (Sta.382+50)	1.00	LS
645.128	Overhead Guide Sign 8 (Sta.414+90)	1.00	LS
645.14	Canopy Mounted Sign	7.00	EA
645.141	Canopy Mounted DMS Remove and Reset	1.00	EA
645.155	Variable Speed Limit Sign	2.00	EA
645.251	Roadside Guide Signs, Type I	1,462.00	SF
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type I	490.00	SF
645.28	Wood Post	26.00	EA
645.289	Steel H-Beam Poles	13,400.00	LB
645.501	Remove and Reset Mainline Sign 1	1.00	LS
645.502	Remove and Reset Mainline Sign 2	1.00	LS
645.503	Remove and Reset Mainline Sign 3	1.00	LS
652.3	Flashing Arrow Board	6.00	EA
652.312	Type III Barricade	10.00	EA
652.33	Drum	400.00	EA
652.34	Cone	200.00	EA
652.35	Construction Signs	1,450.00	SF
652.36	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flagger	880.00	HR
652.41	Portable-Changeable Message Sign	5.00	EA
652.45	Truck Mounted Attenuator	500.00	CD



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
652.451	Automated Trailer Mounted Speed Limit Sign	2.00	EA
652.5	Temporary Barrier	1.00	LS
655.01	Installation of ORT Lane Controller Cabinet	2.00	EA
655.012	Installation of Cash Lane Controller Cabinet	9.00	EA
655.02	DVAS Mount Installation	13.00	EA
655.03	VCARS Mount Installation	20.00	EA
655.04	Installation of Sensor Loops	1.00	LS
655.05	Installation of AVI Antennas	27.00	EA
655.06	Installation of AVI Readers	6.00	EA
655.07	Traffic Control Pedestal Preparation Work	9.00	EA
655.08	OPUS Mount Installation	30.00	EA
655.09	Armored Cable - 10/3	100.00	LF
655.1	#2/0 AWG Wire	1,550.00	LF
655.1001	#1/0 AWG Wire	1,000.00	LF
655.1003	#3/0 AWG Wire	3,500.00	LF
655.101	#1 AWG Wire	5,000.00	LF
655.102	#2 AWG Wire	1,150.00	LF
655.104	#4 AWG Wire	100.00	LF
655.106	#6 AWG Wire	100.00	LF
655.11	#10 AWG Wire	4,850.00	LF
655.12	#12 AWG Wire	80,000.00	LF
655.13	#14 AWG Wire	1,000.00	LF
655.14	4pr/24 (Category 5e) Cable	44,000.00	LF
655.15	LMR 400 Cable	1,730.00	LF
655.16	Fiber Optic Cable – 6 Fiber	3,390.00	LF
655.17	IVIS Homerun Loop Cable (IMSA 50-2 #14)	11,350.00	LF
655.2	1 1/2" Schedule 40 PVC Conduit	250.00	LF
655.2001	3/4" Schedule 40 PVC Conduit	200.00	LF
655.2002	1" Schedule 40 PVC Conduit	200.00	LF
655.2003	2" Schedule 40 PVC Conduit	400.00	LF
655.201	3" Schedule 40 PVC Conduit	200.00	LF
655.202	4" Schedule 40 PVC Conduit	750.00	LF
655.2021	1" Schedule 80 PVC Conduit	400.00	LF
655.203	1 1/2" Schedule 80 PVC Conduit	1,440.00	LF
655.2031	2" Schedule 80 PVC Conduit	430.00	LF
655.204	3" Schedule 80 PVC Conduit	3,000.00	LF
655.205	4" Schedule 80 PVC Conduit	230.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
655.2051	6" Schedule 80 PVC Conduit	300.00	LF
655.2052	5" Schedule 80 PVC Conduit	300.00	LF
655.206	1" Galvanized Rigid Metal Conduit	900.00	LF
655.2061	3/4" Galvanized Rigid Metal Conduit	600.00	LF
655.207	1 1/2" Galvanized Rigid Metal Conduit	350.00	LF
655.2071	2" Galvanized Rigid Metal Conduit	600.00	LF
655.208	3" Galvanized Rigid Metal Conduit	1,040.00	LF
655.209	1/2" Liquid Tight Metallic Flexible Conduit	700.00	LF
655.21	3/4" Liquid Tight Metallic Flexible Conduit	280.00	LF
655.2101	1 1/2" Liquid Tight Metallic Flexible Conduit	100.00	LF
655.2102	2" Liquid Tight Metallic Flexible Conduit	100.00	LF
655.2103	1" Liquid Tight Metallic Flexible Conduit	100.00	LF
655.211	1 1/2" Electrical Metallic Tubing Conduit	180.00	LF
655.2111	1" Electrical Metallic Tubing Conduit	180.00	LF
655.212	2" Electrical Metallic Tubing Conduit	180.00	LF
655.213	3" Electrical Metallic Tubing Conduit	100.00	LF
655.214	4" Electrical Metallic Tubing Conduit	100.00	LF
655.215	3/4" Electrical Metallic Tubing Conduit	100.00	LF
655.221	Type A Pull Box Inside	36.00	EA
655.222	Type C Pull Box in Tunnel/Booth Pit	40.00	EA
655.223	Type D Pull Box Outdoor Canopy	4.00	EA
655.224	Type E Pull Box Steel in Booth	18.00	EA
655.225	Type F Pull Box Outside	13.00	EA
655.3	12" x 12" x 6" Galvanized Junction Box	100.00	EA
655.31	18" x 18" x 6" Galvanized Junction Box	8.00	EA
655.4	18" x 24" x 12" Junction Box	6.00	EA
655.42	36" x 30" x 20" NEMA 4X Cabinet	6.00	EA
655.43	60 AMP 3 Phase Panelboard Cabinet	4.00	EA
655.44	100 AMP 3 Phase Panelboard Cabinets	4.00	EA
655.5	2" PVC Conduit Condulets	20.00	EA
655.51	4" PVC Conduit Condulets	20.00	EA
655.511	3/4" Rigid Metal Conduit Condulets	10.00	EA
655.52	1" Rigid Metal Conduit Condulets	50.00	EA
655.53	1 1/2" Rigid Metal Conduit Condulets	50.00	EA
655.54	2" Rigid Metal Conduit Condulets	20.00	EA
655.55	3" Electrical Metal Tubing Condulets	20.00	EA
655.56	2" Electrical Metal Tubing Condulets	20.00	EA



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
655.57	1 1/2" Electrical Metal Tubing Condulets	20.00	EA
655.58	3/4" Electrical Metal Tubing Condulets	20.00	EA
655.59	1" Electrical Metal Tubing Condulets	20.00	EA
655.63	4-inch x 4-inch PVC NEMA 3R Wireway	630.00	LF
655.64	6-inch x 6-inch PVC NEMA 3R Wireway	660.00	LF
655.65	8-inch x 8-inch PVC NEMA 3R Wireway	660.00	LF
655.66	12-inch x 12-inch PVC NEMA 3R Wireway	400.00	LF
655.75	Concrete Encased Conduit	60.00	CY
655.8	Lightning Suppression System	1.00	LS
655.81	Key Switch	18.00	EA
655.82	Duplex Receptacle	20.00	EA
655.83	NEMA L5-30R Receptacle	6.00	EA
655.84	Quadplex Receptacle	30.00	EA
655.9	Space Frame Lighting	1.00	LS
655.92	LED Canopy Light Fixture	18.00	EA
655.98	Toll Booth Electrical Installation	1.00	LS
655.99	LED Bumper Beacon	9.00	EA
656.5	Baled Hay, In Place	50.00	EA
656.6	Temporary Berms	150.00	LF
656.62	Temporary Slope Drains	150.00	LF
656.632	30" Temporary Silt Fence	24,000.00	LF
659.1	Mobilization	1.00	LS
665.002	Communications	1.00	LS
800.01	Toll Administration Building	1.00	LS
800.22	HVAC Tunnel and Booths	1.00	LS
800.23	Tunnel and Toll Stairway Lighting, Fire Alarm, and House Power	1.00	LS
800.24	Toll Administration Building Standby Generator	1.00	LS
800.4	Tunnel Stair Enclosures	1.00	LS
800.41	Tunnel Access Hatch	1.00	LS
800.501	Southbound and Northbound Plaza Canopies	1.00	LS
800.503	Metal Stairs at Tunnel Staircases	1.00	LS
800.51	New Toll Booth Installation	1.00	LS
800.62	Radon Mitigation System	1.00	LS
801.03	Test Pits	2.00	EA
801.132	2 Inch Force Main	50.00	LF
801.141	4" PVC Sanitary Sewer (SDR-35)	40.00	LF
802.23	Subsurface Wasterwater Leach Field With Geotextile Sand Filter (GSF)	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
802.241	1250 Gallon Precast Septic Tank with Pump	1.00	LS
822.37	16" Ductile Iron Pipe	1,660.00	LF
822.6	Water Meter Pit	1.00	LS
823.3411	1" Air Release Valve	1.00	EA
823.374	16" Gate Valve	2.00	EA
832.41	Type A Steel Site Bollard	9.00	EA