



Maine Turnpike Authority *Schedule of Items*

Bridge Repairs 3 Locations: Bennett Road Underpass Mile 68.6 Grove Street Underpass Mile 83.7 Route 9 Underpass Mile 86.1

Item No.	Description	Quantity	UOM
202.12	REMOVING EXISTING STRUCTURAL CONCRETE	33.00	CY
202.127	REMOVING OF EXISTING BITUMINOUS PAVEMENT (1515 SY)	1.00	LS
202.191	REMOVING EXISTING DRAIN TROUGHS	1.00	LS
202.202	REMOVING PAVEMENT SURFACE	1,130.00	SY
202.206	REMOVING OF RUMBLE STRIPS	1,170.00	LF
203.2	COMMON EXCAVATION	88.00	CY
203.25	GRANULAR BORROW	78.00	CY
403.208	HOT MIX ASPHALT, 12.5MM NOMINAL MAXIMUM SIZE	221.00	TON
403.213	HOT MIX ASPHALT, 12.5MM NOMINAL MAXIMUM SIZE (BASE AND INTERMEDIATE COURSE)	147.00	TON
409.15	BITUMINOUS TACK COAT RS-1 OR RS-1h - APPLIED	177.00	GAL
502.21	STRUCTURAL CONCRETE, ABUTMENTS AND RETAINING WALLS	23.00	CY
502.42	STRUCTURAL CONCRETE ROADWAY AND SIDEWALK SLAB ON STEEL BRIDGES	11.00	CY
502.701	BRIDGE DRAIN GRATE MODIFICATIONS	6.00	EA
502.7011	WEEP DRAIN EXTENSIONS	1.00	LS
503.12	REINFORCING STEEL, FABRICATED AND DELIVERED	3,600.00	LB
503.13	REINFORCING STEEL, PLACING	3,600.00	LB
503.14	EPOXY-COATED REINFORCING STEEL, FABRICATED AND DELIVERED	3,400.00	LB
503.15	EPOXY-COATED REINFORCING STEEL, PLACING	3,400.00	LB
504.8	STRUCTURAL STEEL REPAIR (REPAIR AREA "A")	1.00	LS
504.81	STRUCTURAL STEEL REPAIR (REPAIR AREA "B")	1.00	LS
504.82	STRUCTURAL STEEL REPAIR (REPAIR AREA "C")	1.00	LS
506.9103	ZINC RICH COATING SYSTEM (FIELD APPLIED)	1.00	LS
508.14	HIGH PERFORMANCE WATERPROOFING MEMBRANE (1535 SY)	1.00	LS
515.201	PIGMENTED PROTECTIVE COATING FOR CONCRETE SURFACES	705.00	SY
515.202	CLEAR PROTECTIVE COATING FOR CONCRETE SURFACES	730.00	SY
518.1	ABUTMENT REPAIRS	60.00	SF
518.2	PIER REPAIRS	485.00	SF
518.39	GRANITE CURB JOINT MORTAR AND BEDDING REPAIR	820.00	LF
518.43	PARAPET JOINT REPAIR	350.00	LF
518.75	FASCIA AND OVERHANG REPAIRS	75.00	SF
518.8	PARTIAL DEPTH CONCRETE DECK REPAIRS	140.00	SF
518.81	FULL DEPTH CONCRETE DECK REPAIRS	5.00	SF
520.211	EXPANSION DEVICE MODIFICATIONS (ROUTE 9)	2.00	EA
520.23	EXPANSION DEVICE - ASPHALTIC PLUG JOINT (BENNETT ROAD)	52.00	LF
520.2111	BRIDGE EXPANSION JOINT CLEANING (WILSON ROAD)	1.00	LS
520.2112	BRIDGE EXPANSION JOINT CLEANING (LITTLEFIELD ROAD)	1.00	LS



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
524.31	TEMPORARY DECK SUPPORT SYSTEM	1.00	LS
531.82	HEAT STRAIGHTENING	1.00	LS
607.17	CHAIN LINK FENCE - 6 FOOT	250.00	LF
607.34	BRACING ASSEMBLY CHAIN LINK FENCE	16.00	EA
609.11	VERTICAL CURB TYPE 1	35.00	LF
610.08	PLAIN RIPRAP	85.00	CY
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	370.00	SY
627.712	WHITE OR YELLOW PAVEMENT MARKING LINE	3,220.00	LF
627.73	TEMPORARY 6 INCH PAVEMENT MARKING TAPE	80.00	LF
627.731	TEMPORARY 6 INCH BLACK PAVEMENT MARKING TAPE	180.00	LF
627.77	REMOVING PAVEMENT MARKINGS	310.00	SF
627.94	PAVEMENT MARKING TAPE	2,050.00	LF
629.05	HAND LABOR - STRAIGHT TIME	40.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.00	HR
631.172	TRUCK-LARGE (INCLUDING OPERATOR)	40.00	HR
631.36	FOREMAN	20.00	HR
643.72	TEMPORARY TRAFFIC SIGNAL	1.00	LS
652.39	WORK ZONE TRAFFIC CONTROL	1.00	LS
652.45	TRUCK MOUNTED ATTENUATOR	56.00	CD
652.451	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	28.00	CD
656.5	BALED HAY, IN PLACE	16.00	EA
656.632	30 INCH TEMPORARY SILT FENCE	800.00	LF
659.1	MOBILIZATION	1.00	LS