MAINE TURNPIKE AUTHORITY

MAINE TURNPIKE

CONTRACT DOCUMENTS

CONTRACT 2018.12

PAVEMENT REHABILITATION,
GUARDRAIL, DRAINAGE, AND
CLEAR ZONE IMPROVEMENTS
MM 74.9 TO MM 80.7

NOTICE TO CONTRACTORS

PROPOSAL

CONTRACT AGREEMENT

CONTRACT BOND

FINAL LIEN AND CLAIM WAIVER AND AFFIDAVIT

SPECIFICATIONS

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

The Specifications are divided into two parts:
Part I, Supplemental Specifications and Part II, Special Provisions.

The Maine Turnpike Supplemental Specifications are additions and alterations to the 2014 Maine Department of Transportation Standard Specifications. See Subsection 100.1.

TABLE OF CONTENTS

ARRANGEMENT OF SPECIFICATIONS

MAINE TURNPIKE AUTHORITY

NOTICE TO CONTRACTORS

Sealed Proposals will be received by the Maine Turnpike Authority for:

CONTRACT 2018.12

PAVEMENT REHABILITATION,
GUARDRAIL, DRAINAGE, AND
CLEAR ZONE IMPROVEMENTS
MM 74.9 TO MM 80.7

at the office of the Maine Turnpike Authority, 2360 Congress Street, Portland, ME, until 11:00 a.m., prevailing time as determined by the Authority on April 24, 2018 at which time and place the Proposals will be publicly opened and read. Bids will be accepted from Contractors **prequalified** by the Maine Department of Transportation for Paving Construction Projects. All other bids may be rejected. This Project includes a wage determination developed by the State of Maine Department of Labor.

The pavement rehabilitation works consists of milling and filling two 12-foot wide lanes and the four foot shoulder and the Exit 75 ramps from MM 74.9 to MM 80.7, excluding the area around the Washington Avenue Bridge. The work also involves partial depth pavement repairs, earthwork, drainage, guardrail, pavement markings, maintenance of traffic and all other work incidental thereto in accordance with the Plans and Specifications.

Plans and Contract Documents may be examined by prospective Bidders weekdays between 8:00 a.m. and 4:30 p.m. at the office of the Maine Turnpike Authority, 2360 Congress Street, Portland, Maine. **The half size Plans** and Contract Documents may be obtained from the Authority upon payment of Seventy Five ($75.00) Dollars for each set, which payment will not be returned. Checks shall be made payable to: Maine Turnpike Authority. The Plans and Contract Documents may also be downloaded from a link on our website at http://www.maineturnpike.com/project-and-planning/Construction-Contracts.aspx.

For general information regarding Bidding and Contracting procedures, contact Nate Carll, Purchasing Manager, at (207) 482-8115. For information regarding Schedule of Items, plan holders list and bid results, visit our website at **http://www.maineturnpike.com/project-and-planning/Construction-Contracts.aspx** . For Project specific information, fax all questions to Nate Carll, Purchasing Manager, at (207) 871-7739 or email ncarll@maineturnpike.com. Responses will not be prepared for questions received by telephone. Bidders shall not contact any other Authority staff or Consultants for clarification of Contract provisions, and the Authority will not be responsible for any interpretations so obtained.

All work shall be governed by the Specifications entitled "State of Maine, Department of Transportation, Standard Specifications, Revision of November 2014", "Standard Details, Revision of November 2014" and "Best Management Practices for Erosion and Sediment

Control", latest issue. Copies and recent updates to these publications can be downloaded at: http://www.maine.gov/mdot/contractors/publications/ .

Proposals must be accompanied by an original bid bond, certified or cashier's check payable to the Maine Turnpike Authority in an amount not less than Five (5%) Percent of the Total Amount in the Proposal, but not less than $500.00. The Bidder to whom a Contract is awarded will be required to furnish a Surety Corporation Bond, satisfactory to the Authority, on the standard Contract Bond form of the Authority, for a sum not less than the Total Amount of the Proposal.

Proposals must be made upon the Proposal Forms furnished by the Authority separately with the Contract Documents, and must be enclosed in the sealed special addressed envelope provided therefore bearing the name and address of the Bidder, the name of the Contract, and the date and time of Proposal opening on the outside.

A pre-bid conference will be held on April 9, 2018 at 11:00 a.m. at the Maine Turnpike Authority, 2360 Congress Street, Portland, Maine.

The Authority reserves the unqualified right to reject any or all Proposals and to accept that Proposal which in its sole judgment will under all circumstances serve its best interest.

MAINE TURNPIKE AUTHORITY

Nate Carll
Purchasing Manager
Maine Turnpike Authority

Portland, Maine

Maine Turnpike Authority

MAINE TURNPIKE

PROPOSAL

CONTRACT 2018.12

PAVEMENT REHABILITATION, GUARDRAIL, DRAINAGE, AND CLEAR ZONE IMPROVEMENTS MM 74.9 TO MM 80.7

MAINE TURNPIKE AUTHORITY

PROPOSAL

CONTRACT 2018.12

PAVEMENT REHABILITATION,
GUARDRAIL, DRAINAGE, AND
CLEAR ZONE IMPROVEMENTS
MM 74.9 TO MM 80.7

TO MAINE TURNPIKE AUTHORITY:

The pavement rehabilitation works consists of milling and filling two 12-foot wide lanes and the four foot shoulder and the Exit 75 ramps from MM 74.9 to MM 80.7, excluding the area around the Washington Avenue Bridge. The work also involves partial depth pavement repairs, earthwork, drainage, guardrail, pavement markings, maintenance of traffic and all other work incidental thereto in accordance with the Plans and Specifications.

This Work will be done under a Contract known as Contract 2018.12 according to the Plans and Specifications which are on file in the office of the Maine Turnpike Authority, 2360 Congress Street, Portland, Maine.

On the acceptance of this Proposal for said Work, the undersigned will give the required bond with good security conditioned for the faithful performance of said Work, according to said Plans and Specifications, and the doing of all other work required by said Specifications for the consideration herein named and with the further condition that the Maine Turnpike Authority shall be saved harmless from any and all damages that might accrue to any person, persons or property by reason of the carrying out of said Work, or any part thereof, or by reason of negligence of the undersigned, or any person or persons under his employment and engaged in said Work.

The undersigned hereby declares that he/she has carefully examined the Plans, Specifications and other Contract Documents, and that he/she will contract to carry out and complete the said Work as specified and delineated at the price per unit of measure for each scheduled item of Work stated in the Schedule of Prices as follows:

It is understood that the TOTAL AMOUNT stated by the undersigned in the following Schedule of Prices is based on approximate quantities and will be used solely for the comparison of bids, and that the quantities stated in the Schedule of Prices for the various items are estimates only and may be increased or decreased all as provided in the Specifications.

SCHEDULE OF BID PRICES
CONTRACT NO. 2018.12

Pavement Rehabilitation, Guardrail, Drainage, and Clear Zone Improvements
MM 74.9 to MM 80.7

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
202.202	REMOVING PAVEMENT SURFACE - MAINLINE	Square Yard	153,000				
202.2026	REMOVING PAVEMENT SURFACE - DRAINAGE PATHS	Square Foot	6,350				
202.205	RUMBLE STRIPS	Each	59,000				
203.24	COMMON BORROW	Cubic Yard	170				
205.511	WIDENING OF EXISTING SHOULDER	Linear Foot	75				
211.30	DITCH EXCAVATION	Linear Foot	3,050				
403.208	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE	Ton	860				
403.2081	HOT MIX ASPHALT, 12.5 mm NOMINAL MAXIMUM SIZE (POLYMER MODIFIED)	Ton	12,400				
403.211	HOT MIX ASPHALT, 9.5 mm NOMINAL MAXIMUM SIZE (SHIMMING)	Ton	4,100				
409.15	BITUMINOUS TACK COAT, APPLIED	Gallon	12,500				

CARRIED FORWARD:		

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
			BROUGHT FORWARD:				
424.323	ASPHALT RUBBER MASTIC CRACK SEALER - APPLIED	Pound	20,000				
427.09	PAVEMENT CRACK REPAIR	Linear Foot	7,150				
429.341	GRID/PAVING FABRIC COMPOSITE INTERLAYER	Square Foot	33,600				
470.08	BERM DROP OFF CORRECTION - GRINDINGS	Ton	2,000				
527.304	ENERGY ABSORBING SYSTEM (C-A-T) - REMOVE & STACK	Each	4				
603.155	12" RCP CLASS III	Linear Foot	32				
603.159	12" CULVERT PIPE OPTION III	Linear Foot	91				
603.179	18" CULVERT PIPE OPTION III	Linear Foot	40				
603.199	24" CULVERT PIPE OPTION III	Linear Foot	32				
603.209	30" CULVERT PIPE OPTION III	Linear Foot	16				
603.28	CONCRETE COLLAR	Each	11				
604.184	REBUILD CATCH BASIN TO GRADE - TYPE II	Each	1				
			CARRIED FORWARD:				

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
				BROUGHT FORWARD:			
606.178	GUARDRAIL BEAM	Linear Foot	1,500				
606.24	GUARDRAIL TYPE 3D - SINGLE RAIL	Linear Foot	75				
606.2401	GUARDRAIL TYPE 3D - DOUBLE RAIL	Linear Foot	300				
606.2652	TERMINAL END - REMOVE AND STACK	Each	19				
606.278	TERMINAL END - ANCHORED END	Each	19				
606.356	UNDERDRAIN DELINEATOR POST	Each	35				
606.3562	UNDERDRAIN DELINEATOR POST - REMOVE AND STACK	Each	28				
606.3606	GUARDRAIL - REMOVE, MODIFY, AND RESET DOUBLE RAIL	Linear Foot	890				
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	Linear Foot	20,900				
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	Linear Foot	22,100				
606.471	SINGLE OFFSET BLOCK - W-BEAM	Each	20				
606.48	SINGLE GALVANIZED STEEL POST	Each	30				
				CARRIED FORWARD:			

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
			BROUGHT FORWARD:				
606.754	WIDEN SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	Each	4				
606.755	MODIFY WIDENED SHOULDER FOR GUARDRAIL 350 FLARED TERMINAL	Each	19				
606.79	GUARDRAIL 350 FLARED TERMINAL	Each	5				
610.08	PLAIN RIPRAP	Cubic Yard	57				
613.319	EROSION CONTROL BLANKET	Square Yard	2,400				
615.07	LOAM	Cubic Yard	290				
618.14	SEEDING METHOD #2	Unit	24				
619.1201	MULCH - PLAN QUANTITY	Unit	24				
619.1202	TEMPORARY MULCH	Lump Sum	1				
620.58	EROSION CONTROL GEOTEXTILE	Square Yard	150				
627.18	12" SOLID WHITE PAVEMENT MARKING LINE	Linear Foot	2,550				
627.712	WHITE OR YELLOW PAVEMENT MARKING LINE	Linear Foot	103,000				
			CARRIED FORWARD:				

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
				BROUGHT FORWARD:			
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	Linear Foot	142,000				
627.812	TEMPORARY RAISED PAVEMENT MARKERS	Each	26,000				
627.94	PAVEMENT MARKING TAPE	Linear Foot	1,800				
627.941	PAVEMENT MARKING TAPE - DOTTED WHITE LANE LINE, 6-INCH WIDTH	Linear Foot	550				
629.05	HAND LABOR, STRAIGHT TIME	Hour	40				
631.10	AIR COMPRESSOR (INCLUDING OPERATOR)	Hour	10				
631.11	AIR TOOL (INCLUDING OPERATOR)	Hour	10				
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	Hour	40				
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	Hour	40				
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	Hour	10				
631.36	FOREMAN	Hour	40				
652.30	FLASHING ARROW BOARD	Each	2				
				CARRIED FORWARD:			

Item No.	Item Description	Units	Approx. Quantities	Unit Prices in Numbers		Bid Amount in Numbers	
				Dollars	Cents	Dollars	Cents
				BROUGHT FORWARD:			
652.331	DRUM	Lump Sum	1				
652.34	CONE	Each	10				
652.35	CONSTRUCTION SIGNS	Square Foot	3,400				
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	Lump Sum	1.0				
652.410	PORTABLE - CHANGEABLE MESSAGE SIGN	Each	3				
652.45	TRUCK MOUNTED ATTENUATOR	Cal. Day	100				
652.452	AUTOMATED TRAILER MOUNTED SPEED LIMIT SIGN	Each	2				
652.46	TEMPORARY PORTABLE RUMBLE STRIP	Unit	300	$150	00	$45,000	00
656.632	30 INCH TEMPORARY SILT FENCE	Linear Foot	830				
659.10	MOBILIZATION	Lump Sum	1				
				TOTAL:			

Acknowledgment is hereby made of the following Addenda received since issuance of the Plans and Specifications: _____

_____

_____

Accompanying this Proposal is an original bid bond, cashiers or certified check on _____ Bank, for _____, payable to the Maine Turnpike Authority. In case this Proposal shall be accepted by the Maine Turnpike Authority and the undersigned should fail to execute a Contract with, and furnish the security required by the Maine Turnpike Authority as set forth in the Specifications, within the time fixed therein, an amount of money equal to Five (5%) Percent of the Total Amount of the Proposal for the Contract awarded to the undersigned, but not less than $500.00, obtained out of the original bid bond, cashier's or certified check, shall become the property of the Maine Turnpike Authority; otherwise the check will be returned to the undersigned.

The performance of said Work under this Contract will be completed during the time specified in Subsection 107.1.

It is agreed that time is of the essence of this Contract and that I (we) will, in the event of my (our) failure to complete the Work within the time limit named above, pay to Maine Turnpike Authority liquidated damages in the amount or amounts stated in the Specifications.

The undersigned is an Individual/Partnership/Corporation under the laws of the State of _____, having principal office at _____, thereunto duly authorized.

_____ *(SEAL)*

_____ *(SEAL)*

Affix Corporate Seal
or Power of Attorney
Where Applicable _____ *(SEAL)*

By: _____

Its: _____

Information below to be typed or printed where applicable:

INDIVIDUAL:

_____	_____
(Name)	(Address)

PARTNERSHIP - Name and Address of General Partners:

_____	_____
(Name)	(Address)
_____	_____
(Name)	(Address)
_____	_____
(Name)	(Address)
_____	_____
(Name)	(Address)

INCORPORATED COMPANY:

_____	_____
(President)	(Address)
_____	_____
(Vice-President)	(Address)
_____	_____
(Secretary)	(Address)
_____	_____
(Treasurer)	(Address)

MAINE TURNPIKE AUTHORITY

MAINE TURNPIKE

YORK TO AUGUSTA

CONTRACT AGREEMENT

This Agreement made and entered into between the Maine Turnpike Authority, and sometimes termed the "Authority", and _____

_____

herein termed the "Contractor":

WITNESSETH: That the Authority and the Contractor, in consideration of the premises and of the mutual covenants, considerations and agreements herein contained, agree as follows:

FIRST: The parties hereto mutually agree that the documents attached hereto and herein incorporated and made a part hereof collectively evidencing and constituting the entire Contract to the same extent as if herein written in full, are the Notice to Contractors, the Accepted Proposal, the Specifications, the Plans, this Agreement, the Contract Bond and all Addenda to the Contract Documents duly issued and herewith enumerated:

_____

_____

SECOND: The Contractor for and in consideration of certain payments to be made as hereafter specified, hereby covenants and agrees to perform and execute all of the provisions of this Contract and of all documents and parts attached hereto and made a part thereof, and at his own cost and expense to furnish and perform everything necessary and required to construct and complete, ready for its intended purpose, in accordance with the Contract and such instructions as the Engineer may give, acceptable to the Authority, in the times provided, all of the Work covered and included under Contract No. _____ covering _____ as herein described.

THIRD: In consideration of the performance by the Contractor of his covenants and agreements as herein set forth, the Authority hereby covenants and agrees to pay the Contractor according to the Schedule of Prices set forth in the Proposal with additions and deductions as elsewhere herein provided in the times and in the manner stated in the Specifications. This Agreement shall insure to the benefit of, and shall be binding upon the parties hereto, and upon their respective successors and assigns; but neither party hereto shall assign or transfer his interest herein in whole or in part without the consent of the other, except as herein provided.

IN WITNESS WHEREOF the parties to this Agreement have executed the same in quintuplicate.

AUTHORITY -

MAINE TURNPIKE AUTHORITY

By: _____

Title: CHAIRMAN

Date of Signature: _____

ATTEST:

_____
Secretary

CONTRACTOR -

_____
CONTRACTOR

By: _____

Title: _____

Date of Signature: _____

WITNESS:

_____

CONTRACT BOND

KNOW ALL MEN BY THESE PRESENTS that _____

of _____ in the County of _____ and State of _____

as Principal, and _____ a Corporation duly organized under the

laws of the State of _____ and having a usual place of business in _____

_____

As Surety, are held and firmly bound unto the Maine Turnpike Authority in the sum of _____Dollars ($_____.___), to be paid to said Maine Turnpike Authority, or its successors, for which payment, well and truly to be made, we bind ourselves, our heirs, executors, successors and assigns jointly and severally by these presents.

The condition of this obligation is such that the Principal, designated as Contractor in the foregoing Contract No. _____ shall faithfully perform the Contract on his part and satisfy all claims and demands incurred for the same and shall pay all bills for labor, material, equipment and all other items contracted for, or used by him, in connection with the Work contemplated by said Contract, and shall fully reimburse the Obligee for all outlay and expense which the Obligee may incur in making good any default of said Principal, then this Obligation shall be null and void; otherwise it shall remain in full force and effect.

Signed and sealed this _____ day of _____, A.D., 201___

Witnesses: CONTRACTOR

_____ _____ *(SEAL)*

_____ _____ *(SEAL)*

_____ _____ *(SEAL)*

SURETY

_____ _____ *(SEAL)*

_____ _____ *(SEAL)*

_____ _____ *(SEAL)*

(Surety must attach copy of Power of Attorney showing authority of Office or Agent to execute bonds)

FINAL LIEN AND CLAIM WAIVER AND AFFIDAVIT

Upon receipt of the sum of _____, which sum represents the total amount paid, including the current payment for work done and materials supplied for Project No. _____, in _____, Maine, under the undersigned's Contract with the Maine Turnpike Authority.

The undersigned, on oath, states that the Final Payment of _____ is the final payment for all work, labor, materials, services and miscellaneous (all of which are hereinafter referred to as "Work Items") supplied to the said Project through _____and that no additional sum is claimed by the undersigned respecting said Project.

The undersigned, on oath, states that all persons and firms who supplied Work Items to the undersigned in connection with said Project have been fully paid by the undersigned for such Work Items or that such payment will be fully effected immediately upon receipt of this payment.

In consideration of the payment herewith made, the undersigned does fully and finally release and hold harmless the Maine Turnpike Authority, and its Surety, if any, from any and all claims, liens or right to claim or lien, arising out of this Project under any applicable bond, law or statute.

It is understood that this Affidavit is submitted to assure the Owner and others that all liens and claims relating to the Work Items furnished by the undersigned are paid.

_____
(Contractor)

By: _____

Title: _____

State of MAINE

County of _____

I, _____, hereby certify on behalf of _____
(Company Officer) *(Company Name)*

its _____, being first duly sworn and stated that the foregoing representations are
(Title)

are true and correct upon his own knowledge and that the foregoing is his free act and deed in said capacity and the free act and deed of the above-named

_____

.

(Company Name)

The above-named, _____, personally appeared before me this ____ day of _____ and swears that this is his free act and deed.

(SEAL)

_____
Notary Public

My Commission Expires: _____

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

PART I – SUPPLEMENTAL SPECIFICATIONS

Available at: http://www.maineturnpike.com/Projects-Planning/Construction-Contracts.aspx

(Rev. November 10, 2016)

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

PART II – SPECIAL PROVISIONS

PART II - SPECIAL PROVISIONS

MAINE TURNPIKE AUTHORITY

SPECIFICATIONS

PART II - SPECIAL PROVISIONS

All work shall be governed by the Maine Department of Transportation Standard Specifications, Revision of November 2014, except for that work which applies to sections of the Maine Department of Transportation Standard Specifications which are amended by the Maine Turnpike Supplemental Specifications and the following modifications, additions and deletions.

General Description of Work

The pavement rehabilitation works consists of milling and filling two 12-foot wide lanes and the four foot shoulder and the Exit 75 ramps from MM 74.9 to MM 80.7, excluding the area around the Washington Avenue Bridge. The work also involves partial depth pavement repairs, earthwork, drainage, guardrail, pavement markings, maintenance of traffic and all other work incidental thereto in accordance with the Plans and Specifications.

Plans

The drawings included in these Contract Documents, and referred to as the Plans, show the general character of the work to be done under this Contract. They bear the general title "Maine Turnpike – Contract 2018.12 – Pavement Rehabilitation, Guardrail, Drainage, and Clear Zone Improvements – MM 74.9 to MM 80.7". The right is reserved by the Resident to make such minor corrections or alterations in the Plans as he deems necessary without change in the unit prices on the Schedule of Prices of the Proposal.

101.2 Definition

Holidays

The following is added after Memorial Day in the Supplemental Specifications:

Independence Day 2018 (Fourth of July)	Noon Tuesday to Noon Thursday

103.4 Notice of Award

The following sentence is added:

The Maine Turnpike Authority Board is scheduled to consider the Contract Award on April 26, 2018.

104.3.8 Wage Rates and Labor Laws

Section 104.3.8 Wage Rates and Labor Laws has been amended as follows:

The fair minimum hourly rates determined by the State of Maine Department of Labor for this Contract are as follows:

THIS DOCUMENT MUST BE CLEARLY POSTED AT THE PERTAINING STATE FUNDED PREVAILING WAGE CONSTRUCTION SITE

State of Maine
Department of Labor
Bureau of Labor Standards
Augusta, Maine 04333-0045
Telephone (207) 623-7906

Wage Determination - In accordance with 26 MRSA §1301 et. seq., this is a determination by the Bureau of Labor Standards, of the fair minimum wage rate to be paid to laborers and workers employed on the below titled project.

Title of Project --------2018.12-Pavement Rehabilitation, Guardrail, Drainage and Clear Zone Improvements MM 74.9 to MM 80.7

Location of Project –Lewiston & Auburn, Androscoggin County

2018 Fair Minimum Wage Rates
Highway & Earth Androscoggin County

Occupation Title	Minimum Wage	Minimum Benefit	Total	Occupation Title	Minimum Wage	Minimum Benefit	Total
Asphalt Raker	$17.13	$0.58	$17.71	Ironworker – Ornamental	$23.13	$4.80	$27.93
Backhoe Loader Operator	$20.00	$2.23	$22.23	Ironworker - Reinforcing	$24.79	$10.60	$35.39
Boom Truck (Truck Crane) Operator	$21.66	$6.86	$28.52	Ironworker - Structural	$21.80	$4.88	$26.68
Bulldozer Operator	$22.60	$4.55	$27.15	Laborer (Includes Helper-Tender)	$14.50	$0.95	$15.45
Carpenter	$21.00	$2.36	$23.36	Laborer - Skilled	$17.00	$2.29	$19.29
Cement Mason/Finisher	$17.00	$0.56	$17.56	Line Erector-Power/Cable Splicer	$26.00	$7.59	$33.59
Crane Operator =>15 Tons)	$26.00	$5.97	$31.97	Loader Operator - Front-End	$19.00	$3.13	$22.13
Crusher Plant Operator	$17.50	$2.01	$19.51	Mechanic- Maintenance	$20.75	$2.95	$23.70
Diver	$28.50	$1.48	$29.98	Painter	$17.00	$0.00	$17.00
Driller -Rock	$18.38	$2.60	$20.98	Paver Operator	$19.57	$5.27	$24.84
Earth Auger Operator	$22.97	$6.17	$29.14	Pipelayer	$18.00	$3.16	$21.16
Electrician - Licensed	$26.00	$4.67	$30.67	Pump Installer	$21.00	$3.73	$24.73
Electrician Helper/Cable Puller (Licensed)	$17.00	$2.84	$19.84	Reclaimer Operator	$19.13	$2.98	$22.11
Elevator Constructor/Installer	$19.25	$1.62	$20.87	Roller Operator - Earth	$16.00	$1.89	$17.89
Excavator Operator	$21.25	$3.43	$24.68	Roller Operator - Pavement	$18.00	$4.26	$22.26
Fence Setter	$17.25	$1.72	$18.97	Screed/Wheelman	$18.60	$3.75	$22.35
Flagger	$12.00	$0.00	$12.00	Truck Driver - Light	$17.25	$2.52	$19.77
Grader/Scraper Operator	$21.33	$5.65	$26.98	Truck Driver - Medium	$18.00	$2.98	$20.98
Highway Worker/Guardrail Installer	$16.50	$0.79	$17.29	Truck Driver - Heavy	$16.00	$1.92	$17.92
Hot Top Plant Operator	$22.50	$3.83	$26.33	Truck Driver - Tractor Trailer	$19.00	$3.18	$22.18

The Laborer classifications include a wide range of work duties. Therefore, if any specific occupation to be employed on this project is not listed in this determination, call the Bureau of Labor Standards at the above number for further clarification.

Welders are classified in the trade to which the welding is incidental.

Apprentices - The minimum wage rate for registered apprentices are those set forth in the standards and policies of the Maine State Apprenticeship and Training Council for approved apprenticeship programs.

Posting of Schedule - Posting of this schedule is required in accordance with 26 MRSA §1301 et. seq., by any contractor holding a State contract for construction valued at $50,000 or more and any subcontractors to such a contractor.

Appeal - Any person affected by the determination of these rates may appeal to the Commissioner of Labor by filing a written notice with the Commissioner stating the specific grounds of the objection within ten (10) days from the filing of these rates.

Determination No: **HI-086-2018**

A true copy

Filing Date: **March 21, 2018**

Attest: Scott R. Cotnoir

Scott A. Cotnoir
Wage & Hour Director

Expiration Date: **12-31-2018**

BLS(Highway & Earth Androscoggin)

104.4.7 Cooperation With Other Contractors

This Subsection is amended by the addition of the following:

Adjacent contracts currently scheduled for the 2018 construction season include:

MTA Contract 2018.10 – Bridge and Culvert Repairs – 4 Locations (Mile 75.8 to Mile 91.9)

MTA Contract 2018.07 – Androscoggin River Bridges Substructure Repairs Mile 78.9

MTA Contract 2018.17 – Exit 75 Toll System and Slope Repairs

105.8.2 Permit Requirements

The Project is subject to the requirements of the Maine Pollutant Discharge Elimination System (MPDES) General Permit for Stormwater Discharge from Construction Activity, as promulgated by the US Environmental Protection Agency (US EPA) and Administrated by the Maine Department of Environmental Protection (DEP).

A Notice of Intent (NOI) was submitted by the Authority to the DEP for coverage under the Maine Construction General Permit (MCGP). Compliance with the erosion and sedimentation control requirements outlined in this Contract is required by the Contractor.

The Contractor shall prepare a LOD plan illustrating the Contractor's proposed limit of earthwork disturbance. The LOD plan shall show all construction access locations, field office locations, material and temporary waste storage locations, as well as include the Contract limits of earthwork disturbance. All applicable erosion and sedimentation control devices needed shall be detailed on the Contractor's LOD plan and are not limited to those devices shown on the Contract LOD plan. **This Plan shall be submitted for review and approval, to the Resident within 14 days of Contract award.** Payment for creating, revising, and completing this plan shall be incidental to Item 659.10, Mobilization.

The LOD for this Contract, which were submitted as part of the NOI, has been estimated to be **1.3** acres.

At any time during the Contract, if the Limit of Disturbance needs to be adjusted to accommodate construction activities, the Contractor shall resubmit the LOD plan (including any additional erosion and sedimentation control measures needed) to the Resident for review and approval prior to any additional disturbance taking place:

- If the cumulative area of disturbance exceeds the estimated LOD noted above, by less than one acre, the Resident shall have a minimum of five (5) working days to approve the revised LOD plan.
- If the cumulative area of disturbance exceeds the estimated LOD noted above, by over one acre, the Resident shall first approve of the plan and then possibly resubmit the NOI for MaineDEP approval. The approval may take a minimum of 21 working days.

Compliance with the erosion and sedimentation control requirements outlined in this Contract is required by the Contractor.

The Contractor shall comply with the conditions outlined in the Maine Pollutant Discharge Elimination System General Permit for stormwater discharge associated with construction activity. The Contractor shall indemnify and hold harmless the Maine Turnpike Authority or its agents, representatives and employees against any and all claims, liabilities or fines arising from or based on the violation of the above noted permits.

This Project is also subject to the requirements of the Maine Pollutant Discharge and Elimination System (MPDES) General Permit for the Discharge of Stormwater from MTA's Municipal Separate Storm Sewer Systems (MS4), because it is located within an Urbanized Area (UA) as defined by the 2000 census by the U.S. Bureau of the Census. MS4 compliance requires all Contractors to be properly trained in Erosion and Sedimentation Control (ESC) measures (as per Special Provision Subsections 105.8.1 and 656.07) and implement measures to reduce pollutants in stormwater runoff from construction activities.

107.1 Contract Time and Contract Completion Date

This Subsection is amended by the addition of the following:

The work shall be substantially complete on or before August 31, 2018and all work shall be completed on or before September 14, 2018.

107.1.1 Substantial Completion

This Subsection is amended by the addition of the following:

Substantially complete shall be defined by the Authority as the following:

- All paving and line work has been completed
- No lane closures, except for demobilization (removal of construction signs and drums and general clean-up).
- All disturbed slopes loamed, seeded and mulched, temporary erosion control mix and/or blanket installed where necessary, except for the establishment period.
- All guardrail work has been completed.
- All drainage work has been completed.

Supplemental Liquidated damages on a calendar day basis in accordance with Subsection 107.8 shall be assessed for each calendar day that substantial completion is not achieved.

107.4.6 Prosecution of Work

The following activities shall not begin until the date specified:

- Lane closures in the vicinity of Danville Corner Road will not be allowed until on or after June 15, 2016 based on the work performed for Bridge and Culvert Repairs Contract 2018.10.

Milling for partial depth construction shall take place after milling of pavement surface for project. Paving of partial depth construction areas, including placement of GlasGrid8511 shall occur during the same shift as milling.

SPECIAL PROVISION

SECTION 202

REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing Pavement Surface-Mainline)

202.01 Description

The following sentences are added:

This work shall also consist of removing the surface of the bituminous concrete pavement in all locations to the depth, width, grade, and cross section on the mainline as shown on the Plans or as directed by the Resident. The forty-five degree pavement safety edge needed between lanes 1 and 2 and between lane 2 and the eight foot shoulder shall be incidental to the 202 pay items.

Removal of approach pavement shall be completed through the use of a milling machine. The milling machine(s) shall be capable of accurately establishing profile grades by referencing from a floating straight edge, a minimum of 30 feet.

Areas requiring shim pavement to reach final pavement grade shall not be milled.

This work shall also consist of construction of temporary ramps at all butt joints as shown in the MaineDOT Standard Details, November 2014 Edition – Pavement Overlay Butt Joint Detail (Roadways), Page 202(01) or as approved by the Resident. The length of the temporary ramp shall be at least 1/2 L.

The following subsection is added:

202.061 Removing Pavement Surface

This Subsection is deleted and replaced with the following:

The equipment for removing the bituminous surface, excluding bridge decks, shall be a power-operated milling machine or planer capable of removing the bituminous concrete pavement to the required depth, transverse cross slope, and profile grade by use of an automated grade and slope control system. The controls shall automatically increase or decrease the pavement removal depth as required, and readily maintain desired cross slope to compensate for surface irregularities in the existing pavement course. The mill head on the machine shall have a maximum 8mm tooth spacing pattern and a minimum triple wrap configuration. The milling machine shall be capable of accurately establishing profile grades by referencing from a floating straight edge, minimum of 30± feet. The equipment shall also have an effective means for removing excess material from the surface and preventing flying material in compliance with Subsections 105.2.5 Compliance with Health and Safety Laws and 105.2.6 Convenience of the Public, of the Specification.

The Contractor shall locate, identify and remove all objects in the pavement through the work area that would be detrimental to the milling machine.

The Contractor shall be responsible for the layout of the longitudinal centerline between the travel lane and passing lane.

The finished milled surface will be inspected before being accepted, and any deviations in the profile exceeding 3/8 inch under a 16 foot string line or straightedge placed parallel to the centerline will be corrected. Any deviations in the cross slope that exceed 3/8 inch under a 10 foot string line or straightedge placed transversely to the centerline will be corrected. In no case shall the cross slope in a single lane width be inverted resulting in a depression as measured transverse to the direction of travel. Any cross slope inversions or depressions shall be corrected by spot shimming the area with HMA as directed by the resident prior to installing any leveling or wearing course. These corrections shall be done with no additional expense to the Authority.

All surplus pavement grindings, except for the amount specified above, shall be disposed of by the Contractor off the turnpike right-of-way. All grindings shall be disposed of in accordance with the Maine Department of Environmental Protection Solid Waste Management Requirements.

202.07 Method of Measurement

The removal of existing bituminous concrete pavement – mainline will be measured by the square yard of material removed to the required depth.

The following sentences are added:

Installation of temporary bituminous ramps will not be measured separately for payment, but shall be incidental to the Contract.

Removal of temporary bituminous ramps will not be measured separately for payment, but shall be incidental to the Contract.

202.08 Basis of Payment

Removing Pavement Surface – Mainline will be paid for at unit price per square yard which price shall be full compensation for removing and disposing of the bituminous and gravel materials.

Payment will be made under:

Pay Item		Pay Unit
202.202	Removing Pavement Surface – Mainline	Square Yard

SPECIAL PROVISION

SECTION 202

REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing Pavement Surface – Drainage Paths)

202.01 Description

The following paragraphs are added:

This work shall consist of grinding drainage paths in the existing inside and outside bituminous shoulders on the mainline and interchange ramps. The depth shall match the elevation of the adjacent milled travel lane. Locations and lengths of removal shall be as shown on the Plans or as directed by the Resident.

This work shall also consist of repaving the shoulder drainage paths with bituminous pavement to match the existing grades on each side of the drainage path to coincide with the paving operation of the adjacent travel lane as shown on the Plans or as directed by the Resident.

The following Subsection is added:

202.011 Materials

Grinding shall be done in accordance with Section 202.

Bituminous pavement shall conform to Section 401, Hot Mix Asphalt, 12.5 mm.

Bituminous tack coat shall conform to Section 409.

Joint sealant shall conform to Federal Specifications SS-S-1401C.

202.06 Removing Bituminous Concrete Pavement

This Subsection is deleted and replaced with the following:

The drainage paths shall be milled concurrently with the adjacent travel lane milling. The drainage paths shall be located such that they include all of any milled section of an impacted rumble strip.

The drainage paths shall be installed at the roadway low points of the sag vertical curves and at 500 foot intervals in both the outside and inside shoulders. Drainage paths shall not be installed within 500 feet of the crest of a vertical curve. The drainage paths shall extend from the edge of the milled travel lane (Lane 2) and daylight six feet into the outside shoulder and from the edge of the milled passing lane (Lane 1) and the edge of pavement (4'-0") without guardrail.

All grindings shall be disposed of in accordance with the Maine Department of Environmental Protection Solid Waste Management Requirements.

The Contractor may request that the Resident waive the requirement for the installation of drains at 500 foot intervals. The Resident will consider the weather forecast as well as the Contractor's proposed paving schedule when reviewing the request.

The tapered sides of the outside drainage paths shall be milled to form a vertical face prior to paving. The drainage paths shall be joint sealed, tack coated, and paved concurrently with the adjacent lane.

The Contractor shall not be required to replace the shoulder rumble strips removed for the drainage paths.

Vehicles will be permitted to traverse unfilled drainage paths.

202.07 Method of Measurement

The second paragraph is deleted and replaced with the following:

Removing Pavement Surface – Drainage Paths shall be measured by the square foot.

202.08 Basis of Payment

The following is added after the last paragraph:

Removing Pavement Surface – Drainage Paths shall be paid for at the Contract unit price per square foot which includes all grinding, tack coat, sealant, bituminous pavement, equipment, labor, and incidentals necessary to satisfactorily complete the work.

Payment will be made under:

Pay Item		Pay Unit
202.2026	Removing Pavement Surface – Drainage Paths	Square Foot

SPECIAL PROVISION

SECTION 202

REMOVING STRUCTURES AND OBSTRUCTIONS

(Rumble Strips)

202.01 Description

The following sentences are added after the first paragraph:

This work shall consist of cutting a pattern of rumble strips from MM 74.9 to MM 80.7 on the northbound and southbound roadways at the locations shown on the Plans. Rumble strips shall not be placed across ramp openings or on bridges.

The following Subsections are added:

202.065 Rumble Strips

The rumble strips shall not be cut until the Contractor has placed the permanent pavement markings at the required locations.

At proposed rumble strip locations, the bituminous concrete paved surface shall be removed by milling in strips as detailed on the Plans and as directed by the Resident. The pattern will be 80 feet of rumble strips followed by a 20 foot space repeated along the entire length on the outside shoulder. The inside shoulder shall be continuous. The rumble strips shall be normal to the baseline of the roadway on tangent sections and radial on curves. The Contractor shall be responsible for the layout of the rumble strips. The milling machines for this type of rumble strip are designed by:

Surface Preparation Technology
81 Texaco Road
Mechanicsburg, PA 17055
Tel. (717) 697-1450

L&C Flashing Barricades
60 Walpole Street
Canton, MA 02021
Tel. (508) 580-6700

Thomas Grinding
110 Fox Lane Southwest
Moore Haven, FL 33471
Tel. (863) 946-1461

The milling machine shall be equipped with a 20 foot pointer to provide longitudinal grade control.

202.07 Method of Measurement

The following paragraph is added:

Rumble Strips will be measured by the actual number cut, completed and accepted.

Layout of rumble strips, disposal of milled bituminous pavement and roadway cleanup will not be measured separately for payment, but shall be incidental to this item.

202.08 Basis of Payment

The following sentences are added:

Rumble Strips will be paid for at the Contract unit price per each, which price shall be full compensation for all labor, materials, equipment and incidental items of work for a complete installation.

Payment will be made under:

Pay Item		Pay Unit
202.205	Rumble Strips	Each

SPECIAL PROVISION

SECTION 202

REMOVING STRUCTURES AND OBSTRUCTIONS

(Removing Rumble Strips)

202.01 Description

The following paragraph is added:

This work shall consist of grinding existing rumble strip locations to a depth of 1-1/2 inches, coating vertical and horizontal surfaces with bituminous tack coat, and installing 1-1/2 inches of hot mix asphalt, 9.5 mm over the entire milled area. Locations and lengths of removal shall be as shown on the Plans or as approved by the Resident.

The following Subsections are added:

202.011 Materials

Grinding shall be done in accordance with Section 202. Bituminous tack coat shall conform to Section 409.

Hot mix asphalt, 9.5 mm shall conform to Section 401.

202.025 General

Existing rumble strips are approximately 16 inches long, seven inches wide, 1/2 inch deep, and spaced approximately every five inches.

202.07 Method of Measurement

The following paragraph is added:

Removing Rumble Strips shall be measured by the linear foot removed and accepted. Measurement shall be parallel to the baseline.

202.08 Basis of Payment

The following sentences are added:

Removing Rumble Strips shall be paid for at the Contract unit price per linear foot which includes all grinding, bituminous tack coat, pavement, equipment and labor necessary to satisfactorily complete the work.

Payment will be made under:

Pay Item		Pay Unit
202.206	Removing Rumble Strips	Linear Foot

SPECIAL PROVISION

SECTION 203

EXCAVATION AND EMBANKMENT

203.01 Description

The following paragraph is added:

This work shall consist of cutting, removing and disposing of the full depth of existing bituminous concrete pavement at the approaches to the bridge structures within the limits of work as shown on the Plans or as approved by the Resident. The pavement shall be sawcut to the full depth of pavement at the limits of the excavation to provide a clean, vertical cut surface.

203.04 General

The following sentence is added to the end of the third paragraph.

There are no approved waste storage areas or waste areas within the Project limits unless shown on the Plans. Unsuitable materials shall be disposed of off-site in accordance with Subsection 203.06.

All excavations shall be accomplished in accordance with the applicable OSHA Standards. The Resident reserves the right to request the Contractor to prepare an excavation plan. This plan shall include, but not necessarily be limited to, the limit and depth of excavation, side slope, shoring, trench box and utility support.

203.10 Embankment Construction - General

The thirteenth and fourteenth paragraphs are deleted and replaced with the following:

All portions of the embankment shall be compacted in accordance with the designated embankment compaction requirements specified for the Project.

The existing slopes should be benched as shown on the drawings prior to placing additional fill. Embankment fill should be placed in lifts which extend laterally beyond the limits of the design side slopes such that the specified degree of compaction is achieved within the limits of the completed embankment. The slopes should then be trimmed back to design dimensions.

203.16 Winter Construction of Embankments

The word “core” is deleted from the first and second sentences in the first paragraph.

203.18 Method of Measurement

The following paragraphs are added:

There will be no additional payment for the required excavation plan, and costs shall be incidental to the Excavation items.

SPECIAL PROVISION

SECTION 205

SHOULDER RECONSTRUCTION

(Widening of Existing Shoulder)
(Widening of Existing Shoulder Pavement)

205.01 Description

The following paragraph is added:

This work shall consist of widening existing outside shoulders as shown on the plans in areas of proposed single rail guardrail, or as approved by the Resident. The widening shall be done by excavating, furnishing, placing, grading and compacting aggregate subbase course gravel, granular borrow, common borrow, loam, seed, mulch and asphalt grindings in accordance with the thickness and typical sections shown on the Plans.

The following Subsections are added:

205.021 Granular Borrow

Granular borrow shall be material meeting the requirements of Subsection 703.19.

205.022 Fill Material

Fill material shall be existing excavation or common borrow from an outside source.

205.023 Asphalt Grindings

The grindings shall be reprocessed (crushed) to meet the following gradation:

Sieve Designation	Grading
3/4”	100
1/2”	95-100
No.4	50-80
No.50	18-28
No. 200	3-10

205.024 Aggregate Subbase Course-Gravel

Aggregate subbase course-gravel shall be material meeting the requirements of Subsection 703.06.

205.0511 Compaction - Asphalt Grindings

The asphalt grindings shall be placed and compacted to a minimum thickness of three inches unless otherwise designated by the Resident.

205.06 Method of Measurement

The following sentence is added:

The quantity of Widening of Existing Shoulder measured for payment shall be per linear foot at locations noted on the Plans.

Common Borrow will be measured in accordance with Section 203 of these Specifications.

205.11 Basis of Payment

The following paragraph is added:

The accepted quantity of Widening Existing Shoulder will be paid for at the Contract unit price per linear foot which shall include the asphalt grindings, excavation, aggregate subbase course gravel, granular borrow, loam, seed and mulch.

Common Borrow will be paid for in accordance with Section 203 of these Specifications.

Payment will be made under:

Pay Item		Pay Unit
205.511	Widening of Existing Shoulder	Linear Feet

SPECIAL PROVISION

SECTION 401

HOT MIX ASPHALT PAVEMENT

Section 401 of the Maine Turnpike Authority 2016 Supplemental Specifications is modified as follows:

401.01 Description

The following paragraph is added:

A Quality Control Plan(QCP) is required.

401.02 Materials

Section 401.02 is deleted in its entirety and replaced with the following:

Aggregates for HMA Pavements Coarse Aggregate and fine aggregate for HMA pavements shall be graded such that when combined in the proper proportions, including filler if required, the resultant blend will meet the composition of mixture for the type of pavement specified. Materials shall meet the requirements specified in Section 700 – Materials:

Asphalt Cement	702.01
Aggregates for HMA Pavement	703.07
RAP for HMA Pavement	703.08
HMA Mixture Composition	703.09

Mainline Surface HMA Coarse aggregate: The material retained on the No. 4 sieve, shall consist of angular fragments obtained from crushed quarry stone and be free of dirt or other objectionable materials. Coarse aggregate shall have a Micro-Deval value of 16.0 percent or less as determined by AASHTO T 327. The crushed stone shall have a maximum of 1.5% material finer than the No. 200 mesh when tested in accordance with AASHTO T-11. Flat and elongated particles shall not exceed a maximum of 8% at a 5:1 ratio in accordance with ASTM D-4791. Coarse aggregate angularity shall be a minimum of 95/90 in accordance with AASHTO T-335.

Mainline Surface HMA Fine aggregate: The material passing the No. 4 sieve, shall be crushed manufactured sand free from dirt, clay balls, or other objectionable material. Natural sand may be incorporated into the mix at a rate no greater than 13 percent by weight of total aggregate. The unconfined void content of the fine aggregate blend shall be a 45 minimum value when tested in accordance with AASHTO T-304, method A. AASHTO T-176 sand equivalent value shall be 45 minimum.

Asphalt Low Modulus Joint Sealer: Asphalt Low Modulus Joint Sealer shall be a modified asphalt and rubber compound designed for sealing and improving the strength and performance of the base asphalt cement and shall conform to ASTM D6690 Type IV and the following specifications:

Cone Penetration	90-150
Flow @ 60°C [140ºF]	3.0mm [1/8 in] max
Bond, non-immersed	Three 12.7mm [½ in] specimens pass 3 cycles @ 200% extension @ -29°C [-20ºF]
Resilience, %	60 min
Asphalt Compatibility, ASTM D5329	pass*

* There shall be no failure in adhesion, formation of any oily exudate at the interface between the sealant and asphaltic concrete or other deleterious effects on the asphaltic concrete or sealant when tested at 60°C [140ºF].

The contractor shall provide the Resident or authorized representative with a copy of the material manufacturer's recommendations pertaining to heating, application, and reheating prior to the beginning of operations or the changing of materials.

Section 401.03 Composition of Mixtures

Section 401.03 is deleted in its entirety and replaced with the following:

HMA pavement mixtures for local road and bridge projects shall be a currently approved MDOT design.

HMA pavement mixtures for Mainline paving projects shall conform to the following requirements:

The Contractor shall compose the Hot Mix Asphalt Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), and mineral filler if required. HMA shall be designed and tested according to AASHTO R35 and the volumetric criteria in Table 1. The Contractor shall size, uniformly grade, and combine the aggregate fractions in proportions that provide a mixture meeting the grading requirements of the Job Mix Formula (JMF). The Contractor may use a maximum of 15 percent reclaimed asphalt pavement (RAP) in any mainline surface course, and a maximum of 20 percent RAP in any base, intermediate, or shim course. Current MaineDOT approved designs with up to 20 percent RAP will be allowed on local roads.

The Contractor shall submit a job mix formula (JMF) developed for each specified mixture at least 30 days prior to placement.

The JMF shall establish a single percentage of aggregate passing each sieve size within the limits shown in Subsection 703.09. The mixture shall be designed and produced, including all production tolerances, to comply with the allowable control points for the particular type of mixture as outlined in Subsection 703.09. The JMF shall state the original source, gradation, and percentage to be used of each portion of the aggregate and mineral filler if required. It shall also state the proposed PGAB content, the name and location of the refiner, the supplier, the source of

PGAB submitted for approval, the type of PGAB modification if applicable, and the location of the terminal if applicable.

In addition, the Contractor shall provide the following information with the proposed JMF:

- Properly completed JMF indicating all mix properties (Gmm, VMA, VFB, etc.).
- Stockpile Gradation Summary.
- Test reports for individual aggregate consensus properties
- Design Aggregate Structure Consensus Property Summary.
- Design Aggregate Structure Trial Blend Gradation Plots (0.45 power chart).
- Trial Blend Test Results for at least three different aggregate blends.
- Selected design aggregate blend.
- Test results for the selected design aggregate blend at a minimum of three binder contents.
- Test results for final selected blend compacted to $N_{max.}$
- Specific Gravity for the PGAB to be used.
- Recommended mixing and compaction temperatures from the PGAB supplier.
- Material Safety Data Sheets (MSDS) For PGAB.
- Asphalt Content vs. Air Voids trial blend curve.
- Test report for Contractor's Verification sample.
- Summary of RAP test results (if used), including count, average and standard deviation of binder content and gradation.

At the time of JMF submittal, the Contractor shall identify and make available the stockpiles of all proposed aggregates at the plant site. There must be a minimum of 150 ton for stone stockpiles, 75 ton for sand stockpiles, and 50 ton of blend sand before the Authority will sample. The Authority shall obtain samples for laboratory testing. The Contractor shall also make available to the Authority the PGAB proposed for use in the mix in sufficient quantity to test the properties of the asphalt and to produce samples for testing of the mixture. Before the start of paving, the Contractor and the Authority shall split a production sample for evaluation. The Contractor shall test its split of the sample and determine if the results meet the requirements. If the results are found to be acceptable, the Contractor will forward their results to the Authority's Lab, which will test the Authority's split of the sample. The results of the two split samples will be compared and shared between the Authority and the Contractor. If the Authority finds the mixture acceptable, an approved JMF will be forwarded to the Contractor. The Authority will then

notify the Contractor that paving may commence. The first day's production shall be monitored, and the approval may be withdrawn if the mixture exhibits undesirable characteristics such as checking, shoving or displacement. The Contractor shall be allowed to submit aim changes within 24 hours of receipt of the first Acceptance test result for an individual JMF. Adjustments will be allowed of up to 2% on the percent passing the 2.36 mm sieve through the 0.075 mm and 3% on the percent passing the 4.75 mm or larger sieves. Adjustments will be allowed on the %PGAB of up to 0.2 percent. Adjustments will be allowed on GMM of up to 0.010.

The Contractor shall submit a new JMF for approval each time a change in material source or materials properties is proposed. The same approval process shall be followed. The cold feed percentage of any aggregate except natural sand may be adjusted up to 10 percentage points from the amount listed on the JMF, however no aggregate listed on the JMF shall be eliminated. Natural sand may be adjusted up to 5 percent from the amount listed on the JMF but shall not exceed 13% by weight of total aggregates. The cold feed percentage for RAP may be reduced up to five percentage points from the amount listed on the JMF and shall not exceed the percentage of RAP approved in the JMF or for the specific application.

TABLE 1
VOLUMETRIC DESIGN CRITERIA

Design ESAL's (Millions)	Required Density (Percent of G_{mm})			Voids in the Mineral Aggregate (VMA)(Minimum Percent) Nominal Maximum Aggregate Size (mm)				Voids Filled with Binder (VFB) (Minimum %)	Fines/Eff. Binder Ratio
	$N_{initial}$	N_{design}	N_{max}	19	12.5	9.5	4.75		
10 to <30	≤89.0	96.0	≤98.0	13.5	14.5	15.5	15.5	65-80*	0.6-1.2

** For 9.5 mm nominal maximum aggregate size mixtures, the maximum VFB is 82.*

** For 4.75 mm nominal maximum aggregate size mixtures, the maximum VFB is 84.*

** For 4.75mm nominal maximum aggregate size mixtures, the Fines/Effective Binder Ratio is 0.6-1.4*

As part of the JMF submittal, there are Hamburg Wheel Tracker requirements, the Contractor shall provide the Authority the test results in accordance with AASHTO T324. The results shall be generated by a third party independent testing laboratory as approved by the Authority. The test results shall meet the requirements of Table 1A

TABLE 1A
HAMBURG WHEEL TRACKER REQUIREMENTS

Specified PG Binder Grade	Test Temperature (ºC)	Maximum Rut Depth (mm)	Minimum Number of Passes	Minimum Allowable SIP*
64-28	45	12.5	20,000	15,000
64E-28	45	8.0	20,000	15,000
70E-34	45	6.3	20,000	15,000

* As calculated by the most recently published version of the Maine DOT HWT worksheet, which is available online at http://www.maine.gov/mdot/contractors/publications/

Section 401.08 Hauling Equipment Trucks for Hauling HMA

Add the following paragraph:

The undercarriage of haul units actively hauling HMA to the site shall be relatively free of dust / mud agglomerations. Haul units found to be contaminating the paving surface shall be removed from the site and cleaned prior to returning.

Section 401.091 Material Transfer Vehicle (MTV)

The fourth paragraph shall be deleted and replaced with:

The MTV shall be designed so that the mix receives additional mixing action.

Section 401.165 Longitudinal Joint Density

The first paragraph shall be deleted and replaced with:

When noted in Special Provision Section 403, the Authority will measure the pavement density of longitudinal joints between adjoining mainline travel lanes in both the unconfined and confined condition as determined by the days paving operation.

The eighth paragraph shall be deleted and replaced with:

The minimum density of the completed pavement shall be 92.0 percent of the theoretical maximum density obtained. Two consecutive failing tests shall result in production shut down. Prior to resuming paving operations, the contractor quality control unit shall satisfy the Authority that the paving operation will produce joint densities in compliance with the Specifications.

The eleventh paragraph and associated table shall be deleted and replaced with:

Payment reduction will be applied to each sublot that has a density lower than 92.0% as outlined below.

PERCENT COMPACTION	PERCENT PAY
92.0 or greater	100
91.9 to 90.0	95
89.9 or less	90

Section 401.17 Joints

The fourth paragraph shall be deleted and replaced with:

When required by Special Provision Section 403, Mainline Longitudinal joints shall be constructed as notched-wedge joint and constructed in a manner that will best ensure joint integrity.

Section 401.18 Quality Control

The following shall be added to section c. Quality Control Technician(s) QCT:

The QCT shall be on site during paving operations performing quality control activities. QCT's shall not act as equipment operators or laborers.

Section 401.191 Inspection/Testing

In paragraph nine delete and replace Item #8 with:

8. Secure High Speed Internet Access

SPECIAL PROVISION

SECTION 401

HOT MIX ASPHALT PAVEMENTS

(HMA using Hydrated Lime)

The following sections of Section 400 have been revised with following additional requirements.

401.01 Description

The Contractor shall compose Hot Mix Asphalt (HMA) Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), hydrated lime, and mineral filler if required. Hydrated Lime shall be utilized in all mixtures so denoted in Special Provision 403 - Hot Mix Asphalt Pavement.

401.02 Materials

Materials shall meet the requirements specified.

Hydrated Lime	AASHTO 216

401.03 Composition of Mixtures

The Contractor shall compose the Hot Mix Asphalt Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), hydrated lime and mineral filler if required. HMA shall be designed and tested according to AASHTO R35 and the volumetric criteria in Table 1. The Contractor shall size, uniformly grade, and combine the aggregate fractions in proportions that provide a mixture meeting the grading requirements of the Job Mix Formula (JMF).

Hydrated lime shall be used in all HMA at a rate of one percent (1%) by weight of the total dry aggregate including RAP aggregate, if used. The Contractor shall obtain a shipping ticket for each shipment of hydrated lime. The Contractor shall provide the Resident with a copy of each shipping ticket from the supplier, including the date, time and weight of hydrated lime shipped and used in HMA production. The Contractor shall submit a material data sheet for the hydrated lime to the Resident for approval.

The Contractor shall provide the following information with the proposed JMF:

Material Safety Data Sheets (MSDS) for hydrated lime

Supplier and source for Hydrated Lime

401.13 Preparation of Aggregates

The Contractor shall add water to the aggregates as required to maintain a minimum total aggregate moisture content of 3 percent. The Contractor shall mix the lime uniformly with the aggregate before introducing the aggregate into the dryer or dryer drum. Hydrated lime introduction systems must be controlled by a proportioning device to the amount required on the JMF plus or minus 0.1% of the target.

The Contractor shall add lime to the aggregate by one of the following methods:

A. The Contractor shall add lime to the combined cold feed aggregate using an enclosed in-line cold feed mechanical pugmill mixer. The Contractor shall use a twin-shaft, continuous mixing pugmill with mixing paddles to thoroughly blend the lime with the aggregate. The Contractor shall adjust the retention time of the mixture in the pugmill so no unmixed lime is visible after the lime and aggregate exit the pugmill.

B. The Contractor shall add lime to the produced aggregates during stockpiling using a pugmill. The Contractor shall distribute the lime per the stockpile ratios stated in the asphalt concrete mix design. A minimum moisture content of 2 percent by dry weight for coarse aggregate and 4 percent by dry weight for fine aggregate is required at the time the aggregates and lime are mixed. The Contractor shall marinate treated aggregate in stockpiles from 24 hours to 60 days before using in asphalt concrete mix. Do not use aggregate marinated longer than 60 days.

C. The Contractor shall add lime to the combined cold feed aggregate by introducing the lime between aggregate layers as the aggregate flows from the cold feed bins. The Contractor shall thoroughly mix the lime and aggregate on the conveyor belt. The Contractor shall provide a lime introduction system so that no unmixed lime is visible before the lime and combined aggregate enter the drum.

D. Other methods of hydrated lime introduction as approved by the Authority.

The cold storage for hydrated lime shall be a separate bulk storage bin with a vane feeder or other approved feeder system which can be readily calibrated. The system shall provide a means for convenient sampling of the hydrated lime additive and verifying the quantity of lime dispensed. If the hydrated lime is to be introduced directly into the plant then the additive equipment shall be synchronized with the cold feed controls to operate concurrently with the cold feed operation. The system will be configured to automatically adjust the hydrated lime feed to variations in the cold aggregate feed. The hydrated lime system shall have out-of-tolerance sensing ability by weight, and have a means to indicate the out–of–tolerance condition.

401.14 Mixing

Hydrated lime shall be added into the HMA aggregate mixture prior to the aggregate blend mixing with the PGAB. Aggregate feed rate, or pugmill mixing times shall be adjusted to ensure complete blending of Hydrated Lime and aggregate before the PGAB is added.

401.18 Quality Control

The Contractor shall provide a written supplement to the project specific QCP outlining the proposed methods of adding and mixing the hydrated lime for approval by the Authority. This written summary shall also provide information describing how the Contractor will perform quality control on the addition of hydrated lime, specifically the method of introduction and how the lime use will be measured to assure that the specified percentage is consistently added, and appropriately mixed. The supplemental QCP covering hydrated lime introduction shall be provided to the Authority at least one week prior to the prepave meeting.

SPECIAL PROVISION

SECTION 403

HOT MIX ASPHALT PAVEMENT

403.01 Description

This work shall also consist of the construction, maintenance and removal of all temporary bituminous ramps at locations as shown on the Plans or as directed by the Resident.

403.02 General

The Contractor shall compose the Hot Mix Asphalt Pavement with aggregate, Performance Graded Asphalt Binder (PGAB), and mineral filler if required. The Performance Graded Asphalt Binder (PGAB) shall be polymer modified as detailed in this special provision and shall conform to the requirements of AASHTO M 332 (including Appendix 1). The PG64E-28 Binder shall contain a minimum of 2.25% Styrene-Butadiene-Styrene (SBS) polymer {BWT} in a homogeneous blend with a minimum average percent recovery of 75% as determined by AASHTO T350 @ 3.2 kPA (R3.2) on RTFO residue at 64ºC to assure significant polymer load and performance. The stability of the modified binder shall be verified in accordance with ATSM D7173 using the Dynamic Shear Rheometer (DSR). The DSR G*/sin(δ) results from the top and bottom sections of the ATSM D7173 test shall not differ by more than 10%. The results of ASTM D7173 shall be included on the Certified Test Report.

403.03 Construction

All areas which have been milled or overlaid shall have a minimum length temporary ramp constructed as determined by the Resident at the milled or overlaid limits prior to opening the roadway to traffic. Temporary ramps shall be constructed using the same material as being placed on that day or as directed by the Resident. All temporary ramps are to be constructed on a sand joint. The Contractor shall be responsible for all repairs and maintenance required for the temporary ramps.

The Contractor shall be responsible for the layout of the longitudinal centerline between the travel lanes.

The sand and loose debris adjacent to the median guardrail shall be removed and disposed of by the Contractor off of Turnpike property.

The forty-five degree pavement safety edge needed between lanes 1 and 2 shall be incidental to the 202 pay items.

A minimum test strip of 100 tons placed at a nominal depth of 1 ½ inches, full lane width, shall be required. It shall be evaluated under testing requirements for mix volumetric and density. The exact location will be identified by the Authority. Prior to placement of the test strip, a leveling course (Item 403.211) shall be placed at the chosen location. A fog coat of Item 409.15, Bituminous Tack Coat, shall be applied to the level course prior to the placement of the HMA surface course, payment to be made under the 409.15 pay item. The test strip will be excluded from the remainder of the projects' QA analysis. The Contractor shall notify the

Authority at least 48 hours in advance of placing the test strip. The test strip is intended to allow the Contractor to establish a method of compaction and adjust plant settings prior to mainline plant production.

403.04 Method of Measurement

The construction and removal of temporary ramps on sand joints, and maintaining the ramps will not be measured separately for payment, but shall be incidental to Items 403.

The removal of sand and loose debris will not be measured separately for payment, but shall be incidental to paving items.

Hot Mix Asphalt, 12.5 mm (Polymer Modified pavement with (up to) 15% RAP, placed as a wearing surface will be measured under Item 403.2081 Hot Mix Asphalt, 12.5 mm (Polymer Modified) - RAP.

403.05 Basis of Payment

Hot Mix Asphalt, 12.5 mm (Polymer Modified) pavement with (up to) 15% RAP, placed as a wearing surface will be paid under Item 403.2081 Hot Mix Asphalt, 12.5 mm (Polymer Modified) – RAP.

The following pay items are added:

Pay Item		Pay Unit
403.2081	Hot Mix Asphalt, 12.5 mm (Polymer Modified) – RAP	Ton

SPECIAL PROVISION

SECTION 403

HOT MIX ASPHALT PAVEMENT

Course	HMA Grading	Item Number	Total Thickness	No. of Layers	Complimentary Notes

Mainline Mill and Fill and Shim and Overlay

Wearing	**12.5mm**	**403.2081**	**1.5”**	**1**	**A,C,F,G,H,I,J,K,L,M,N,O**
Intermediate	**12.5mm**	**403.208**	**1.75”**	**1**	**B,E,J,L,N**
Base	**12.5mm**	**403.208**	**1.75”**	**1**	**B,E,J,L,N**
Shim	**4.75mm**	**403.211**	**½”**	**1**	**B,E,J,L,N**

COMPLEMENTARY NOTES

A. The required PGAB for this mixture shall be **64E-28.**
B. The required PGAB for this mixture shall be **64-28.**
C. A maximum of 15 percent RAP may be used.
D. RAP may not be used.
E. The Maine DOT will conduct the job mix verification. The aggregate qualities shall meet the design traffic level of 3 to <10 million ESALS for mix placed under this contract. The design verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**. (N design) Minimum and Maximum PGAB content shall not apply.
F. The MTA will conduct the job mix verification. The aggregate qualities shall meet the design traffic level of 10 to <30 million ESALS for mix placed under this contract. The design verification, Quality Control, and Acceptance tests for this mix will be performed at **75 gyrations**. (N design)
G. A material transfer vehicle (MTV) shall be used for the placement of Hot Mix Asphalt wearing surface on all roadways including acceleration and deceleration lanes and all ramps.
H. Joints shall be constructed as the “notched wedge” type in accordance with Subsection 401.17.
I. Joint density will be measured in accordance with Subsection 401.165.
J. Tack coat shall be applied between all layers of pavement at a rate of 0.04 G/SY.
K. PGAB shall conform to the provisions of 403.02 – Polymer Modified PGAB for HMA
L. The contractor shall furnish a quality control technician equipped with an approved densometer to ensure density requirements are met.
M. Hydrated Lime shall be incorporated into the mixture.
N. No vehicular loads shall be permitted on newly completed pavement until adequate stability has been attained and the material has cooled sufficiently to prevent distortion or loss of fines. The newly paved area may be opened to traffic after the internal temperature of the pavement has cooled to 120° F. The Resident will test the internal temperature of the pavement and shall be the sole judge as to the opening to traffic. The period of time before opening to traffic may be extended at the discretion of the Resident. The lane closure may not be removed until the internal temperature has cooled to 120° F.

O. The warm mix/antistrip additive Zycotherm manufactured by Zydex Industries shall be incorporated into the PGAB at a rate of 0.1%.

SPECIAL PROVISION

SECTION 409

BITUMINOUS TACK COAT

409.02 Bituminous Material

This Subsection is deleted and replaced with the following:

Bituminous material shall conform to the Specifications for Emulsified Asphalt RS-1, of the AASHTO Designation M-140.

409.05 Equipment

Add "or as determined by the Resident", after the words "gal/yd^2]" in the fourth line of the second paragraph of this Subsection.

409.06 Preparation of Surface

The following paragraph is added:

All existing pavement and shoulder areas on which bituminous concrete mixtures are to be placed shall receive a tack coat. The surface area where the tack coat is to be applied shall be dry and cleaned of all dirt, sand, and loose material. Cleaning shall be accomplished by use of revolving brooms or mechanical sweepers. Undesirable material not removed by the above means shall be cleaned by hand sweeping or scraping, or a combination of both. Small areas otherwise inaccessible may be swept with hand brooms. The tack coat shall be applied only when the existing surface is dry.

409.08 Method of Measurement

The following paragraphs are added:

Measurement will be based on delivery slips made out in duplicate by the Contractor and signed by the Resident, or his representative, at the point of delivery. One of these slips shall be retained by the Resident and one by the Contractor. Delivery slips shall be furnished by the Contractor and shall provide space for identifying the vehicle and driver, for stating the volume of material carried, the source of the material, the date, and the Resident or his representative's signature.

Material included in the delivery slips and not used or rejected shall be deducted from the amount being measured for payment. Each day's delivery slips shall be reconciled by the Contractor and the Resident within 24-hours.

Cleaning of the surface area where tack coat is to be applied shall be incidental to Item 409.15, Bituminous Tack Coat - Applied.

409.09 Basis of Payment

The following pay items are added:

Pay Item		Pay Unit
409.15	Bituminous Tack Coat – Applied	Gallon

SPECIAL PROVISION

SECTION 424

ASPHALT RUBBER MASTIC CRACK SEALER

424.01 Description

This work shall consist of the furnishing and placement of a mastic material in the longitudinal, transverse, and random cracks of the milled bituminous concrete pavement in accordance with these Special Provisions.

Placement shall consist of:

1. Crack cleaning and drying
2. Material preparation and application
3. Material finishing and shaping.

424.02 Materials

GAP 201 Mastic shall be supplied by Maxwell Products or an approved equal designed especially for improving the strength and performance of the base asphalt cement with sealant and engineered aggregates.

424.03 Weather

Mastic shall not be applied on a wet surface or when the atmospheric temperature is below 45°F as determined by an approved thermometer (placed in the shade at the crack sealing location), or when weather conditions are otherwise unfavorable for proper construction procedures.

424.04 Equipment

Equipment used in the performance of the work shall be subject to the Resident's or authorized representative's approval and shall be maintained in a satisfactory working condition at all times.

(a) Air Compressor: Air compressors shall be portable and capable of furnishing not less than 4 yd^3 of air per minute at not less than 90 psi pressure at the nozzle. The compressor shall be equipped with traps that will maintain the compressed air free of oil and water.

(b) Sweeper: Manually operated, gas powered air-broom or self-propelled sweeper designed especially for use in cleaning pavements shall he used to remove debris, dirt, and dust from the cracks.

(c) Hot Air Lance: Should operate with propane and compressed air in combination at 2000°F - 3000°F, exit air heated at 310 m/s [1000 ft/s]. The lance should draw propane from no smaller than a 100 pound tank using separate hoses for propane and air draw. The hoses shall be wrapped together with reflectorized wrap to keep them together and to protect workers in low light situations.

(d) Hand Tools: Shall consist of V-shaped squeegee. brooms, shovels, metal bars with chisel shaped ends, and any other tools which may be satisfactorily used to accomplish this work. The joints shall be raked open.

(e) Melting Kettle: The unit used to melt the joint sealing compound shall be a double boiler. indirect fired type. The space between inner and outer shells shall he filled with a suitable heat transfer oil or substitute having a flash point of not less than 320°C [608°F]. The kettle shall he equipped with a satisfactory means of agitating and mixing the joint sealer with 90% fibers at all times. This may be accomplished by continuous stirring with mechanically operated paddles and/or a continuous circulating gear pump attached to the heating unit. The kettle must be equipped with thermostatic control calibrated between 200°F and 550°F.

424.05 Preparations of Cracks

All cracks greater than 1 ¼ in shall be blown free and raked off of loose material, dirt, vegetation, and other debris by high pressure air. Material removed from the crack shall be removed from the pavement surface by means of a power sweeper or appropriate hand tools as required. Cracks showing evidence of vegetation after being blown out shall be additionally cleaned by appropriate hand tools and additionally blown out. All cracks must be blown and heated via the hot air lance 10 minutes prior to the crack being sealed. Distance between the hot air lance and the crack sealing unit should be no more than 50 ft to eliminate reinvasion of water, debris, and other incompressibles. All debris, vegetation, and water shall be removed to enhance adhesion of the crack sealing material. This work shall not be done in inclement weather.

424.06 Preparation and Placement of Sealer

The mastic material shall be heated and applied at the temperature specified by the manufacturer and approved by the Resident or authorized representative. Any material that has been heated above the manufacturer's specification longer than thirty minutes shall not be used. Material that is reheated or held at temperature for an extended period of time may be used as allowed by the manufacturer's specification and approval of the Resident or authorized representative. The Contractor shall provide the Resident or authorized representative with a suitable device for verifying the mastic temperature in the kettle and at the application site.

Any over application or spills are to be removed to the satisfaction of the Resident or authorized representative. Any sealed areas with damaged or contaminated sealer or visible voids are to be removed, prepared and resealed.

Mastic shall be delivered to the crack while the cracks are still hot from the hot air lance preparation through a pressure hose line and applicator shoe.. The cracks are to be filled, struck off with a 2” overband on each side and smoothed at the surface of the milled surface. A heated steel hotplate may be used on the surface of the repair area after the mastic has been applied. Any loose material on the surface or in the crack, which may contaminate the crack sealer or impede bonding of the sealant to the pavement, is to be removed by hand tools prior to crack filling. No crack filling material shall be applied in a crack that is wet or where frost, snow, or ice is present.

424.07 Quality of Work

A Maxwell Products representative shall be present to verify the proper application, installation, material and pavement preparation on the first days' production. Excess of spilled mastic shall be removed from the pavement by approved methods and discarded. Any quality of work determined to be below normal acceptable standards will not be accepted and will be corrected and/or replaced as directed by the Resident or authorized representative at no additional expense to the Authority.

424.08 Method of Measurement

Asphalt Rubber Mastic Crack Sealer - Applied will be measured by the pound of mastic used. The manufacturer's weights of the mastic will be accepted as the basis for measurement.

424.09 Basis of Payment.

Asphalt Rubber Mastic Crack Sealer – Applied will be paid for at the contract unit price per pound complete in place. This price shall be full compensation for furnishing and placing crack sealer, including cleaning and drying cracks; and furnishing all labor, materials, tools, equipment and incidentals necessary to complete the work.

Payment will be made under:

Pay Item		Pay Unit
424.323	Asphalt Rubber Mastic Crack Sealer - Applied	Pound

SPECIAL PROVISION

SECTION 427

PAVEMENT CRACK REPAIR

427.01 Description

This work shall consist of grinding the existing bituminous pavement to the depth and width as shown on the plans and coating the vertical and horizontal surfaces with a bituminous tack coat, and placing hot bituminous pavement over the entire milled area. The exact limits of the repair will be determined by the Resident in the field after the pavement has been milled.

427.02 Materials

Grinding shall be done in accordance with Section 202 of the Standard Specifications.

Bituminous tack coat shall conform to Section 409.

Hot Mix Asphalt, 12.5 mm shall be a MaineDOT approved mix that conforms to Section 401.

427.03 General

The bituminous concrete pavement to be milled shall be accurately marked before beginning the milling operation. The marking shall be in accordance with the locations as shown on the Plans or as approved by the Resident. The milling machine shall be capable of removing the pavement to the required width and depth in one pass.

Residue or debris from the milling operation shall be removed immediately and legally disposed of by the Contractor off of Turnpike property.

427.04 Method of Measurement

Pavement Crack Repair shall be measured by the linear foot removed, in filled and accepted. Measurement shall be parallel to the baseline.

Hot mix asphalt, bituminous tack coat and hot rubberized asphalt will not be paid for separately, but shall be incidental to the 427.09 pay item.

427.05 Basis of Payment

Pavement Crack Repair shall be paid for at the Contract unit price per linear foot. This price shall be full compensation for all materials, equipment, labor, and incidental items necessary to satisfactorily complete the work.

Payment will be made under:

Pay Item		Pay Unit
427.09	Pavement Crack Repair	Linear Foot

SPECIAL PROVISION

SECTION 429

PAVEMENT REINFORCING SYSTEM

(Grid/Paving Fabric Composite Pavement Interlayer)

429.01 Description

This work consists of furnishing and placing a section of GlasGrid8511 interlayer in the HMA base layers. GlasGrid8511 shall be installed as indicated in this specification.

429.02 General

The bituminous concrete pavement shall be milled 5 ½" deep in the locations in the plans. The marking of the layout shall be as approved by the Resident.

The GlasGrid8511 interlayer shall be placed between the two 1 ¾" layers of 12.5 mm HMA as shown on the plans.

429.03 Method of Measurement

The Grid/Paving Fabric Composite Pavement Interlayer shall be measured by the square foot of pavement in place.

419.04 Basis of Payment

The accepted quantity of Grid/Paving Fabric Composite Pavement Interlayer will be paid for at the Contract unit price per square foot which shall be full compensation for all materials, tools, equipment labor, and all incidentals necessary for the completion of the work to the satisfaction of the Resident.

Payment will be made under:

Pay Item		Pay Unit
429.341	Grid/Paving Fabric Composite Pavement Interlayer	Square Foot

SPECIAL PROVISION

SECTION 470

BERM DROP OFF CORRECTION

(Berm Dropoff Correction - Grindings)

470.01 Description

This work shall consist of furnishing and placing bituminous grindings to eliminate the berm dropoff along the inside and outside shoulder edges at all locations, including guardrail sections at locations shown on the plans or as directed by the Resident.

470.02 Bituminous Materials

The recycled bituminous pavement shall be reprocessed (crushed) to meet the following gradations:

Sieve Designation	Percentage by Weight Passing Square Mesh Sieve
¾"	100
½"	95-100
No. 4	50-80
No. 50	18-28
No. 200	3-10

470.03 Method of Construction

Work under this item shall be in accordance with the details as shown on the Plans or as directed by the Resident.

At a minimum, a walk behind plate compactor shall be used for compaction. Other methods may be used upon approval by the Resident.

470.04 Method of Measurement

Berm Dropoff Correction – Grindings will be measured by the ton of Pavement grindings delivered and installed.

Material included in the delivery slips and not used or rejected shall be deducted from the amount being measured for payment.

470.05 Basis of Payment

The accepted quantity of "Berm Dropoff Correction – Grindings" will be paid for at the contract unit price per ton, which price shall include all materials, crushing to gradation range,

weighing, transportation, placement, labor, equipment, and all incidentals necessary to accomplish the work.

Payment will be made under:

Pay Item		Pay Unit
470.08	Berm Dropoff Correction – Grindings	Ton

SPECIAL PROVISION

SECTION 527

ENERGY ABSORBING UNIT

(Energy Absorbing System (CAT) – Remove and Stack)

527.01 Description

The following sentences are added:

This work consists of removing and stacking existing Crash-cushion Attenuating Terminal (CAT) System at the Crosby Maintenance Yard at MM 46 Southbound, backfilling post holes, and repairing pavements as required.

527.04 Method of Measurement

Energy Absorbing System (CAT) – Remove and Stack will be measured by each unit satisfactorily removed and stacked.

527.05 Basis of Payment

Energy Absorbing System (CAT) – Remove and Stack will be paid for at the Contract unit price each, which price shall be full compensation for removing and stacking Energy Absorbing System (CAT) for furnishing all labor, equipment, materials and incidentals necessary to complete the work.

Payment will be made under:

Pay Item		Pay Unit
527.304	Energy Absorbing System (CAT) – Remove and Stack	Each

SPECIAL PROVISION

SECTION 603

PIPE CULVERTS AND STORM DRAINS

(Reinforced Concrete Pipe)
(Concrete Collar)
(Corrugated Polyethylene Pipe)

603.01 Description

The following paragraphs are added:

This work shall also consist of furnishing and installing Class III or Class V reinforced concrete pipe at the locations as shown on the Plans or as approved by the Resident.

This work also consists of furnishing and installing a concrete collar to join existing concrete pipe to the proposed concrete or Corrugated High Density Polyethylene (HDPE) pipe in accordance with the details as shown on the Plans. The Contractor shall note that the concrete pipe ends may be of different sizes and may not fit snugly together.

This work shall also consist of furnishing and installing various sizes of corrugated HDPE pipe, including a dual wall adaptor fitting by Hancor or an approved equal as shown on the plans. No other pipe types within the Option III alternatives will be accepted.

603.02 Materials

All Corrugated High Density Polyethylene (HDPE) pipe for storm water and drainage systems shall meet the requirements of Subsection 706.06.

603.11 Method of Measurement

The following paragraph is added:

The Concrete Collar shall be measured by each unit installed, complete in place and accepted. This shall be full compensation for furnishing labor and materials to construct a Concrete Collar to connect the existing and proposed pipe ends in a working like manner.

Dual Wall Adapter Fitting shall be included for payment as three additional linear feet of the largest pipe involved.

603.12 Basis of Payment

Concrete Collars will be paid for at the Contract unit price each regardless of the size of the existing and proposed pipes.

Corrugated HDPE pipe will be paid for under the appropriate sized Culvert Pipe Option III pay items

Payment will be made under:

Pay Item		Pay Unit
603.155	12 inch Reinforced Concrete Pipe - Class III	Linear Foot
603.28	Concrete Collar	Each

SPECIAL PROVISION

SECTION 604

MANHOLES, INLETS AND CATCH BASINS

604.01 Description

This Subsection is amended by the addition of the following*:*

The Type II work shall consist of rebuilding catch basins as specified in the Specifications to grade, removing the existing unsound concrete, frame and grate, applying a bead of Elastometic sealer to the frame seat and reinstalling the existing grate in accordance with these Specifications and in reasonable close conformity with the lines and grades as shown on the Plans.

The work locations are listed on the Drainage Summary sheets of the Plans.

604.02 Materials

The following sentences are added:

Elastomeric sealer shall be Sikaflex 1a as manufactured by Sika or an approved equal.

Class AAA concrete shall conform to Subsection 502.05; except that the minimum cement factor shall be 750 pounds per cubic yard and the coarse aggregate size shall conform to ASTM C33 Grading 7.

The third paragraph should be deleted and replaced with:

Catch Basin Frames and Grates shall be as outlined below and be manufactured by EJ Company of Brockton, Massachusetts or an approved equal and shall meet or exceed the AASHTO M306 Loading Requirements.

Catch Basin Frames shall be manufactured by EJ Company of Brockton, Massachusetts (or an approved equal) with the following product numbers:

5521Z - 8 Inch Frame Product Number 00552111
5546Z – 6 Inch Frame Product Number 00554611
5544Z - 4 Inch Frame Product Number 00554411

Catch Basin Frames shall be 8” frames unless otherwise specified by the plans or approved by the resident.

Catch Basin Grates shall be a square holed grate as manufactured by EJ Company of Brockton, Massachusetts (or an approved equal) with the following product number:

5520M5 Grate Product Number 00552060

If a cascade catch basin grate is specified on the plans then it shall be manufactured by EJ Company of Brockton, Massachusetts (or an approved equal) with the following product numbers depending on the direction of flow:

5520M8 Product Number 00552084 or 5520M8 Product Number 00552085

604.04 Altering, Adjusting, and Rebuilding Catch Basins and Manholes

This Subsection is deleted and replaced with the following:

When adjusting the existing catch basins they shall be dismantled sufficiently to allow reconstruction in accordance with the following requirements and as shown on the Plans:

Any frame or grate damaged by the Contractor's operations shall be replaced by the Contractor at no additional cost to the Authority. Replacement frame and grate shall meet the requirements of Subsection 604.02. Damaged frames and grates shall become the property of the Contractor and shall be removed from Turnpike property.

Rebuild Catch Basin to Grade – Type II

The existing frame and grate shall be removed, stacked and reset. Remove all unsound concrete and anchor rods shall be removed to sound concrete as determined by the Resident. Install four Number 4 dowels, twelve inches in length, in each sidewall, reform catch basin to necessary grade using Class AAA concrete. The existing frame shall be reinstalled to the pavement grade as determined by the Resident.

Prior to installation of the grate, the frame shall be cleaned to accept a bead of elastomeric sealer. Sealer shall be placed in a continuous bead over the horizontal surface in accordance with the manufacturer's recommendation. The existing grate shall be reinstalled and allowed to set for a minimum of 1 ½-hour before receiving traffic loads.

604.05 Method of Measurement

The following are added after Subsection e. Grate:

Rebuild Catch Basin to Grade – Type II will be measured for payment by each unit rebuilt, secured and accepted.

Each unit includes removing and replacing a depth up to 12 inches from the bottom of the frame to the top of sound concrete in the wall. Each six inches of concrete removed and replaced over 12 inches will be measured for payment as one eighth (1/8) of a unit. Depth measurements in excess of the dimensions authorized will not be included.

604.06 Basis of Payment

The following paragraphs are added after the first paragraph:

The accepted quantity of Rebuild Catch Basin to Grade – Type II will be paid for at the Contract unit price each. This price shall be full compensation for removing existing frame and grate, rebuilding the catch basin top to grade, reinstalling the existing frame, cleaning the horizontal surface, applying the elastomeric sealer, reinstalling the existing grate, and all other labor, equipment and materials required to complete the work.

The second paragraph is deleted and replaced with the following:

Excavation and backfill will not be measured separately for payment, but shall be incidental to the following pay items.

Payment will be made under:

Pay Item		Pay Unit
604.184	Rebuild Catch Basin to Grade – Type II	Each

SPECIAL PROVISION

SECTION 606

GUARDRAIL

((Terminal End - Remove and Stack)

606.01 Description

The following sentences are added:

This work shall also consist of removing existing terminal end elements, component parts and hardware, and resetting to the proper location.

This work shall also consist of removing existing terminal end elements, component parts and hardware, and stacking at Crosby Maintenance Yard, located at Mile Marker 46 (SB).

In locations where new guardrail is being installed on the departure side, terminal ends are required as end treatments. These terminal ends shall be provided from the ones designated under this item to be stacked. Installation of these terminal ends shall also be included under this item.

606.08 Method of Measurement

The following sentences are added:

Terminal End - Remove and Stack will be measured by each unit satisfactorily stacked.

Terminal ends removed, but not suitable to be reset or stacked shall become property of the Contractor. Payment shall be incidental to the other guardrail pay items.

606.09 Basis of Payment

The following paragraphs are added:

The accepted quantity of Terminal End – Remove and Stack will be paid for at the Contract unit price bid which shall be full compensation for removing and stacking the terminal end and all equipment, labor and incidentals necessary to complete the work. This price shall be full compensation for removing all rails, posts, offset brackets, nuts, bolts, washers, hardware, all labor, transportation and all other incidentals necessary to complete the work. No additional compensation will be made for furnishing terminal ends from the stacked location and installing them on the departure side of the new guardrail, but shall be incidental to the Remove and Stack Terminal End item.

Payment will be made under:

Pay Item		Pay Unit
606.2652	Terminal End - Remove and Stack	Each

SPECIAL PROVISION

SECTION 606

GUARDRAIL

(Terminal End - Anchored End)

606.01 Description

The following sentence is added:

This work shall consist of furnishing and installing Terminal End – Anchored End end treatments in accordance with these Specifications, the AASHTO-AGC-ARBTA Joint Committee Task Force 13 Report: A Guide to Standardized Highway Barrier Hardware, dated May 1995; and in reasonably close conformity with the lines and grades as shown on the Plans or as approved by the Resident.

606.02 Materials

The following sentences are added:

The guardrail elements shall be per the Components' List found on Sheet No. 2 of 2 of Drawing SEW02a – Trailing End Terminal – Foundation Tube Option in the Task Force 13 Report noted above and/or as noted in the Contract Documents.

The following Subsection is added:

606.042 Terminal End - Anchored End

Installation of the Terminal End – Anchored End shall be in strict accordance with the AASHTO-AGC-ARBTA Joint Committee Task Force 13 Report and the Details on Sheet No. 1 of 2 of Drawing SEW02a – Trailing End Terminal – Foundation Tube Option.

Height of installation of Terminal End – Anchored End units shall be 27.5-inches to the top of rail, transitioning to the standard height of 30-inches over a 25-foot length of Type 3d rail located immediately after the last post of the Anchored End unit.

The reveal on the soil tube for the Anchored End units shall not exceed 3.5-inches. If site grading is required to achieve the required rail height and soil tube reveal height, then such work will be incidental to the installation of the Anchored End units

606.08 Method of Measurement

The second paragraph is amended by the addition of: "Terminal End - Anchored End," after the words "NCHRP 350 end treatments,".

606.09 Basis of Payment

The second paragraph is amended by the addition of: “Terminal End - Anchored End,” after the words “NCHRP 350 end treatments,”.

Payment will be made under:

Pay Item		Pay Unit
606.278	Terminal End - Anchored End	Each

SPECIAL PROVISION

SECTION 606

GUARDRAIL

(Delineator Post - Remove and Stack)

606.01 Description

The following paragraphs are added:

This work shall also consist of furnishing and installing new delineator posts and/or removing and resetting and/or removing and stacking existing delineator posts within the Contract limits at the Crosby Maintenance Facility at Mile Marker 46 Southbound. The existing reflectorized delineator panels shall be removed and replaced with new reflectorized delineator panels as required by the Resident.

Existing and new delineator posts shall be located as follows, with the indicated panel:

Outside Shoulder:

- One at guardrail trailing ends (green delineator).
- Two at guardrail approach ends (one red delineator on first post and one red delineator on angle points.)

Median:

- One at guardrail trailing ends (green delineator, facing traffic).
- Two at guardrail approach ends (one red delineator on first post of CAT units, green on guard rail side, red on median opening side; and one red (both sides) delineator at angle point.)
- One at all other median guardrail angle points (red on both sides)

Other Locations:

- One at culvert outlets (green delineator).
- Twenty per mile evenly spaced at the edge of outside shoulder (white delineator).
- One at electrical junction boxes not associated with another item (red delineator).
- One at communication only junction boxes not associates with another item(orange delineator).

Delineator posts that do not exist in the locations described above, shall be supplied and installed by the Contractor. The installation of the delineator post shall include the demountable reflectorized delineator panel.

White edge delineators shall not be installed on any portion of the widened shoulder for Guardrail 350 Flared Terminal installations, and shall not be installed behind the Guardrail 350 Flared Terminal rail segments.

606.02 Materials

The following paragraphs are added:

Non-guardrail Delineator Posts shall conform to Subsection 606.02 paragraph 3.

The seventh through ninth sentences of the fourth paragraph are deleted and replaced with the following:

Reflectorized flexible guardrail markers shall be a minimum of 2-inches in diameter, a maximum of 36” in length, ovalized at the top of the post to allow application of 3 inch by 9 inch high intensity reflective sheeting, and shall be capable of recovering from repeated impacts. The flexible guardrail delineator markers shall be grey and capped at the top with a flexible rubber cap; Safe-Hit Flexible Guardrail Delineator or approved equal. Reflective material shall meet the requirements of ASTM Type IX Diamond Grade VIP (Visual Impact Performance).

The demountable reflectorized delineator panels shall meet the material requirements of Subsection 719.06. The delineator panel shall be rectangles measuring 9" x 3".

606.03 Posts

The following paragraphs are added:

The top of delineator posts shall be installed 4’ - 6” (54”)) above edge of pavement elevation. Delineators shall be installed four feet from edge of pavement except those delineating end treatments, culverts and electrical items.

Mile marker posts shall be mounted on breakaway supports. The bottom of the sign shall be 5’ - 0” (60”) above the pavement at the solid white line and shall be offset five feet from the edge of pavement.

A mock-up of the guardrail delineator posts shall be submitted to the Resident for approval prior to installation.

Any materials damaged by the Contractor’s operations shall be replaced at no additional cost to the Authority.

Top of the delineator panel shall be flush with the top of post.

606.08 Method of Measurement

The following paragraphs are added:

Delineator Posts shall be measured by each unit satisfactorily installedDelineator Posts Removed and Stacked will be measured by each unit satisfactorily removed and stacked.

606.09 Basis of Payment

The following sentences are added:

The accepted quantity of Delineator Posts will be paid for under the Underdrain Delineator Post item, at the Contract unit price per each which price shall be full compensation for the post and specified delineator or mile marker panel, complete in place.

The accepted quantity of Delineator Posts Removed and Stacked will be paid for at the Contract unit price each, which price shall be full compensation for removing and stacking delineator panel or mile marker panel and posts and all incidentals necessary to complete the work.

Payment will be made under:

Pay Item		Pay Unit
606.3562	Delineator Post - Remove and Stack	Each

SPECIAL PROVISION

SECTION 606

GUARDRAIL

(Guardrail – Remove, Modify and Reset, Double Rail)
(Guardrail Adjust – Single Rail)
(Guardrail Adjust – Double Rail)

606.01 Description

The following paragraphs are added:

This work shall also consist of adjusting the height of the existing single and double rail guardrail in locations where the existing height of rail is not 30 inches. The guardrail shall be adjusted to a height of 30 inches. Existing single and double rail shall also be adjusted for lean.

The guardrail adjustment shall take place at all necessary locations; approximate locations are listed in the schedule of guardrail limits both median and outside shoulder. Exact locations for adjustment shall be determined by the Resident. If, during the course of the work, the contractor finds additional rail to be adjusted, then he shall notify the Resident, and the Resident determine if the rail is to be adjusted.

This work shall also consist of removing, stockpiling and stacking of existing double guardrail elements, component parts and hardware suitable for replacement as approved by the Resident. At the completion of the Contract, any unused guardrail elements, posts, component parts and hardware suitable for reuse shall remain the property of the Authority. Any guardrail elements, posts, component parts and hardware unsuitable for reuse shall become property of the Contractor.

Stockpiled materials, suitable for reuse, shall be utilized on Remove, Modify and Reset items prior to new materials being paid for.

Guardrail materials may be temporarily stockpiled at the Crosby Maintenance Facility at MM 46 Southbound.

This work shall consist of removing, disposing of existing guardrail elements, component parts and hardware, as directed by the Resident. All materials shall become the property of the Contractor and shall be removed from the site at the completion of the Project. The Contractor shall provide the Resident with an affidavit stating the final location of all disposed material and that the material was disposed of in accordance with the Maine Department of Environmental Protection Solid Waste Regulations.

606.02 Materials

The following paragraph is added at the end of the subsection:

New non-wood offset blocks conforming to NCHRP 350 Test Level 3 shall be installed on all guardrail being reset. The existing steel offset brackets and backup plates shall become the property of the contractor.

The following Subsection is added:

606.021 General

All existing guardrail to be raised or lowered shall be completed prior to new guardrail or end treatments being attached.

606.036 Adjusting Existing Guardrail

Any materials or galvanizing damaged by the Contractor's operations shall be replaced or touched-up at no additional cost to the Authority.

Guardrail posts shall be raised to a minimum of five inches above final elevation prior to driving post to final elevation; this applies to both raising and lowering rail.

Any given length of guardrail to be adjusted shall be done in such a way that top of rail elevations do not vary drastically between each section of guardrail. Rail height tolerance shall be 30 inches, plus 0 inches, minus 1/2 inch. The 30 inches shall be measured from the edge of pavement to the top of rail beam when within 2 feet of the edge of pavement.

Rail shall be adjusted for lean where needed. All posts shall be plumb after adjusting for lean.

When the rail tapers from one bound to the other the rail shall be adjusted to the correct height on the farthest ends and shall be adjusted towards the center of the median to create a smooth line.

Earth around each adjusted or reset post shall be raked and compacted with a minimum 8 pound hand tamper or an approved device. Holes created due to adjusting or resetting a post shall be filled with a similar surrounding material and compacted.

606.08 Method of Measurement

The following paragraphs are added:

Adjusting of both single and double rail guardrail shall be measured by the linear foot of Guardrail adjusted and accepted.

Raking and compacting the earth around each reset post with a minimum 8 pound hand tamper or an approved device, and infilling and compacting holes created due to resetting posts with a similar surrounding material wil not be paid separately, but shall be incidental to the Guardrail - Remove, Modify and Reset Pay or Guardrail - Adjust pay items.

Guardrail removed and not reset or stacked shall be incidental to Contract Items and include all removal, disposal, equipment and labor necessary to satisfactorily complete the work.

Steel posts to replace damaged posts shall come from the stockpile of guardrail components to be disposed of, from this Contract and will not be measured separately for payment. If, in the opinion of the Resident, there are no suitable steel posts in the stockpile then steel posts will be measured for payment.

W-beam rail elements to replace damaged rail elements shall come from the stockpile of guardrail from the Remove and Stack or the guardrail to be disposed of from this Contract and will not be measured separately for payment. If, in the opinion of the Resident, there are no suitable W-beam rail elements in the stockpile then the W-beam rail elements will be measured for payment.

606.09 Basis of Payment

The following paragraphs are added:

Adjusting of single and double rail guardrail will be paid for at the Contract unit price per linear foot and shall be full compensation for furnishing all labor, equipment and materials necessary to complete the work. Guardrail Adjust will not be measured for payment until all compaction has been completed.

The accepted quantity of guardrail removal will be paid for at the Contract unit price bid, which price shall be full compensation for removing, transporting and stacking all guardrail elements, component parts and hardware, equipment, labor and all incidentals necessary to complete the work. No additional payment will be made for double rail.

Payment will be made under:

Pay Item		Pay Unit
606.3606	Guardrail – Remove, Modify, and Reset Double Rail	Linear Foot
606.3621	Guardrail Adjust, Single Rail	Linear Foot
606.3622	Guardrail Adjust, Double Rail	Linear Foot

SPECIAL PROVISION

SECTION 606

GUARDRAIL

(Single Offset Block – W-Beam)

606.01 Description

The following paragraph is added:

This work shall consist of furnishing and installing single offset blocks at all existing guardrail beam locations that are not part of a new or remove, modify and reset location and as shown on the Contract Documents. New NCHRP 350 compliant offset block shall be installed on existing galvanized steel posts and connected to Guardrail Type 3d.

606.02 Materials

The following sentences are added:

Offset blocks shall have passed NCHRP 350 Test Level 3 and shall not be wood.

The following Subsection is added:

606.021 General

The existing median guardrail posts have four off-center bolt holes used to attach the existing steel offset blocks. The new offset blocks have two bolt holes centered on the W-beam section. The existing posts must be retrofitted to receive the new non-wood offset block assembly. Additional bolt holes required in the existing posts shall be drilled or punched but the size shall not exceed the dimension given by the manufacturer. Metal around the holes shall be cleaned and painted with a cold-applied zinc-rich paint. The holes shall not be burned with a torch.

The completed guardrail system shall be in conformance with the NCHRP 350 Test Level 3 requirements.

606.08 Method of Measurement

The following paragraphs are added:
Single Offset Block - W-Beam shall be measured per each unit installed and accepted.

606.09 Basis of Payment

The following paragraphs are added:

New Single Offset Block - W-Beam furnished and installed at specified locations will be paid for at the Contract unit price each complete in place and accepted. Payment shall be full

compensation for furnishing all labor, equipment and materials necessary to complete the work including, but not necessarily limited to, removal of existing rail beam, removal and disposal of existing offset block, drilling new holes in existing post, application of galvanized paint, furnishing and installing new non-wood offset block, removal and disposal of back-up plates, and resetting the rail beam.

Payment will be made under:

Pay Item		Pay Unit
606.471	Single Offset Block – W-Beam	Each

SPECIAL PROVISION

SECTION 606

GUARDRAIL

(Widen Shoulder for Guardrail 350 Flared Terminal)
(Modify Widened Shoulder for Guardrail 350 Flared Terminal)

606.01 Description

The following sentence is added:

Widen Shoulder for Guardrail 350 Flared Terminal work shall consist of widening the existing shoulder at specified Guardrail 350 Flared Terminal locations by excavating, furnishing, grading and compacting new shoulder aggregate subbase course gravel, granular borrow, common borrow, and asphalt grindings in accordance with the thickness and typical sections as shown on the Plans or as approved by the Resident.

Modify Widened Shoulder for Guardrail 350 Flared Terminal work shall consist of regrading the existing widened shoulder by excavating, furnishing, grading and compacting new shoulder untreated aggregate surface course, common borrow, and asphalt grindings in accordance with the thickness and typical sections as shown on the Plans or as approved by the Resident.

The following Subsections are added:

606.021 Granular Borrow

Granular borrow shall be material meeting the requirements of Subsection 703.19.

606.022 Fill Material

Fill material shall be existing excavation or common borrow from an outside source.

606.023 Asphalt Grindings

Asphalt grindings shall consist of pavement millings created by the cold planning process. The asphalt grindings stockpile must be viewed and approved by the Resident prior to any grindings being placed at any location.

The grindings shall be reprocessed (crushed) to meet the following gradation:

SIEVE DESIGNATION	GRADING
3/4”	100
1/2”	95 - 100
No. 4	50 - 80
No. 50	18 - 28
No. 200	3 - 10

606.024 Aggregate Subbase Course-Gravel

Aggregate subbase course-gravel shall be material meeting the requirements of Subsection 703.06.

606.025 Untreated Aggregate Surface Course

Untreated aggregate surface course shall be material meeting the requirements of Subsection 703.10.

606.051 Compaction - Asphalt Grindings

The asphalt grindings shall be placed and compacted to a minimum thickness of three inches unless otherwise designated by the Resident.

606.08 Method of Measurement

Widen Shoulder for Guardrail 350 Flared Terminal will be paid at the contract unit price per each.

Modify Widened Shoulder for Guardrail 350 Flared Terminal will be paid at the contract unit price per each.

Common borrow will be measured in accordance with Section 203 of these Specifications.

Loam, seed and mulch will not be measured separately but shall be incidental to the Widen Shoulder for Guardrail 350 Flared Terminal pay item and the Modify Widened Shoulder for Guardrail 350 Flared Terminal.

606.09 Basis of Payment

The following paragraphs are added:

The accepted quantity of Widen Shoulder for Guardrail 350 Flared Terminal and Modify Widened Shoulder for Guardrail 350 Flared Terminal shall also include the excavation, asphalt grindings, aggregate subbase course gravel, granular borrow, loam, seed, fertilizer, and mulch.

Common borrow will be measured in accordance with Section 203 of these Specifications.

Payment will be made under:

Pay Item		Pay Unit
606.755	Modify Widened Shoulder for Guardrail 350 Flared Terminal	Each

SPECIAL PROVISION

SECTION 606

GUARDRAIL

(Guardrail - 350 Flared Terminal)

606.01 Description

The following sentences are added:

This work shall consist of furnishing and installing a Guardrail 350 FLEAT (Flared Energy Absorbing Terminal) as manufactured by Road Systems, Inc., 1507 East 4th Street, Big Spring, Texas 79720, (915) 263-2435, and retroreflective adhesive sheeting in accordance with these Specifications and the manufacturer's installation instructions, and in reasonably close conformity with the lines and grades as shown on the Plans or as approved by the Resident.

606.02 Materials

The following sentence is added:

Reflective sheeting shall meet the requirements of Subsection 719.01, Reflective Sheeting – minimum ASTM Type XI; 3M™ Diamond Grade™ DG³ Reflective Sheeting Series 4000 or approved equal, color WHITE.

The following Subsections are added:

606.03 Posts

Wood offset blocks shall be toe-nailed in two locations to the wood post to prevent the blocks from moving.

606.035 Construction Requirements

The Contractor shall submit a set of installation drawings to the Resident for approval. The system shall be installed in accordance with the manufacturer's recommendation and the installation drawings.

Height of installation of New Guardrail 350 FLEAT units shall be 27.5-inches to the top of rail, transitioning to the standard height of 30-inches over a 25-foot length of Type 3d Single rail located immediately after the last post of the Guardrail 350 FLEAT unit.

The reveal on soil tubes for post #1 and #2 of the Guardrail 350 FLEAT units shall not exceed 3.5-inches. If site grading is required to achieve the required rail height and soil tube reveal height, then such work will be incidental to the installation of the Guardrail 350 FLEAT units.

A reflective adhesive sheeting shall be applied to the nose of the FLEAT System after installation. The existing sheeting shall be replaced on FLEAT systems to be removed, modified, and reset. Color – WHITE.

606.041 Reflective Sheeting

The color for the reflective sheeting shall be silver (WHITE) when installed on the outside shoulder. Black chevron on yellow background will not be acceptable.

606.08 Method of Measurement

The second paragraph is amended by the addition of: "Guardrail 350 Flared Terminal" after the words "breakaway cable terminal".

Guardrail 350 Flared Terminal – New will be measured by each unit satisfactorily complete in place and accepted.

606.09 Basis of Payment

The second paragraph is amended by the addition of: "and Guardrail 350 Flared Terminal" after the words "breakaway cable terminal".

The retroreflective sheeting will not be measured separately for payment, but shall be incidental to the Guardrail 350 Flared Terminal item.

SPECIAL PROVISION

SECTION 613

EROSION CONTROL BLANKET

613.01 Description

This work shall also include seeding, mulching and watering the median swale and/or longitudinal flow line to the limits and width as shown on the Plans or as directed by the Resident.

613.02 Materials

The following sentences are added:

Seeding shall meet the requirements of Section 618, Seeding, Method Number 2.

Mulch shall meet the requirements of Section 619.

The following Subsection is added:

613.041 Maintenance and Acceptance

See Section 618.10 for maintenance and acceptance of seeding.

613.042 Mulch

All mulch shall be placed after the area has been seeded and prior to the installation of the Erosion Control Blanket.

613.09 Basis of Payment

The following "and mulch" is added after the words "initial seeding" in the second sentence.

SPECIAL PROVISION

SECTION 619

MULCH

(Mulch – Plan Quantity)
(Temporary Mulch)

619.01 Description

The first paragraph is modified by the addition of the following:

"as a temporary or permanent erosion control measure" after the word "mulch".

Add the following sentence at the end of the first paragraph:

Refer to Section 656 Temporary Soil and Water Pollution Control, for more information on Temporary Mulch.

619.03 General

The first paragraph is deleted and replaced with the following:

Cellulose fiber mulch shall not be used within 200 feet of a wetland or stream. The limits shall be 200 feet up station and down station of the wetland or streams as well as the slopes adjacent to the stream. The application of hay or straw mulch with an approved binder shall be used at these locations to prevent erosion.

The use of cellulose fiber mulch will only be allowed at other areas with the approval of the Resident. The Contractor may be required to demonstrate that the material may be applied in a manner that will prevent erosion and will aid in the establishment of permanent vegetation. The Resident reserves the right to require the use of hay or straw mulch at all locations if he determines that the cellulose mulch is ineffective. Cellulose fiber mulch is not acceptable for winter stabilization.

610.06 Method of Measurement

The following sentence is added:

Temporary Mulch will be paid for by the lump sum.

656.10 Basis of Payment

Temporary Mulch will be paid for at the Contract price per lump sum which shall be full compensation for furnishing and spreading the Temporary Mulch as many times as necessary as determined by the Contractor's operations and staging. The price shall also include the additional mulch netting and snow removal necessary during the winter months.

Payment will be made under:

Pay Item		Pay Unit
619.1201	Mulch – Plan Quantity	Unit
619.1202	Temporary Mulch	Lump Sum

SPECIAL PROVISION

SECTION 627

PAVEMENT MARKINGS

(White or Yellow Pavement Marking Line)

627.01 Description

The following sentences are added:

This work shall consist of furnishing and placing the final pavement markings at locations as shown on the Plans or as directed by the Resident.

The following sentence is added:

This work shall consist of furnishing and placing pavement marking paint and temporary pavement marking paint at locations as shown on the Plans or as directed by the Resident.

627.02 Materials

The following is added before the last paragraph:

The paint for pavement markings shall be 100% acrylic waterbase paint.

627.04 General

The following is added to the third paragraph:

Dotted white lines (DWL) shall consist of alternate 3 foot painted line segments and 9 foot gaps.

Permanent pavement marking paint shall be applied at the end of each work week prior to opening the work area to traffic or as approved by the Resident.

Temporary pavement marking paint and temporary pavement markers shall be applied daily prior to opening the work area to traffic during non-work hours or as approved by the Resident.

627.08 Removing Lines and Markings

The last sentence is deleted and is not replaced.

627.09 Method of Measurement

The second and third sentences in the second paragraph are deleted and replaced with the following:

The measurement of broken white lines, both permanent and temporary and dotted white lines, will include the gaps when painted. Temporary painted pavement marking lines will be measured for payment by the linear foot.

627.10 Basis of Payment

This Subsection is deleted and replaced with the following:

The accepted quantity of white or yellow pavement marking lines will be paid at the Contract price per linear foot. This price shall include all labor and materials to furnish, and install the paint line.

The accepted quantity of broken and dotted white pavement marking lines will be paid at the Contract price per linear foot. This price shall include all labor and materials to furnish and install the paint line.

The accepted quantity of temporary white or yellow pavement marking lines will be paid at the Contract price per linear foot. This price shall include all labor and materials to furnish, install and maintain the paint marking.

Payment will be made under:

Pay Item		Pay Unit
627.712	White or Yellow Pavement Marking Line	Linear Foot

SPECIAL PROVISION

SECTION 627

PAVEMENT MARKINGS

(Temporary Raised Pavement Markers)

627.01 Description

The following sentence is added:

This work shall consist of furnishing, placing and removing temporary raised pavement markers at locations as shown on the Plans or as directed by the Resident.

627.02 Materials

The second paragraph is deleted and replaced with the following:

The temporary raised pavement markers shall be white or yellow one way markers (Type Tom W-1, Y-1, Grade WZ) as distributed by Davidson Plastics Co. (DAPCO), Kent, WA, or an approved equal. Colors shall conform to 2009 MUTCD requirements.

627.04 General

The following sentences are added:

Temporary raised pavement markers shall be used to delineate travel lanes (BWLL) after placement of the surface course (HMA 12.5 mm).

Temporary raised pavement marker that lose reflectivity, becomes broken, dislodged or missing during the life of the Contract shall be replaced by the Contractor at no additional cost to the Authority.

The spacing and number of temporary pavement markers installed as edge lines shall be the same as shown for the BWLL on the Plans for Temporary Pavement Marking.

627.09 Method of Measurement

The following sentence is added:

Temporary Raised Pavement Markers will be measured by each unit, complete in place, maintained and accepted.

627.10 Basis of Payment

The following paragraphs are added:

The accepted quantity of Temporary Raised Pavement Markers white and/or yellow will be paid for at the Contract price each. This price shall include all labor and materials to furnish, install, maintain, and remove the markers.

Payment will be made under:

Pay Item		Pay Unit
627.812	Temporary Raised Pavement Markers	Each

SPECIAL PROVISION

SECTION 627

PAVEMENT MARKINGS

(Pavement Marking Tape)
(Pavement Marking Tape – Dotted White Lane Line, 6-inch Width)

627.01 Description

The following sentence is added:

This work shall consist of furnishing and placing reflective pavement marking tape in conformity with the Plans, as specified herein and as directed by the Resident.

The pavement marking tape shall be installed at all locations.

627.02 Materials

The following sentence is added:

For the Broken White Lane Line (BWLL), Pavement Marking Tape shall be 3M Stamark™ High Performance Tape Series 380AW – High Performance pavement marking tape, color- white, six (6) inch width, as manufactured by 3M of St. Paul, Minnesota.

For the Dotted White Lane Line (DWLL), Pavement Marking Tape shall be 3M Stamark™ High Performance Tape Series 380I ES – High Performance pavement marking tape, color- white, six (6) inch wide and twelve (12) inch wide, as manufactured by 3M of St. Paul, Minnesota.

3M Traffic Safety Systems Division
Mr. Michael D. Allen
Tel: (401) 368-0438
Email: mdallen@mmm.com

627.04 General

The following paragraphs are added:

The tape shall be used as a supplemental broken white lane line. The tape shall be installed between the painted Broken White Lane Line (BWLL) spaced eighty (80) foot center to center as shown on the Plans. The length of the tape shall be three (3) feet.

The tape shall also be used to mark a Dotted White Lane Line (DWLL) and shall be installed on parallel deceleration and acceleration lanes at locations as noted in the Plans. On deceleration lanes, the tape shall be installed from the beginning of the full width deceleration lane and shall extend to the theoretical gore markings. On acceleration lanes, the DWLL shall extend from the theoretical gore markings to a point one-half of the total length of the acceleration lane (including the lane taper length). Layout data is noted on the Plans. Dotted White Lane Line tape

shall be three (3) foot in length and shall be spaced nine (9) feet apart. Spacing from the Solid White Lane Line (SWLL) or the Theoretical Gore Markings shall be nine (9) feet.

627.05 Preparation of Surface

The following paragraph is added:

The Contractor shall mill a groove in the pavement for each tape length to be placed ("in-and-out" pattern). Continuous grooving for installation of the tape shall not be allowed. The groove length shall be the required tape length plus 12 inches on both ends. Tape length spacing shall be as shown on the plans. The groove width for inlaid tape pavement marking shall be the pavement marking width plus 1 inch, with a tolerance of ± ¼ inch. The groove shall have a uniform depth of 150 Mils (±20 Mils). Groove position shall be a minimum of 2 inches from the edge of the pavement marking to the longitudinal pavement joint. The bottom of the groove shall have a smooth, flat finished surface. The use of gang stacked Diamond cutting blades is required for asphalt pavement surfaces. The spacers between blade cuts shall be such that there will be less than a 10 mil rise in the finished groove between the blades.

Grooves shall be clean, dry and free of laitance, oil, dirt, grease, paint or other foreign contaminants. The Contractor shall prevent traffic from traversing the grooves, and re-clean grooves, as necessary, prior to application of the primer and pavement marking tape. Depth plates shall be provided by the contractor to assure that desired groove depth is achieved.

Reference is made to 3M Information Folder 5.18 Grooving Applications, May 2011, "Application Guidelines for Pavement Marking in Grooved Pavement Surfaces."

627.09 Method of Measurements

The following paragraph is added:

The quantity of Pavement Marking Tape measured for payment will be the linear feet of tape in place and accepted. The measurement will not include the gaps.

627.10 Basis of Payment

The following paragraphs are added:

The accepted quantity of pavement marking tape will be paid for at the Contract unit price per linear foot which price shall include all material, pavement grooving, equipment, labor and incidentals necessary to complete the work.

Payment will be made under:

Pay Item		Pay Unit
627.94	Pavement Marking Tape	Linear Foot
627.941	Pavement Marking Tape – Dotted White Lane Line, 6-inch Width	Linear Foot

SPECIAL PROVISION

SECTION 652

MAINTENANCE OF TRAFFIC

(Specific Project Maintenance of Traffic Requirements)

This Specification describes the specific project maintenance of traffic requirements for this Project.

The following minimum traffic requirements shall be maintained. These requirements may be adjusted based on the traffic volume when authorized by the Authority.

The minimum width required for traffic during the following operations, are shown on the Traffic Control Plans.

- Milling and Paving Operations
- Drainage Installation and/or Adjustment
- Guardrail Improvements
- Median Opening and Shoulder Widenings
- Pavement Markings Layout and Placement

All temporary lane closures shall be made utilizing drums.

Three cones or drums shall be placed transversely across the closed lane for every quarter mile of lane closure.

The Contractor will be allowed to store drums on the traffic side of the guardrail (face of guardrail) during non-work hours or when drums are not required for a lane closure. The drums shall be placed no more than six inches from the face of guardrail. If there is a Lane 2 closure the drums need to be stored on non-traffic side of the guardrail.

Temporary lane closures shall be removed if construction is not ongoing. Unattended lane closures are not allowed unless included in the contract language or approved by the Resident as a long term traffic control operation.

Portable light towers will be required to illuminate the night construction work area.

Maine Turnpike Traffic Control Requirements

This Section outlines the minimum requirements that shall be maintained for work on, over, or adjacent to the Maine Turnpike roadway. Operations are allowed as outlined below:

Temporary Mainline Lane Closures	24 hours per day starting at 7:00 p.m. Sunday thru 6:00 p.m. Friday
Temporary Mainline Shoulder Closures	24 hours per day starting at 7:00 p.m. Sunday thru 6:00 p.m. Friday

Exception: Lane Closures will NOT be allowed Northbound on Fridays from 3 p.m. to 5:30 p.m. from June 1 to October 15.

652.7 Method of Measurement

The following paragraph is added:

Traffic control devices required to complete the work will be measured for payment under their respective pay items. Installation, maintenance, and removal of traffic setups and the Contractor's dedicated traffic employee's will not be measured separately for payment, but shall be incidental to Item 652.361, Maintenance of Traffic Control Devices.

SPECIAL PROVISION

SECTION 652

MAINTENANCE OF TRAFFIC

(General)

Section 652 of the Maine Turnpike Authority 2016 Supplemental Specifications is modified as follows:

652.1 Description

The following sentence is added to the second paragraph:

652.3.5 Installation of Traffic Control Devices

This Subsection is amended by the addition of the following after the first paragraph.

All signs shall be mounted on easels except the following which shall be mounted on NCHRP 350 approved posts, unless behind guardrail.

- G20-1 ROAD WORK NEXT 6 MILES
- G20-2 END ROAD WORK
- G20-5aP WORK ZONE*
- R2-1 SPEED LIMIT 50*
- R2-6aP FINES DOUBLE*
- R2-12 END WORK ZONE SPEED LIMIT*
- R4-9P STAY IN LANE
- W8-11 UNEVEN LANES
- W8-15 GROOVED PAVEMENT
- W8-15P MOTORCYCLES (Graphic)
- W20-1 ROAD WORK AHEAD*
- CS-45 WIDE LOADS
- CS-48 WIDE LOADS
- LOGO S MAINE TURNPIKE
- W24-1aL LANE SHIFT PICTORIAL

* Where indicated on Plans

All traffic control signs shall be installed and removed daily with the exception of the above construction signs which shall be permanent until all work is complete or as approved by the Resident. During non-working hours, G20-5aP, R2-1 and R2-6aP signs shall be covered so they are not visible to drivers. When the paving operation in a location is completed, the W8-15, W8-15P and 4-9P construction signs shall be removed or covered.

G20-5aP, R2-1 & R2-6aP Construction Signs

There shall be a set of signs (a set consist of two each of G20-5aP, R2-1 and R2-6aP) installed off the edge of pavement on the inside and outside shoulders of both roadways. There shall be a set of signs at approximately every mile:

Beginning at:	Ending at:
Mile 74.5 northbound	Mile 80.7 northbound
Mile 81.1 southbound	Mile 74.9 southbound

4-9P & W8-11 Construction Signs

There shall be one set of signs (a set consist of two each of R4-9P & W8-11) for each area with uneven lanes. Each sign shall be mounted on easels on both sides of the roadway. The R4-9P signs shall be installed 2100 feet beyond the G20-5a, R2-1, and R2-6aP sign sets and the W8-11 signs shall be installed 500 feet beyond the R4-9P sign. These signs shall only be installed whenever there is the possibility of traffic traversing uneven lanes.

Drums shall not be placed in front of easel-mounted construction signs. Easel-mounted signs shall be placed adjacent to the drum line in the closed lane or shoulder, not off the edge of pavement.

652.3.6 Traffic Control

The following paragraph is added:

A Spotter shall be required at the front and rear of the paving operation on the mainline or as approved by the Resident and shall not be measured for payment. All spotters shall be equipped with handheld radios and spare batteries. The spotters will be required to move and maintain drums during the mobile paving operation.

The following Subsection is added:

652.62 Patrol Vehicle

The Contractor shall provide one traffic control vehicle(s) dedicated for traffic control only, with traffic coordinator(s) to be used for erecting, maintaining and dismantling lane closures as directed by the Resident. The traffic control vehicle(s) shall provide continuous patrolling (24-hours/seven days a week) when lane closures are installed (during non-work and work hours) to replace any and all damaged traffic control devices (arrow boards, variable message signs, barrels, signs, etc.). The traffic coordinator(s) shall report any and all disabled motorists, accidents or other unusual occurrences to the Resident, his representative or the Turnpike Authority's communication dispatcher throughout the duration of any and all lane closures.

The traffic control vehicle shall meet the following requirements:

a. In good mechanical condition, clean and presentable at all times.

b. Be equipped with a cellular phone capable of communicating with the Resident, his representative or the Turnpike Authority's communication dispatcher.

c. Be equipped with a mounted revolving amber light or amber strobe light capable of 360-degree visibility to meet all lighting requirements.

d. Be equipped with a light bar (arrow board).

If the proper maintenance of traffic and proper provisions for traffic control are not being provided by the Contractor, the Authority reserves the right to assume maintenance of the traffic control and deduct the cost from any money due or to become due under the Contract. The Authority also reserves the right to suspend all work until the Contractor provides the proper maintenance of traffic and provisions for traffic control to the satisfaction of the Resident.

652.7 Method of Measurement

The second paragraph is deleted and replaced with the following:

Spotters will not be measured separately for payment except as noted, but shall be incidental to Item 652.361, Maintenance of Traffic Control Devices.

The following sentences are added:

The patrol vehicle(s), driver(s), assistant(s) and cellular phone(s) will not be measured separately for payment, but shall be incidental to Item 652.361.

The following is added to the end of the second paragraph:

The Authority will make payment for the State Police officers and vehicles directly to the State Police when utilized for mainline traffic control activities. State Police escorts, if required to move oversize material or equipment loads to the jobsite, will not be paid separately, but shall be incidental to the various pay items.

SPECIAL PROVISION

SECTION 652

MAINTENANCE OF TRAFFIC

(Truck Mounted Attenuator)

Section 652 of the Maine Turnpike Authority 2016 Supplemental Specifications is modified as follows:

652.1 Description

The following paragraph is added:

When a pay item for a Truck Mounted Attenuator (TMA) is included in the contract at least one TMA will be required on the project and its use will be required. The truck mounted attenuator should be utilized in lane closures and other construction operations where workers are exposed to traffic and not protected by other positive means. The Contractor shall manage the utilization and operation of the TMA and if at least one is not used as described above then it will be considered a Traffic Control Plan violation and result in a reduction of payment as outlined in Section 652.

652.2.1 Truck Mounted Attenuator

This section is deleted in its entirety and replaced with the following:

The truck mounted attenuator system shall conform to the following requirements:

- Truck and attached attenuator shall conform to the NCHRP Report 350, Test Level 3 criteria.
- A mounted revolving amber light or amber strobe light with 360-degree visibility.
- An arrow light bar fixed to the vehicle.
- The attenuator shall be mounted to a vehicle with a minimum weight of 10,000 lbs.

652.3.7 Operations

This section is deleted in its entirety and replaced with the following:

The Contractor shall manage the operation of the truck mounted attenuator. The truck mounted attenuator should be utilized in lane closures and other construction operations where workers are exposed to traffic and not protected by positive means. The operation of the vehicle shall be in accordance with the Manual of Uniform Traffic Control Devices and the manufacturer's recommendation.

Installation: The chart below identifies the distance from the work zone or hazard where the TMA shall be deployed. If the work zone is within a marked lane closure, the barrier truck distances shall apply and if the work is mobile, then shadow truck distances shall

apply. The TMA shall not be located in the buffer zone. When used as a barrier, the barrier truck shall be parked in low gear with brakes applied and the front wheels turned away from the work zone and the adjacent traffic lane. For placement details, reference the Manual of Uniform Traffic Control Devices (MUTCD).

Weight of Truck	Barrier Truck Distance from Work Zone of Hazard	Shadow Truck Distance from Work Vehicle or Work Zone
10,000 lbs	250 ft	300 ft
15,000 lbs	200 ft	250 ft
>24,000 lbs	150 ft	200 ft

652.7 Method of Measurement

The last paragraph is deleted and replaced with:

Truck mounted attenuator shall be measured for payment by the calendar day for each calendar day that a unit is used on a travel lane or shoulder on the project, as approved by the resident.

652.8.2 Basis of Payment

The last two paragraphs are deleted and replaced with:

The Truck Mounted Attenuator(s) will be paid for at the Contract unit price per calendar day for each TMA used. This price shall include all costs associated with the use of the vehicle. Payment shall include operator, fuel, truck, maintenance, flashing lights, arrow board and all other incidentals necessary to operate the vehicle.

Payment will be made under:

Pay Item		Pay Unit
652.45	Truck Mounted Attenuator	Calendar Day

SPECIAL PROVISION

SECTION 652

MAINTENANCE OF TRAFFIC

(Automated Speed Limit Sign)

652.1 Description

This special provision provides for furnishing, operating, and maintaining an Automated Trailer Mounted Radar Speed Limit Sign for project use. When a pay item for an Automated Trailer Mounted Radar Speed Limit Sign is included in the Contract at least one will be required on the project when there is a Work Zone Speed Limit in place. The Contractor shall furnish, operate, and maintain the Automated Trailer Mounted Radar Speed Limit Signs during the project operations.

652.1.1 Instruction and maintenance manuals shall be provided.

652.2 Materials

Automated Trailer Mounted Speed Limit Sign

Trailer mounted speed limit signs shall be self-contained units including sign assembly, flashing lights, directional radar to measure speed limits, a regulatory speed limit sign, and power supply specifically constructed to operate as a trailer-mounted sign. The preferred color of the unit shall be “construction orange”.

Signs

Base material for the regulatory speed limit signs shall be weather proof, rigid substrate specifically manufactured for highway signing and meet the retro-reflective sheeting application requirements of the sheeting manufacturer.

Sign text shall consist of the letters, digits and symbols either applied by stick-on or silk screen, to conform to the dimensions and designs indicated in the Contract, MUTCD and/or FHWA Standard Highway Signs. The materials and methods shall be in accordance with standard commercial processes.

“Work Zone” construction signs shall be mounted on the trailer unit above and below the regulatory speed limit sign. (see Appendix

Signs and secondary signs shall follow the MUTCD for minimum mounting heights.

Power supply

The power supply shall be either full battery power with solar panel charging (capable of maintaining a charged battery level) and 135 ampere, 12 volt deep cycle batteries, or diesel powered generator with a fuel capacity sufficient for 10 hours of continuous operation.

Flashing Lights

Each unit shall be equipped with two mono-directional flashing lights, placed in accordance with the MUTCD, with amber lenses and reflectors, which are visible through a range of 120 degrees when viewed facing the sign. The lights, either strobe, halogen, or incandescent lamps, shall be visible for a minimum distance of one mile under daylight conditions and shall have a minimum flash rate of 40 flashes per minute. An "On" indicator light shall be mounted on the back of the signs, which is visible for at least 500 feet to provide confirmation that the flashing lights are operating.

Radar

The directional radar shall monitor approaching traffic only. The radar shall be capable of measuring speeds from 5 to 70 MPH at a distance of up to 1500 feet and shall have a high speed cut off thresh hold.

CONSTRUCTION REQUIREMENTS

652.3.2 Responsibility of the Contractor

The Contractor shall furnish the Automated Trailer Mounted Speed Limit Sign as described in this Special Provision for this project.

All existing speed limit signs, which conflict with the construction zone trailer mounted speed limit signs shall be covered completely when the work zone speed limit is in place.

Automated Trailer Mounted Speed Limit Signs shall only be used when a work zone speed limit is in place. The Contractor shall manage the utilization and operation of the Automated Trailer Mounted Speed Limit Signs and if at least one is not used when work zone speed limits are in place then it will be considered a Traffic Control Plan violation and result in a reduction of payment as outlined in Section 652.

The Resident will record the actual time and location for the signs on a daily basis when the Automated Trailer Mounted Speed Limit Signs are in use.

The Automated Trailer Mounted Radar Speed Limit Sign may be placed as shown on the plans, or may replace the posted regulatory speed limit signs or may be placed at a location within the closed lane that has a reduced speed limit.

Automated Trailer Mounted Speed Limit Signs shall be delineated with retro-reflective temporary traffic control devices while in use and shall also be delineated by affixing a retro-reflective material directly on the trailer.

Upon delivery of the Automated Trailer Mounted Speed Limit Sign and before acceptance by the Authority, the Contractor shall have a representative of the manufacturer review the condition and notify the Resident in writing, of all deficiencies noted.

The Contractor shall arrange to have all necessary repairs performed at no cost to the Authority.

To avoid impairing driver vision, the Contractor shall dim the lighted speed limit readings by 50 percent during nighttime use, and restore full power lighting during daytime operation.

652.7 Method of Measurement

Automated Trailer Mounted Speed Limit Sign shall be measured for payment by the calendar day for each calendar day that the unit is used on a travel lane or shoulder on the project or per each for the continued use for the duration of the project. Payment shall include the Trailer, Radar Speed Limit Sign, flashing beacon amber lights, regulatory speed limit sign, fuel, necessary maintenance, and all checking of Radar Speed Limit Signs by manufacturer and all project moves including the transporting and delivery of the unit.

652.8 Basis of Payment

The Automated Trailer Mounted Speed Limit Sign(s) will be paid for at the Contract unit price per calendar day or per each. This price shall include all costs associated with the use of the Automated Trailer Mounted Speed Limit Sign.

Payment will be made under:

Pay Item		Pay Unit
652.451	Automated Trailer Mounted Speed Limit Sign	Calendar Day
652.452	Automated Trailer Mounted Speed Limit Sign	Each

Appendix B

Automated Trailer Mounted Speed Limit Sign





SIGN #1

1.25" BORDER, 0.75" INDENT,
BLACK ON ORANGE, BB GRADE PLYWOOD SIGN



SIGN #2

1.25" BORDER, 0.75" INDENT,
BLACK ON WHITE, BB GRADE PLYWOOD SIGN

	DIMENSIONS (INCHES) / LETTER FONTS											
	A	B	C	D	E	F	G	H	I	J	K	L
#1	48	20	5D	18⅛	16⅝	14⅞	15⅝	4	2	N/A	N/A	N/A
#2	48	60	8E	16E	38¼	29¼	29½	4⅛	9⅜	9¼	8	6

Date: 2/13/2018

Filename: Trailer Mounted Speed Limit.dgn

MAINE TURNPIKE

HNTB

FEBRUARY 2018

TRAILER MOUNTED CONSTRUCTION ZONE
SPEED LIMIT SIGN

2 OF 2

SPECIAL PROVISION

SECTION 652

MAINTENANCE OF TRAFFIC

(Temporary Portable Rumble Strip)

652.01 Description:

This work consists of furnishing and placing temporary portable rumble strips RoadQuake 2F TPRS or an approved equal.

652.02 Materials:

Furnish a temporary portable rumble strip system, which includes a method to transport and move these to on-site locations where they will be used. The Contractor shall submit for approval, literature and all necessary certifications to the Maine Turnpike prior to procurement of the product.

652.03 General:

If used, Temporary Portable Rumble Strips may not be practicable in areas where the roadway has more than two travel lanes, where volume windows do not allow for breaks in traffic to set up and monitor and adjust, or during night time lane closures.

Placement:

Provide rumble strips where the plans show or as directed by the Resident as follows:

Prior to placing rumble strips, clean the roadway of sand and other materials, that may cause slippage.

Place one end of the rumble strips 6 inches from the roadway centerline. Extend the strips perpendicular to the direction of travel. Ensure strips lay flat on the roadway surface.

Only one series of rumble strips, placed before the first work zone, is required per direction of travel for multiple work zones spaced 1 mile or less apart. Work zones spaced greater than 1 mile apart require a separate series of rumble strips. Each lane shall use one group of temporary rumble strips.

Bracketed “Rumble Strip Ahead” and “Bump” signs shall be utilized and will be paid for under the respective construction sign pay items.

Maintenance:

Maintain rumble strips as follows:

If rumble strips slide, become out of alignment, or are no longer in the wheel path of approaching vehicles during the work period, thoroughly clean both sides of the rumble strips and reset on a clean roadway.

Repair or replace damaged rumble strips immediately.

652.04 Method of Measurement:

The accepted quantity of temporary portable rumble strips shall be measured by the unit complete in place, per lane closure application. A unit shall consist of 1 group of 3 full-lane width of rumble strips. As shown in the plans, a maximum of 3 units may be used at each lane closure. A unit shall be measured for each group of rumble strips, each time they are used for a lane closure.

652.05 Basis of Payment:

The accepted quantity of temporary portable rumble strips will be paid for at the contract unit price per unit which shall include the transport device. Payment is full compensation for providing, relocating, maintaining or replacing, and removing temporary portable rumble strips.

If the pay item is not included in the contract quantities, then the Authority does not anticipate the use of this item on the contract. If contractor wishes to utilize temporary portable rumble strips and the item is not in the contract, then the contractor may propose use of them to the Authority for consideration.

Pay Item		Pay Unit
652.46	Temporary Portable Rumble Strip	Unit

SPECIAL PROVISION

SECTION 719

SIGNING MATERIAL

Section 719.01 Reflective Sheeting

This Subsection is deleted in its entirety and replaced with the following:

Retroreflective sheeting for signs shall meet at a minimum the requirements for ASTM 4956 – Type XI (Prismatic) manufactured by 3M Company, for all signs.

Reflective sheeting, used in sign construction, shall have been manufactured within the six months immediately prior to the fabrication of each sign. Upon delivery at the job site of each shipment of signs, a letter of certification shall be provided that the reflective sheeting conforms to the requirements.

For Type 1 Guide Signs, all reflective sheeting shall be color matched on each sign unit.

All warning signs shall be fluorescent yellow except for Ramp Advisory Speed signs which shall be yellow.

All Construction Series signs that use orange backgrounds shall be fluorescent orange.

All Pedestrian Signs shall be fluorescent yellow-green.

EZ-PASS Purple shall conform to the FHWA Purple color box.

719.02 Demountable High Intensity Reflectorized Letters, Numerals, Symbols, and Borders

This Subsection, including the title, is deleted in its entirety and replaced with the following:

719.02 Direct Applied Reflectorized Letters, Numerals, Symbols, and Borders

Direct applied letters, numerals, symbols and borders shall consist of cut out sheeting that shall meet at a minimum the requirements for ASTM 4956 – Type XI (Prismatic) sheeting. The sheeting material used for the direct applied legend shall be the same type as used for the background.