



# Maine Turnpike Authority *Schedule of Items*

## Superstructure Replacement - Richmond Road (Route 197) Underpass Mile 93.3

Item No.	Description	Quantity	UOM
201.11	Clearing	1.00	AC
202.1	Removing Existing Superstructure - Property of Contractor ( Steel 157,000 lbs; Concrete 280 CY)	1.00	LS
202.12	Removing Existing Structural Concrete	92.00	CY
203.2	Common Excavation	1,900.00	CY
203.24	Common Borrow	2,750.00	CY
203.34	Lightweight Fill	80.00	CY
206.082	Structural Earth Excavation - Major Structures, Plan Quantity	125.00	CY
304.1	Aggregate Subbase Course - Gravel	3,150.00	CY
403.207	Hot Mix Asphalt, 19 mm Nominal Maximum Size	580.00	Ton
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	415.00	Ton
403.209	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	2.00	Ton
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Base and Intermediate Base Course)	415.00	Ton
409.15	Bituminous Tack Coat, Applied	280.00	Gal
419.3	Sawing Bituminous Pavement	46.00	LF
502.219	Structural Concrete, Abutments and Retaining Walls (115 CY)	1.00	LS
502.239	Structural Concrete, Piers (47 CY)	1.00	LS
502.26	Structural Concrete Roadway and Sidewalk Slab on Steel Bridges (226 CY)	1.00	LS
502.31	Structural Concrete Approach Slab (11 CY)	1.00	LS
502.49	Structural Concrete Curbs and Sidewalks (40 CY)	1.00	LS
503.14	Epoxy-Coated Reinforcing Steel, Fabricated and Delivered	107,200.00	LB
503.15	Epoxy-Coated Reinforcing Steel, Placing	107,200.00	LB
504.711	Structural Steel Erection, Supplied by Authority (217,000 lbs)	1.00	LS
505.08	Shear Connectors (3,264 EA)	1.00	LS
507.0821	Steel Bridge Railing, 3 Bar (592 LF)	1.00	LS
508.13	Sheet Waterproofing Membrane (75 SY)	1.00	LS
508.14	High Performance Waterproofing Membrane (795 SY)	1.00	LS
509.202	Culvert Sliplining	1.00	LS
511.07	Cofferdam	1.00	LS
514.06	Curing Box for Concrete Cylinders	1.00	EA
515.201	Pigmented Protective Coating for Concrete Surfaces	380.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	710.00	SY
518.2	Pier Repairs	220.00	SF
518.4	Epoxy Injection Crack Repair	40.00	LF
520.2211	Expansion Device Installation - Gland Seal, Supplied by the Authority	2.00	EA
523.521	Installation of Bearing Devices - Supplied by Authority	20.00	EA



# Maine Turnpike Authority

## Schedule of Items

Item No.	Description	Quantity	UOM
524.4	Protective Shielding - Steel Girders	1,200.00	SY
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (320 LF)	1.00	LS
526.34	Permanent Concrete Transition Barrier	4.00	EA
527.341	Work Zone Crash Cushions - TL-3	2.00	Unit
606.1301	31" W-Beam Guardrail - Mid-Way Splice (7' Steel Posts, 8" Offset Blocks, Single Faced)	1,350.00	LF
606.1307	31" W-Beam Guardrail - Mid-Way Splice Flared Terminal	4.00	EA
606.1723	Bridge Transition - Type III	4.00	EA
606.353	Reflectorized Flexible Guardrail Marker	8.00	EA
606.3605	Guardrail - Remove, Modify, and Reset Single Rail	540.00	LF
607.17	Chain Link Fence - 6 Foot	370.00	LF
607.183	Chain Link Snow Fence	304.00	LF
607.23	Chain Link Fence Gate	2.00	EA
607.32	Bracing Assembly Type I - Metal Posts	8.00	EA
607.33	Bracing Assembly Type II - Metal Posts	8.00	EA
610.08	Plan Riprap	61.00	CY
610.181	Temporary Stone Check Dam	2.00	CY
613.319	Erosion Control Blanket	3,850.00	SY
615.07	Loam	360.00	CY
618.14	Seeding Method Number 2	57.00	Unit
619.1201	Mulch, Plan Quantity	57.00	Unit
619.1202	Temporary Mulch	1.00	LS
619.14	Erosion Control Mix	490.00	CY
620.58	Erosion Control Geotextile	200.00	SY
627.733	4" White or Yellow Painted Pavement Marking Line	4,500.00	LF
629.05	Hand Labor, Straight Time	30.00	HR
631.1	Air Compressor (including operator)	30.00	HR
631.11	Air Tool (including operator)	30.00	HR
631.12	All Purpose Excavator (including operator)	30.00	HR
631.172	Truck - large (including operator)	30.00	HR
631.32	Culvert Cleaner (including operators)	10.00	HR
631.36	Foreman	10.00	HR
639.18	Field Office, Type A	1.00	EA
652.3	Flashing Arrow	2.00	EA
652.312	Type III Barricades	4.00	EA
652.33	Drum	70.00	EA
652.34	Cone	70.00	EA



# Maine Turnpike Authority

## *Schedule of Items*

Item No.	Description	Quantity	UOM
652.35	Construction Signs	960.00	SF
652.361	Maintenance of Traffic Control Devices (244 CD)	1.00	LS
652.41	Portable-Changeable Message Sign	2.00	EA
652.45	Truck Mounted Attenuator	200.00	CD
652.452	Automated Trailer Mounted Speed Limit Sign	2.00	EA
656.5	Baled Hay, in place	10.00	EA
656.6	Temporary Berms	100.00	LF
656.62	Temporary Slope Drains	100.00	LF
656.632	30 inch Temporary Silt Fence	2,020.00	LF
659.1	Mobilization	1.00	LS