



Maine Turnpike Authority

Schedule of Items

Bridge Repairs - Various Locations & EVR - Littlefield Road

Item No.	Description	Quantity	UOM
201.11	Clearing	0.55	AC
201.23	Removing Single Tree Top Only	2.00	EA
201.24	Removing Stump	2.00	EA
202.1211	Removing Existing Girder Haunches	6,360.00	LF
202.122	Removing Existing Structural Concrete	50.00	SF
202.202	Removing Pavement Surface	8,580.00	SY
202.203	Pavement Butt Joints	200.00	SY
203.2	Common Excavation	2,110.00	CY
203.24	Common Borrow	100.00	CY
203.25	Granular Borrow	155.00	CY
304.1	Aggregate Subbase Course-Gravel	1,090.00	CY
304.14	Aggregate Base Course - Type A	340.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size (Base)	270.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size (Surface)	1,067.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	447.00	GAL
419.3	Sawing Bituminous Pavement	360.00	LF
502.702	Replace Bridge Drain (Type A1)	25.00	EA
502.703	Replace Bridge Drain (Type B)	6.00	EA
506.14	Field Painting of Existing Structural Steel (Ramp H)	1.00	LS
508.141	High Performance Waterproofing Membrane (Rt 236)	1.00	LS
508.142	High Performance Waterproofing Membrane (Ramp J)	1.00	LS
508.143	High Performance Waterproofing Membrane (Ramp H)	1.00	LS
508.144	High Performance Waterproofing Membrane (Wilson Rd)	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	2,910.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	2,060.00	SY
518.1	Abutment Repairs	1,030.00	SF
518.2	Pier Repairs	25.00	SF
518.391	Repairing Granite Curb Joint and Bedding Mortar	2,938.00	LF
518.4	Epoxy Injection Crack Repair	210.00	LF
518.48	Reseal Joints	125.00	LF
518.7	Repair of Overhead Surfaces < 8 inches	105.00	SF
518.75	Fascia and Overhang Repairs	157.00	SF
518.76	Partial Concrete Curb Reconstruction	280.00	LF
518.8	Partial Depth Concrete Deck Repairs	1,635.00	SF
518.81	Full Depth Concrete Deck Repairs	190.00	SF
518.92	Slope Protection Repairs	270.00	LF
518.921	Slope Protection Concrete Repairs	80.00	SF



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
518.93	Parapet Repairs	110.00	SF
518.94	Parapet Surface Repairs	361.00	LF
520.231	Asphaltic Plug Joint (Route 236)	100.00	LF
520.232	Asphaltic Plug Joint (Spruce Creek NB)	125.00	LF
520.233	Asphaltic Plug Joint (Spruce Creek SB)	125.00	LF
520.234	Expansion Device - Silicone Coated and Pre-Compressed Seal	331.00	LF
520.24061	Bridge Joint Modification (Ramp H)	1.00	LS
520.24062	Bridge Joint Modification (Littlefield Rd)	1.00	LS
520.2407	Bridge Joint Steel Modification	4.00	EA
520.51	Remove and Replace Gland Seal (Wilson Rd)	2.00	EA
520.52	Remove and Replace Gland Seal (RT 236)	1.00	EA
523.1201	Reset Steel Bearings	7.00	EA
523.521	Bearing Removal and Installation	4.00	EA
523.5301	Steel Bearings, Fixed, Sliding Plate	2.00	EA
523.5302	Steel Bearings, Expansion, Sliding Plate	2.00	EA
524.4	Protective Shielding - Steel Girders	179.00	SY
524.72121	Jacking Existing Superstructure (Route 236)	1.00	LS
524.72122	Jacking Existing Superstructure (Ramp J)	1.00	LS
524.72123	Jacking Existing Superstructure (Spruce Creek)	1.00	LS
603.179	18 inch Culvert Pipe Option III	118.00	LF
606.1723	Bridge Transition Type 1	2.00	EA
606.24	Guardrail Type 3d - Single Rail	12.50	LF
606.242	Guardrail Type 3d - Over 15 foot Radius	25.00	LF
606.265	Terminal End-Single Rail - Galvanized Steel	1.00	EA
606.278	Terminal End - Anchored End	1.00	EA
606.353	Reflectorized Flexible Guardrail Marker	2.00	EA
606.3562	Delineator Post - Remove and Stack	1.00	EA
606.369	Guardrail - Remove and Stack	25.00	LF
607.17	Chain Link Fence - 6 foot	40.00	LF
607.2325	Pipe Entry Gate	2.00	EA
607.2326	Remove Chain Link Gate	1.00	EA
607.32	Bracing Assembly Type I - Metal Posts	4.00	EA
607.33	Bracing Assembly Type II - Metal Posts	2.00	EA
609.11	Vertical Curb Type 1	35.00	LF
610.08	Plain Riprap	15.00	CY
610.181	Temporary Stone Check Dam	14.00	CY
613.319	Erosion Control Blanket	768.00	SY



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
615.07	Loam	430.00	CY
618.14	Seeding Method Number 2	36.00	UNIT
619.1201	Mulch - Plan Quantity	36.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	57.00	SY
626.15	Electrical Service Box	1.00	EA
627.712	White or Yellow Pavement Marking Line	6,600.00	LF
629.05	Hand Labor, Straight Time	230.00	HR
631.1	Air Compressor (including operator)	200.00	HR
631.11	Air Tool (including operator)	200.00	HR
631.12	All Purpose Excavator (including operator)	230.00	HR
631.171	Truck - small (including operator)	230.00	HR
631.36	Foreman	230.00	HR
634.1612	Removal of Bridge & Highway Lighting Including Wire	1.00	LS
639.19	Field Office, Type B	1.00	EA
645.109	Remove and Reset Sign	5.00	EA
645.271	Regulatory, Warning, Confirmation and Route Assembly Sign, Type 1	33.00	SF
652.39	Work Zone Traffic Control	1.00	LS
656.5	Baled Hay, in place	30.00	EA
656.632	30 inch Temporary Silt Fence	1,620.00	LF
656.75	Temporary Soil Erosion and Water Pollution Control	1.00	LS
659.1	Mobilization	1.00	LS
830.17	Utility Conduit Hanger System Hardware	1.00	LS