



Maine Turnpike Authority

Schedule of Items

Crosby Maintenance Office Building

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE	2,300.00	SY
202.81	REMOVING STRUCTURES AND OBSTRUCTIONS	1.00	LS
203.2	COMMON EXCAVATION	3,075.00	CY
203.25	GRANULAR BORROW	300.00	CY
203.2312	HEALTH AND SAFETY PLAN	1.00	LS
203.2333	DISPOSAL AND TREATMENT OF SPECIAL EXCAVATION	50.00	CY
203.234	TREATMENT OR DISPOSAL OF CONTAMINATED GROUNDWATER	500.00	GAL
203.35	CRUSHED STONE 3/4 INCH	150.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	1,100.00	CY
304.105	STRUCTURAL FILL	1,475.00	CY
304.14	AGGREGATE BASE COURSE - TYPE A	550.00	CY
403.207	HOT MIX ASPHALT - 19.0 MM NOMINAL MAXIMUM SIZE	350.00	TON
403.208	HOT MIX ASPHALT - 12.5 MM NOMINAL MAXIMUM SIZE	200.00	TON
403.209	HOT MIX ASPHALT - 9.5 MM NOMINAL MAXIMUM SIZE	50.00	TON
409.15	BITUMINOUS TACK COAT RS-1 or RS1h - APPLIED	375.00	GAL
419.3	SAWCUT BITUMINOUS PAVEMENT	325.00	LF
502.701	CONCRETE EQUIPMENT PAD	1.00	EA
502.702	CONCRETE PROPANE TANK PAD	1.00	EA
604.15	MANHOLE	1.00	EA
604.151	MANHOLE COVER 57" INTERIOR DIAMETER	1.00	EA
604.158	UTILITY VAULT - 4' X 6'	2.00	EA
605.072	4 INCH PERFORATED SDR-35 UNDERDRAIN	375.00	LF
606.356	UNDERDRAIN DELINATOR POST	1.00	EA
615.07	LOAM	325.00	CY
618.14	SEEDING METHOD NUMBER 2	17.00	UNIT
619.1201	MULCH - PLAN QUANTITY	17.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	1,800.00	SY
629.05	HAND LABOR, STRAIGHT TIME	40.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	40.00	HR
631.172	TRUCK-LARGE (INCLUDING OPERATOR)	40.00	HR
631.221	SMALL FRONT END LOADER (INCLUDING OPERATOR)	20.00	HR
631.36	FOREMAN	20.00	HR
633.031	PROPANE SERVICE	1.00	LS
634.1943	4" SCHEDULE 80 PVC CONDUIT	125.00	LF
634.1945	2" SCHEDULE 80 PVC CONDUIT	925.00	LF
634.1946	3" SCHEDULE 80 PVC CONDUIT	350.00	LF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
634.3122	#2/0 COPPER WIRE - 12 KV RATED (4 WIRE)	275.00	LF
634.3152	#4 GND WIRE	275.00	LF
634.3153	#6 GND WIRE	125.00	LF
634.3335	MANHOLE - FIBER OPTIC - STANDARD	2.00	EA
639.19	FIELD OFFICE, TYPE B	1.00	EA
656.632	SILT FENCE	370.00	LF
659.1	MOBILIZATION	1.00	LS
670.1	SUBSURFACE WASTEWATER DISPOSAL SYSTEM	1.00	LS
800.01	CROSBY MAINTENANCE OFFICE BUILDING	1.00	LS
801.14	4 INCH PVC SANITARY SEWER	15.00	LF
822.322	6 INCH CLASS 52 DUCTILE IRON WATER MAIN	30.00	LF
822.34	8 INCH CLASS 52 DUCTILE IRON WATER MAIN	500.00	LF
823.325	8 INCH GATE VALVE	5.00	EA
823.331	6 INCH GATE VALVE	1.00	EA
824.32	REMOVE/RESET HYDRANT	1.00	EA
825.3355	2 INCH GATE VALVE WITH BOX	3.00	EA
825.423	2 INCH HDPE CTS	250.00	LF
825.4311	1 1/2 INCH HDPE CTS	75.00	LF