



Maine Turnpike Authority

Schedule of Items

Slope & Drainage Repairs

MM 0.0 to 109.1

Item No.	Description	Quantity	UOM
203.2	Common Excavation	35.00	CY
304.1	Aggregate Subbase Course Gravel	25.00	CY
459.06	Bituminous Concrete Waterway, Type I	2.00	EA
602.4	Pumped Grout Fill	3.00	CY
603.159	12 inch Culvert Pipe Option III	154.00	LF
603.229	42 inch Culvert Pipe Option III	14.00	LF
603.28	Concrete Collar	2.00	EA
604.242	Catch Basin Type F3	1.00	EA
604.244	Catch Basin Type F4	1.00	EA
610.08	Plain Riprap	55.00	CY
613.319	Erosion Control Blanket	1,000.00	SY
615.07	Loam	18.00	CY
618.1401	Seeding Method Number 2, Plan Quantity	5.00	UNIT
619.1201	Mulch, Plan Quantity	5.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	95.00	SY
629.05	Hand Labor, Straight Time	10.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.172	Truck - Large (including operator)	10.00	HR
631.36	Foreman	10.00	HR
631.37	Earthwork Crew (slope/pipe repairs)	24.00	HR
656.5	Baled Hay, in place	15.00	EA
656.632	30 inch Temporary Silt Fence	50.00	LF
659.1	Mobilization	1.00	LS
659.101	Mobilization (crew)	3.00	Shift
659.102	Mobilization (lowbed equipment)	5.00	HR