



Maine Turnpike Authority *Schedule of Items*

Maine Turnpike Toll Tunnel Repairs New Gloucester - Mile 67.0 & West Gardiner - Mile 100.2

Item No.	Description	Quantity	UOM
515.203	Broadcast Sealant for Concrete Surfaces	1,910.00	SY
518.4	Epoxy Injection Crack Repair	200.00	LF
518.511	Repair of Concrete Surfaces - Stairwell Steps	1.00	LS
518.512	Repair of Concrete Surfaces - Stairwell Grinding	4.00	EA
518.513	Repair of Concrete Surfaces - Stairwell Landing	4.00	EA
518.514	Tollbooth Blockout Sealing	10.00	EA
526.306	Temporary Concrete Barrier, Type I - Supplied by Authority (600 LF)	1.00	LS
527.341	Work Zone Crash Cushions - TL-3	1.00	UNIT
631.53	Electrician	80.00	HR
631.54	Electrician's Apprentice	80.00	HR
652.361	Maintenance of Traffic Control Devices	1.00	LS
655.1004	#4/0 AWG Wire	130.00	LF
655.101	#6 AWG Wire	700.00	LF
655.103	#10 AWG Wire	200.00	LF
655.12	#12 AWG Wire	1,880.00	LF
655.141	4pr/24 (Category 5e) Cable	1,700.00	LF
655.2021	1" Sch 80 PVC Conduit	150.00	LF
655.203	1 1/2" Sch 80 PVC Conduit	140.00	LF
655.2031	2" Sch 80 PVC Conduit	90.00	LF
655.2032	2 1/2" Sch 80 PVC Conduit	230.00	LF
655.2101	1-1/2" Liquid Tight Metallic Flexible Conduit	300.00	LF
655.2102	2" Liquid Tight Metallic Flexible Conduit	250.00	LF
655.2103	1" Liquid Tight Metallic Flexible Conduit	100.00	LF
655.225	Type F Pull Box	1.00	EA
655.227	Type H Pull Box	3.00	EA
655.228	Type I Pull Box	1.00	EA
655.431	60 AMP Panel Board and Cabinet	4.00	EA
655.432	100 AMP Panel Board and Cabinet	6.00	EA
655.433	225 AMP Panel Board and Cabinet	1.00	EA
655.501	1" PVC Conduit Condulets	2.00	EA
655.502	1 1/2" PVC Conduit Condulets	2.00	EA
655.503	2" PVC Conduit Condulets	2.00	EA
655.5031	2 1/2" PVC Conduit Condulets	2.00	EA
655.63	4"x4" Plastic NEMA 4R Raceway	55.00	LF
655.64	6"x6" Plastic NEMA 4R Raceway	715.00	LF
655.82	Duplex Receptacle	1.00	EA
655.84	Quadplex Receptacle	3.00	EA



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
659.1	Mobilization	1.00	LS
800.31	Stairwell Enclosure	1.00	LS
800.32	Tollbooth Canopy Drainage Modifications	1.00	LS
800.33	Heating, Ventilation, and Dehumidification	1.00	LS