



Maine Turnpike Authority

Schedule of Items

Auburn Vehicle Storage Garage Mile 76.9

Item No.	Description	Quantity	UOM
202.081	Removing Buildings	1.00	LS
202.082	Removing Generator	1.00	EA
202.202	Removing Pavement Surface	3,200.00	SY
203.2	Common Excavation	3,100.00	CY
203.2312	Health and Safety Plan	1.00	LS
203.2333	Disposal/Treatment of Special Excavation	50.00	TON
203.2334	Disposal/Treatment of Groundwater	500.00	GAL
203.25	Granular Borrow	25.00	CY
203.35	Crushed Stone 3/4-Inch	10.00	CY
304.1	Aggregate Subbase Course - Gravel	210.00	CY
304.105	Structural Fill	1,570.00	CY
304.14	Aggregate Base Course - Type A	640.00	CY
403.207	Hot Mix Asphalt, 19.0 mm Nominal Maximum Size	560.00	TON
403.208	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size	890.00	TON
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size	50.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h - Applied	450.00	GAL
419.3	Sawing Bituminous Pavement	1,100.00	LF
424.3231	Asphalt Rubber Mastic Crack Sealer - Applied	690.00	LB
502.701	Concrete Generator Pad	1.00	EA
502.702	Concrete Propane Tank Pad	2.00	EA
502.703	Concrete Electrical Building Pad	1.00	EA
603.04	4 Inch PVC Pipe	80.00	LF
603.165	15 inch Reinforced Concrete Pipe - Class III	160.00	LF
604.158	6000 Gallon Holding Tank	1.00	EA
604.1581	Remove and Reset 6000 Gallon Holding Tank	1.00	EA
604.401	Remove and Reset Oil / Water Separator	1.00	EA
605.072	4 Inch Perforated SDR-35 Underdrain	450.00	LF
606.356	Underdrain Delineator Post	2.00	EA
610.18	Stone Ditch Protection	70.00	CY
615.07	Loam	290.00	CY
618.14	Seeding Method Number 2	22.00	UNIT
619.1201	Mulch - Plan Quantity	22.00	UNIT
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	420.00	SY
626.112	Heavy Duty Precast Concrete Junction Box	3.00	EA
629.05	Hand Labor, Straight Time	40.00	HR
631.12	All Purpose Excavator (including operator)	40.00	HR



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
631.172	Truck-large (including operator)	40.00	HR
631.221	Small Front End Loader (including operator)	20.00	HR
631.36	Foreman	20.00	HR
633.031	Propane Service	1.00	LS
639.19	Field Office, Type B	1.00	EA
655.1004	#4/0 AWG Wire	1,300.00	LF
655.102	#2 AWG Wire	750.00	LF
655.103	#3 AWG Wire	250.00	LF
655.104	#4 AWG Wire	3,240.00	LF
655.108	#8 AWG Wire	3,925.00	LF
655.111	500 KCMIL Wire	750.00	LF
655.112	250 KCMIL Wire	120.00	LF
655.2021	1" Schedule 80 PVC Conduit	1,900.00	LF
655.2022	1.25" Schedule 80 PVC Conduit	1,175.00	LF
655.2031	2" Schedule 80 PVC Conduit	1,100.00	LF
655.2041	3" Schedule 80 PVC Conduit	290.00	LF
656.632	30 Inch Temporary Silt Fence	920.00	LF
659.1	Mobilization	1.00	LS
800.01	Auburn Vehicle Storage Garage	1.00	LS
825.423	2 inch HDPE Plastic Service	350.00	LF
825.4311	1-1/4 inch HDPE Plastic Service	110.00	LF
832.41	Type A Steel Site Bollard	9.00	EA