



Maine Turnpike Authority *Schedule of Items*

Ramp Improvements - Biddeford Exit 32 Mile 31.6

Item No.	Description	Quantity	UOM
202.202	REMOVING PAVEMENT SURFACE	1,450.00	SY
203.2	COMMON EXCAVATION	4,250.00	CY
203.25	GRANULAR BORROW	230.00	CY
304.1	AGGREGATE SUBBASE COURSE - GRAVEL	1,650.00	CY
304.14	AGGREGATE BASE COURSE - TYPE A	410.00	CY
403.207	HOT MIX ASPHALT, 19.0 mm NOMINAL MAXIMUM SIZE	330.00	TON
403.2081	HOT MIX ASPHALT, 12.5 mm (POLYMER MODIFIED) - RAP	300.00	TON
403.211	HOT MIX ASPHALT, 9.5 mm NOMINAL MAXIMUM SIZE (SHIMMING)	10.00	TON
403.213	HOT MIX ASPHALT, 12.5 mm (BASE AND INTERMEDIATE BASE COURSE)	470.00	TON
409.15	BITUMINOUS TACK COAT RS-1 OR RS1H - APPLIED	430.00	GAL
419.3	SAWING BITUMINOUS PAVEMENT	2,050.00	LF
526.306	TEMPORARY CONCRETE BARRIER, TYPE I - SUPPLIED BY THE AUTHORITY (1040 LF)	1.00	LS
527.341	WORK ZONE CRASH CUSHIONS TL-3	1.00	UNIT
603.175	18 INCH REINFORCED CONCRETE PIPE - CLASS III	32.00	LF
603.195	24 INCH REINFORCED CONCRETE PIPE - CLASS III	12.00	LF
603.28	CONCRETE COLLAR	2.00	EA
606.13	31" W-BEAM GUARDRAIL - MID-WAY SPLICE (7' STEEL POSTS, 8" OFFSET BLOCKS, SINGLE FACED)	820.00	LF
606.1307	31" W-BEAM GUARDRAIL - MID-WAY SPLICE FLARED TERMINAL	2.00	EA
606.353	REFLECTORIZED FLEXIBLE GUARDRAIL MARKER	4.00	EA
606.356	UNDERDRAIN DELINEATOR POST	15.00	EA
606.3621	GUARDRAIL ADJUST, SINGLE RAIL	60.00	LF
606.3622	GUARDRAIL ADJUST, DOUBLE RAIL	75.00	LF
610.08	PLAIN RIPRAP	14.00	CY
610.181	TEMPORARY STONE CHECK DAM	12.00	CY
613.319	EROSION CONTROL BLANKET	3,250.00	SY
615.07	LOAM	860.00	CY
618.14	SEEDING METHOD NUMBER 2	70.00	UNIT
619.1201	MULCH - PLAN QUANTITY	70.00	UNIT
619.1202	TEMPORARY MULCH	1.00	LS
620.58	EROSION CONTROL GEOTEXTILE	51.00	SY
626.122	QUAZITE JUNCTION BOX (18X11)	3.00	EA
626.21	METALLIC CONDUIT	5.00	LF
626.22	NON-METALLIC CONDUIT	760.00	LF
626.31	18 INCH DIAMETER FOUNDATION	2.00	EA
627.73	TEMPORARY 6 INCH PAVEMENT MARKING TAPE	430.00	LF
627.77	REMOVING EXISTING PAVEMENT MARKING	1,000.00	SF



Maine Turnpike Authority *Schedule of Items*

Item No.	Description	Quantity	UOM
627.78	TEMPORARY PAVEMENT MARKING LINE, WHITE OR YELLOW	6,450.00	LF
629.05	HAND LABOR, STRAIGHT TIME	40.00	HR
631.12	ALL PURPOSE EXCAVATOR (INCLUDING OPERATOR)	20.00	HR
631.133	SKID STEER (INCLUDING OPERATOR)	20.00	HR
631.172	TRUCK - LARGE (INCLUDING OPERATOR)	20.00	HR
631.22	FRONT END LOADER (INCLUDING OPERATOR)	20.00	HR
631.32	CULVERT CLEANER (INCLUDING OPERATOR)	20.00	HR
631.36	FOREMAN	40.00	HR
631.53	ELECTRICIAN	40.00	HR
631.54	ELECTRICIAN'S APPRENTICE	40.00	HR
645.1099	REMOVE AND DISPOSE SIGN	1.00	EA
645.161	BREAKAWAY DEVICE SINGLE POLE	1.00	EA
645.271	REGULATORY, WARNING, CONFIRMATION, AND ROUTE ASSEMBLY SIGN, TYPE 1	28.00	SF
645.289	STEEL H-BEAM POLES	260.00	LB
652.3	FLASHING ARROW	1.00	EA
652.312	TYPE III BARRICADES	6.00	EA
652.35	CONSTRUCTION SIGNS	780.00	SF
652.361	MAINTENANCE OF TRAFFIC CONTROL DEVICES	1.00	LS
652.41	PORTABLE-CHANGEABLE MESSAGE SIGN	7.00	EA
652.4502	TRUCK MOUNTED ATTENUATOR	1.00	EA
652.4503	TRUCK MOUNTED ATTENUATOR	4.00	WEEK
652.47	SEQUENTIAL FLASHING WARNING LIGHTS	30.00	EA
656.5	BALED HAY, IN-PLACE	10.00	EA
656.632	30" TEMPORARY SILT FENCE	1,550.00	LF
659.1	MOBILIZATION	1.00	LS