



Maine Turnpike Authority

Schedule of Items

Exit 45 Interchange Paving

Item No.	Description	Quantity	UOM
202.202	Removing Pavement Surface	4,350.00	SY
202.22	Grooved Pavement Strips	380.00	LF
203.24	Common Borrow	410.00	CY
304.14	Aggregate Base Course - Type A	17.00	CY
403.207	Hot Mix Asphalt 19.0 mm Nominal Maximum Size	950.00	TON
403.208	Hot Mix Asphalt 12.5 mm Nominal Maximum Size	370.00	TON
403.212	Hot Mix Asphalt, 4.75 mm Nominal Maximum Size	80.00	TON
403.213	Hot Mix Asphalt, 12.5 mm Nominal Maximum Size(Base and Intermediate Base course)	240.00	TON
409.15	Bituminous Tack Coat RS1 or RS1H - Applied	500.00	GAL
470.08	Berm Dropoff Correction - Grindings	10.00	TON
520.232	Asphaltic Plug Joint - Exit 45	130.00	LF
520.233	Asphaltic Plug Joint - Exit 47	100.00	LF
610.08	Plain Riprap	20.00	CY
615.07	Loam	230.00	CY
618.14	Seeding Method Number 2	19.00	UNIT
619.1201	Mulch - Plan Quantity	19.00	UNIT
619.1202	Temporary Mulch	1.00	LS
626.122	Quazite Junction Box (18x11)	6.00	EA
626.22	Non-metallic Conduit	350.00	LF
627.712	White Or Yellow Painted Pavement Marking Line	2,100.00	LF
627.745	6" White or Yellow Polyurea Pavement Marking Line	1,350.00	LF
627.812	Temporary Raised Pavement Markers	500.00	EA
627.944	Pavement Markings - Recessed Tape - Words, Arrows, Stop Bars	210.00	SF
629.05	Hand Labor, Straight Time	20.00	HR
631.1	Air Compressor (including operator)	10.00	HR
631.11	Air Tool (including operator)	10.00	HR
631.12	All Purpose Excavator (including operator)	10.00	HR
631.133	Skid Steer (including operator)	10.00	HR
631.172	Truck-large (including operator)	20.00	HR
645.305	Sign Mounted Beacon Array	1.00	LS
645.511	36" x 48" Radar Activated Flashing LED Right Chevron Warning Signs	5.00	EA
652.361	Maintenance of Traffic Control Devices - Exit 45	1.00	LS
652.3611	Maintenance of Traffic Control Devices - Exit 47	1.00	LS
652.41	Portable - Changeable Message Sign	4.00	EA
652.45	Truck Mounted Attenuator	2.00	EA
656.5	Baled Hay, In Place	5.00	EA



Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
656.632	30 Inch Temporary Silt Fence	700.00	LF
659.1	Mobilization	1.00	LS