



Maine Turnpike Authority

Schedule of Items

Emergency Vehicle Ramp - Southbound Captain Thomas Road Mile Marker 14.8

Item No.	Description	Quantity	UOM
201.11	Clearing	0.40	AC
203.2	Common Excavation	600.00	CY
203.21	Rock Excavation	240.00	CY
203.24	Common Borrow	170.00	CY
203.25	Granular Borrow	20.00	CY
304.1	Aggregate Base Course - Gravel	460.00	CY
304.14	Aggregate Base Course - Type A	130.00	CY
403.208	Hot Mix Asphalt - 12.5 MM Nom. Max. Size (Surface)	64.00	Ton
403.213	Hot Mix Asphalt - 12.5 MM Nom. Max. Size (Base)	110.00	Ton
409.15	Bituminous Tack Coat RS-1 or RS-1h, Applied	31.00	GA
419.3	Saw Cutting Bituminous Pavement	190.00	LF
603.179	18" Culvert Pipe OPT III	91.00	LF
606.3561	Delineator Post - Remove and Reset	1.00	EA
607.17	Chain Link Fence - 6 Ft	40.00	LF
607.32	Bracing Assembly Type I - Metal Posts	3.00	EA
607.33	Bracing Assembly Type II - Metal Posts	1.00	EA
610.08	Plain Riprap	11.00	CY
610.181	Temporary Stone Check Dam	8.00	CY
613.319	Erosion Control Blanket	480.00	SY
615.07	Loam	140.00	CY
618.14	Seeding Method Number 2	11.00	Unit
619.1201	Mulch - Plan	11.00	Unit
619.1202	Temporary Mulch	1.00	LS
620.58	Erosion Control Geotextile	20.00	SY
629.05	Hand Labor, Straight Time	20.00	HR
631.12	All Purpose Excavator (Including operator)	20.00	HR
631.171	Truck - Small (Including operator)	40.00	HR
631.36	Foreperson	16.00	HR
645.271	Regulatory, Warning, Confirmation and Route Marker Assembly Sign, Type 1	36.00	SF
652.361	Maintenance of Traffic Control Devices	1.00	LS
652.38	Flaggers	200.00	HR
656.5	Baled Hay, In Place	15.00	EA
656.632	30" Temporary Silt Fence	830.00	LF
659.1	Mobilization	1.00	LS