



Maine Turnpike Authority *Schedule of Items*

Bridge Repairs - Broadturn Road Underpass (MM 39.90) I-295 Southbound Underpass (MM 44.30) Maine Mall Road Underpass (MM 44.91)

Item No.	Description	Quantity	UOM
202.1211	Removing Existing Girder Haunches	2,050.00	LF
202.202	Removing Pavement Surface	5,650.00	SY
403.2081	Hot Mix Asphalt, 12.5 mm (Polymer/Latex Modified)	476.00	TON
403.209	Hot Mix Asphalt, 9.5 mm Nominal Maximum Size (sidewalks, drives, islands & incidentals)	2.00	TON
403.211	Hot Mix Asphalt, Shimming	89.00	TON
409.15	Bituminous Tack Coat RS-1 or RS1h- Applied	271.00	GAL
502.7011	Weep Drain Extensions with Brace	21.00	EA
506.14	Field Painting of Existing Structural Steel	1.00	LS
515.201	Pigmented Protective Coating for Concrete Surfaces	660.00	SY
515.202	Clear Protective Coating for Concrete Surfaces	1,120.00	SY
515.203	Broadcast Sealant for Concrete Surfaces	270.00	SY
518.1	Abutment Repairs	35.00	SF
518.2	Pier Repairs	245.00	SF
518.4	Epoxy Injection Crack Repair	231.00	LF
518.43	Parapet Joint Repair	180.00	LF
518.7	Repair of Overhead Surfaces < 8 inches	5.00	SF
518.75	Fascia and Overhang Repairs	440.00	SF
518.865	Elastomeric Concrete	410.00	CF
518.866	Concrete Header Repair	20.00	CF
520.234	Expansion Device - Silicone Coated and Pre-Compressed Seal	200.00	LF
523.521	Bearing Removal and Installation	4.00	EA
523.5304	Steel Bearings, Expansion, Rocker	4.00	EA
524.4	Protective Shielding - Steel Girders	380.00	SY
524.7212	Jacking Existing Superstructure (I-295 Southbound Underpass)	1.00	LS
627.712	White or Yellow Pavement Marking Line	5,350.00	LF
627.73	Temporary 6 Inch Pavement Marking Tape	690.00	LF
627.75	White or Yellow Pavement & Curb Marking	71.00	SF
627.77	Removing Existing Pavement Marking	620.00	SF
627.78	Temporary Pavement Marking Line, White or Yellow	6,050.00	LF
627.812	Temporary Raised Pavement Markers	219.00	EA
629.05	Hand Labor, Straight Time	120.00	HR
631.1	Air Compressor (including operator)	120.00	HR
631.11	Air Tool (including operator)	120.00	HR
631.112	Welding Machine (including operator)	80.00	HR
631.36	Foreman	120.00	HR
643.72	Temporary Traffic Signal: Broadturn Road	1.00	LS



Contract ID: 2026.05
Contract Type: Contract

Maine Turnpike Authority

Schedule of Items

Item No.	Description	Quantity	UOM
652.3611	Maintenance of Traffic Control Devices (Broadturn Road)	1.00	LS
652.3612	Maintenance of Traffic Control Devices (I-295 Southbound)	1.00	LS
652.3613	Maintenance of Traffic Control Devices (Maine Mall Road)	1.00	LS
656.75	Temporary Soil Erosion and Water Pollution Control	1.00	LS
659.1	Mobilization	1.00	LS